

# MARINE REVIEW

Entered at Cleveland Post Office as Second-class Mail Matter.

VOL. XXIV.

Published every Thursday at 418-19 Perry-Payne Bldg., by the Marine Review Pub. Co.

CLEVELAND, O., AUG. 15, 1901.

Subscription \$3.00 a year.  
Foreign \$4.50 a year.

No. 7

## CONTRACTS CLOSED FOR TWO MORE VESSELS.

Contracts were closed on Tuesday with the American Ship Building Co. for two new freighters—one of 5,500 tons capacity and the other of 6,200 tons capacity—by the National Transportation Co., of which Capt. W. W. Brown of Cleveland is to be the general manager. In addition, the company purchased the three boats which the ship building company is now building for the Mutual Steamship Co. These three vessels are of 4,800 tons capacity but it was decided to lengthen one of them 24 ft., which will give her a capacity of 5,200 tons. It was the original intention of the National Transportation Co. to place an order for five new vessels, but with all the berths in the different plants of the ship building company filled General Manager Wallace was unable to take an order for five vessels for delivery in April, 1902. Negotiations were therefore begun for the freighters building for the Mutual Steamship Co. This company was organized by the late William Fitzgerald, and since his death the stockholders had decided to dispose of the boats should a favorable opportunity offer. This transaction will enable the National Transportation Co. to come out at the opening of the season with a fleet comprising two vessels of 4,800 tons capacity, one of 5,200 tons, one of 5,500 tons and one of 6,200 tons, or a combined capacity of 26,500 tons per trip. This makes a total of nineteen freighters and three passenger steamers which the American Ship Building Co. has under contract and constitutes more tonnage than was ever ordered in one season before. The combined carrying capacity in a single trip of the nineteen freighters on 18 ft. draught is 104,000 gross tons.

The National Transportation Co. is the same company the prospectus of which was lately issued in Chicago. At that time it was the intention to incorporate it on a basis of \$5,000,000 and to build ten steamers. Mr. Charles Counselman of Chicago and Mr. W. H. Prime, well known in marine insurance circles, were to be heavily interested with Mr. Lyman C. Smith of Syracuse, N. Y. Mr. Counselman and Mr. Prime, having other extensive interests to look after, decided later not to join in the enterprise. Capt. W. W. Brown, who has been identified with Mr. Smith in a number of undertakings, then went ahead and organized the company upon a basis of \$2,500,000 and cut the number of vessels to five. The company was organized at Syracuse, N. Y., this week and will be incorporated under the laws of New Jersey. Lyman C. Smith of Syracuse will be president, Capt. W. W. Brown of Cleveland secretary and manager, and H. W. Smith of Syracuse treasurer. The following are the directors: L. C. Smith, William Nottingham, Charles M. Warner, George B. Leonard, H. A. Smith, Horace S. Wilkinson, all of Syracuse; W. W. Brown and J. B. Cowle of Cleveland, and A. G. Brower of Utica.

## A TRIPLE LAUNCHING.

The three torpedo boat destroyers, Truxtun, Whipple and Worden, were launched together on Thursday of this week at the Maryland Steel Co.'s yards, Sparrow's Point, Md. The construction of these boats was begun early in 1900, but considerable delay was caused on account of the slow delivery of material. The boilers and a considerable part of the auxiliary machinery, pumps, blowers, etc., are in position and the main engines will now be put in place. These boats are the largest in length and displacement of their class and are being built after the contractor's own plans in contrast to many of the same lot which are from government plans. Although there have been several double launches, it is understood that this is the first time for any yard in America to launch in one day three vessels of any considerable size.

The three boats lay on parallel ways side by side. A special electric automatic device had been arranged at the head of each pair of groundways for the releasing of the cradles and at the touch of the electric button, one destroyer after another in quick succession glided gracefully into the water.

Mrs. Emelie B. N. Worden of New York, a relative by marriage to Admiral Worden, christened the destroyer bearing that name. The Truxtun was christened by Miss Isabelle Truxtun of Norfolk, granddaughter of Commodore Truxtun, and the Whipple by Miss Elsie Pope of St. Paul.

## WILL PUT ANOTHER LIGHT-SHIP ON SOUTH EAST SHOAL.

A meeting, called by Capt. George P. McKay, chairman of the committee on aids to navigation of the Lake Carriers' Association, was held in the office of J. C. Gilchrist, Cleveland, on Wednesday, to take steps to replace the light-ship recently destroyed by fire on the south east shoal, Point au Pelee passage. There were present at the meeting Messrs. J. C. Gilchrist, H. Coulby, William Gerlach, Edward Morton, W. W. Smith, J. J. H. Brown, T. T. Morford, Edwin S. Mills and George P. McKay. It was the unanimous opinion of those present that the old light-ship Smith & Post should be replaced with another light-ship. Letters to this effect were also received from Messrs. R. R. Rhodes, C. W. Elphicke, G. W. Maytham, W. A. Livingstone, G. L. Douglass, B. W. Parker, D. Sullivan and James Corrigan. Messrs. George P. McKay, H. Coulby, Edward Morton, William Gerlach and W. W. Smith were appointed as a committee to see that another light-ship was placed upon the shoal at the earliest possible moment. The committee met on Thursday morning and decided to invite tenders for furnishing a suitable vessel for this work. Such tenders should be addressed to Capt. George P. McKay, Perry-Payne building, Cleveland, and must state equipment, size and general description of the vessel. Both the selling price outright and charter price per day must also be given. The old schooner Smith & Post, which served as a light-ship until burned, was chartered by the day, but the committee this time inclines to purchase if favorable terms can be secured.

## BALL-THRUST-BEARING ON STEAMER GLADSTONE.

Last spring the steamer Gladstone of the Bradley fleet was equipped with a ball-thrust-bearing device upon its propeller shaft by the American Ball Bearing Co. of Cleveland and the result of the experiment has been most successful. By the introduction of the ball bearing arrangement upon the driving part of the machinery the steamer has been enabled to make a mile more per hour and the master of the vessel figures that he saves 320 lbs. of coal per hour. Mr. M. A. Bradley, the owner of the vessel, is quite enthusiastic over the result as far as it has gone. The Gladstone, to date, is the only vessel of his fleet so equipped, though he intends to equip two more at once.

"I figure," said Mr. Bradley, "that the vessel saves 10 per cent. in time—or 18 hours on a round trip of 1,800 miles. Her average season is fourteen round trips, or twenty-eight cargoes. With this device she ought to make an additional trip during the season. The master of the boat is very well pleased with the working of the ball bearing device upon the shaft, and says that he makes a mile more speed with less consumption of coal. The device uses neither oil nor water. It is quite an achievement to get a mile more speed out of an old boat like the Gladstone and we are watching the result with great interest. The ability to make an extra trip during a season would add considerably to the earning power of a vessel."

Regarding the construction and performance of the ball thrust bearing on the steamer Gladstone the American Ball Bearing Co. in a letter to the Review says:

"We beg to say that the bearing was designed by our Mr. Baker and embodies several improvements in ball bearing construction. Particular attention has been given to the necessary self-aligning features, that all twisting and bending strains, always present in vessels of such large proportions, shall not effect any unequal pressure on bearing. The bearing is entirely enclosed in a brass sheath and requires greasing but once in a season. This greasing is necessary only to prevent rust. The bearing has now been in constant use for about ninety days and very careful examination shows no wear whatever. Mr. Bradley has kindly sent us letters from the master of the Gladstone, whereby we are informed that a full mile per hour has been added to the speed of the boat, with a decided saving in fuel. To this remarkable showing must be coupled the fact that the constant water cooling and lubricating of former thrust-bearing is dispensed with by this improvement."

The Review will at a later date contain a full description of this bearing with drawings.

## PRODUCTION OF IRON AND STEEL RAILS IN 1900.

The American Iron and Steel Association has completed its collection of the statistics of the production of all kinds of rails in the United States in 1900. In March last the production of Bessemer steel rails by the producers of Bessemer steel ingots in 1900 was given as amounting to 2,361,921 gross tons. To this total must now be added 21,733 tons of Bessemer rails made in the same year from purchased blooms and re-rolled and renewed Bessemer rails, making a grand total for the year of 2,383,654 tons of Bessemer steel rails. In the same year we also made the largest quantity of open hearth rails in recent years, 1,333 tons, and the smallest quantity of iron rails ever recorded, 695 tons, which, added to the Bessemer steel rails above given, make the total production of rails in 1900 amount to 2,385,682 tons, the largest production ever attained in one year.

The following table gives the total production of rails in the United States in 1900 according to the weight of the rails per yard. Included in the total production are 101,312 tons which have been definitely reported to the association as street rails.

Kinds.	Under 45 lbs.	45 lbs. and less than 85.	85 lbs. and over.	Total. Gross tons
Bessemer .....	155,950	1,625,646	602,058	2,383,654
Open hearth .....	886	447	.....	1,333
Iron .....	695	.....	.....	695
Total .....	157,531	1,626,093	602,058	2,385,682

The total production of all kinds of rails in 1899 was 2,272,700 tons, of which 133,836 tons weighed less than 45 lbs. to the yard, 1,559,340 tons weighed 45 lbs. and less than 85 lbs., and 579,524 tons weighed 85 lbs. and over 85 lbs. The street rails made in 1899 and reported to the association amounted to 154,346 tons.

Improvements at the Brooklyn navy yard to cost about \$2,000,000 will soon be commenced by the yards and docks department. Within the next few weeks the department will advertise through the authorities at Washington for bids on the construction of four structures to cost in the neighborhood of \$1,000,000. These buildings, with the erection of a great coaling pier from the coal dock, a number of buildings on the ordnance dock and the completion of work already under way will call for an expenditure of about \$2,000,000.

The plans for a small revenue cutter for patrolling St. Mary's river are now ready and the department will soon ask bids for her construction. Congress provided an appropriation of \$75,000 for the construction of this vessel. According to the plans, the vessel will be 110 ft. long, 20.6 ft. beam and 12 ft. deep, with a displacement of about 215 tons. She will be constructed of steel and have a steel deckhouse.



### THE DENNY MODEL TANK AT DUMBARTON.

Com. J. D. Jerrold-Kelley of the United States navy gave a very interesting account in the Sunday New York Herald of the new system of testing ship's models in the tank used in the Denny ship yard at Dumbarton, England. In part he said:

At the Glasgow meeting this summer of the British Institution of Naval Architects Mr. Archibald Denny, of the well known Leven Ship Building Co., was asked by Mr. Yarrow if the researches made by the Denny firm with the model tank employed for testing the resistance of ships had been of practical utility. The designer and ship builder at once declared its utility to be so great that his firm often regretted it did not own two tanks instead of one, as both could be kept fully and profitably occupied. The subject under discussion was the benefit derived in the United States by the government and by private ship builders from the Washington model tank, and the liberality shown by naval officials in undertaking difficult inquiries for the private construction industries of the country. Mr. Denny's answer was evidently convincing, because then and there the institution, by unanimous vote, requested its council to take into serious consideration the question of providing for ship builders a model tank, where resistances may be tested, and where the data of bodies moving in the water may be collected, analyzed and converted into beneficent formulas for befogged and bewildered designers. All this shows that ideas march, even if in seasons they march slowly, perhaps lamely, and not to the beat of drum nor to the fanfare of trumpets, up the difficult road of peaceful endeavor. But it is curious that Great Britain, the originator of the government system of testing tanks, should have failed to provide this means of investigation for the builders and owners of the greatest merchant marine in the world. Foreign governments have long owned testing basins, open to private designers, and at Washington a tank built with the latest improvements is at the service of the people, and is already noted, not so much for the original researches made, but for the clever adaptation of new and more effected methods to old and apparently settled practices.

The Denny tank is distinguished above all others by the fact that it is the only one created by private enterprise. The government tank at Haslar is never idle, but the experiments made are for the exclusive use of the admiralty, and it is only on rare occasions that important discoveries are published. This is comparatively an old institution, for more than a quarter of a century has passed since William Froude established under government patronage at Torquay, England, the model tank that has done so much to make fairly exact the hitherto very inexact science of naval architecture. "It is not too much to say," writes a cautious expert, "that without the knowledge that Mr. Froude's labors have given to the world the marvellous results attained by ocean steamers at this end of the century would still be problems for the future." This to the unwary may seem fulsome praise, but not a word is misplaced, nor any adjective made too strong.

When steam propulsion began to change the commercial theories of the world, ancient ideas in ship modelling, "rule of thumb" practices, moss grown trade secrets and occult mysteries of the craft were of slight use in solving the new problems. Under sail it was and is different, for here the speed that may be attained is mainly a question of stability, of the power to carry large spreads of canvas without unduly or dangerously inclining or heeling the hull. This element, of course, demanded new treatment when propelling power ceased to be an unsetting force. Other factors, some old, some new, also vexed the designer, such, for example,

as the relative proportions of length, breadth and depth; the form of entrance and of run, and the proportions, form and number of revolutions of the propelling agency, be this screw or paddle. The essential, vital factor is always stability, for this governs the safety of all and controls in great degree the behavior of the ship under the varied conditions of her cruising career. Only less important, however, were the obscure and hidden factors that are now generalized under the name of resistances.

From the beginning the inquiry has been pursued with the express intention of submitting to thorough experiment these vague elements of restraint and of determining by scientific processes the various proportions and forms of ships through the behavior of models whose proportions bear a definite ratio to those of the actual vessels under investigation. In this labor it became necessary to compare the relative resistances of

the same model at various speeds, and those of different forms and proportions at equal speeds. Practical results were therefore needed to establish the truth or untruth of the relations that, according to mathematics, must exist between the full sized ship in smooth water and its model in the tank. After much complacent official conservatism had been overcome, the admiralty finally loaned for this work her majesty's ship Greyhound of 1,157 tons, and her majesty's ship Active of 2,087 tons. In the trials the Active towed the Greyhound at the end of a spar forty-five feet in length, so that all interference and resistance due to the leader's wake might be eliminated. The experiments were successful.

Among other facts discovered was the astonishing loss of energy in the steam propulsion of that day. By comparing the indicated horse power of the Greyhound on her official trial with the actual resistance shown by the dynamometer during the towing experiments, and, after making all allowance for opposing conditions, notably for the "slip" (the work lost by a screw turning in a yielding instead of a solid medium), it was found that only 45 per cent. of the power exerted by the steam was usefully employed in propelling the ship. The wasted 55 per cent. was finally debited to the friction of the engines and of the screw and to the detrimental reaction of the screw on the stream lines of the water rushing on and up and around the stern of the vessel. When it is remembered that under the most favorable conditions only about 10 per cent. of the available coal energy was developed in steamers of that day, the rest going up the chimney or into the machinery spaces, more than half of this was dissipated, and that, as a consequence, the working value of one hundred pounds of coal became in propulsion a trifle less than the value of four pounds, it must be conceded that the British admiralty was not getting good money for very exacting and costly labor.

Then, too, the trials and subsequent experiments showed how false the old beliefs were concerning the real action of a ship in the water. By rule of thumb practices, based upon dull tradition, it was held that the resistance of a ship consisted essentially of the force employed in driving the water clear of her as she lumbered on her foaming way. Even in these wiser days the inexpert insist that resistance is the force exerted to excavate a channel along the chosen pathway of the ship. Froude soon demonstrated the inexactness of the old belief, and crystallized the deductions from his own experiments in laws, where the total resistance met was divided into three elements: First, wave making; second, skin friction, and third, eddy making. His discoveries in this field were immediately accepted, and his formulae were stamped with the approval of mathematicians and physicists, notably his two famous enunciations, that wave making controls at high speed and that skin friction constitutes the main resistance at low speed.

Briefly summarized, his methods of investigation have established the



Photo copyrighted by Enrique Muller, Brooklyn.

SCHOOLSHIP ST. MARY'S, OF NEW YORK.

Built for U. S. Navy in 1844.

Displacement, 1,025 tons.



resistance for a model of any given form, and by the law of comparison the resistances of a ship of similar form. In practice each model is driven through the water at successive, appropriate and uniform speeds. During this run a dynamometer furnishes automatic and accurate records of the resistances encountered and of the speed made. In order to render the separate and the successive results intelligible and easy to employ, a curve known as the "curve of resistance" of any particular model is laid down graphically. This curve expresses for a model of particular form the law of its resistance in terms of its speed. By means of previous experiments the force necessary to draw one square foot of the model's immersed section, or "wetted skin," was known. If, then, the number of square feet of immersed skin in the model is calculated, the total skin resistance may be found by multiplying the force required for one square foot by the total square feet of immersed area.

If on the curve of skin resistance be laid a second curve representing the whole resistance at low speeds it will be seen that these two curves are practically identical. On this similarity has been based Froude's first law—that the resistance of tolerably fine ships moving at moderate speeds is almost wholly due to surface friction, or to the friction due to the particles of water that rub on the immersed surface. When a model is made to move speedily it is noticed that a train of waves is put in motion and that the size of these waves increases with the velocity of the model. After constructing the curve of resistance at high speeds and comparing it with that of low speeds it will be found that the former has risen—indeed, in some cases it has shot—much above the curve of low speed or skin resistance. This indicates the entrance into the problem of a new force, and it is now accepted that this excess in great degree measures the force exerted in that "wave making" which at high speeds is the most important resistance evolved.


In these experiments the instruments employed were, first, a tank or basin, sufficiently long for the models to attain the requisite uniform speed; second, "an exquisitely devised apparatus," as an enthusiast terms it, to

#### NEW SHIP BUILDING PLANT AT CHESTER.

Philadelphia, Pa., Aug. 14.—Within a very few days it is expected that the plans of the incorporators of a company said to be capitalized at \$3,000,000 to build ships on the Delaware river, will be made public. It has been generally known for several weeks in this vicinity that a new plant was proposed for Chester, Pa., 12 miles below this city, but the promoters have been so reticent concerning details that came to light regarding the scope of the scheme.

The land optioned consists of from fifty-five to sixty acres on the river front in the heart of Chester. It has a water front of about 2,400 ft. and at present is clear of obstructions. The depth of water in front of the property is from 20 to 25 ft. on the bulkhead line, allowing vessels of the largest size to be docked without much dredging. About thirty acres of the land is owned by the River Front Improvement Co. of Chester, which is composed of many of the most influential citizens of that place, including John B. Roach, president of Roach's ship yard; J. Frank Black, president of the Chester National bank; W. C. Sproul, president of the Seaboard Steel Casting Co.; Josiah Smith, district attorney, and several others. One of the leading factors in the new concern is Senator W. C. Sproul of Delaware county, who represents the largest investors. The Arthur Sewall estate, which has a controlling interest in the Bath Iron Works of Bath, Me., will be the largest single stockholder in the new corporation, and this interest will be represented by Arthur Sewall, Jr., executor of the estate.

It is said that the formation of this new concern will mean the consolidation, or at least the working in harmony of the Wetherell, Engine Building Co. and the plate and steel industries of Chester. A yard such as is contemplated will give employment to 1,500 men when running at its normal capacity, and this number will easily reach 2,000 if the yard is fortunate in securing contracts. It is claimed by those close in touch with the enterprise that \$2,600,000 of the stock has already been subscribed.



Milwaukee.

Illinois.

Cadillac.

OF THESE THREE YACHTS THE CADILLAC WAS SELECTED TO CONTEST FOR THE CANADIAN CUP.

Copyrighted by Detroit Photographic Co.

record automatically with electric contacts the speed and resistances of the models, and, third, the tank models.

The experimental tank of the Denny firm at the Leven ship yard is 300 ft. long, in 250 ft. of which length it is 22 ft. broad and 10 ft. deep. The remaining 50 ft. of length, divided into two shallow docks, one at each end, are used for ballasting, trimming and handling the models conveniently. A double line of rails, 3 ft. 4 in. apart, is carried on suitable beams and girders over the fore and aft center of the tank, and two carriages, one known as the dynamometer truck and the other as the screw truck, are drawn on these rails by means of an endless wire rope that is moved by an ordinary two cylinder engine.

The dynamometer truck is used to ascertain the resistance of the model; the screw truck to record the thrust of the screw, the number of screw revolutions, the slip of the screw and the turning force needed to drive the screws. These instruments are all extremely delicate. The levers are hung either on knife edges or on flat springs, and the wheels in the screw truck work on ball bearings or over Atwood pulleys. The precision and delicacy of these instruments must be extreme, because the quantities dealt with, especially at low speeds, must be measured within one-tenth of one per cent.

#### ARMOR PLATE SUCCESSFULLY TESTED.

Two successful tests of armor plate, one for the battleship Maine and the other for a Russian vessel, were conducted at Indian Head last week. The American armor tested was a 6-in. Krupp plate, representing the first group of such armor manufactured by the Bethlehem Steel Co. for the new battleship. Three shots were fired from a 6-in. gun at a velocity of 1,900 ft. per second. All the projectiles were broken on impact. The plate showed a very high resisting quality and proved equal to any ever tested at the proving grounds. As a result of the test the group of armor plate, representing about 400 tons, designed for the Maine, which is now building at Cramps, Philadelphia, will be shipped there immediately. The Russian test was of a 10-in. Krupp plate manufactured by the Bethlehem Steel Co. for the Russian government, representing a group of armor of 300 or 400 tons, intended for the Russian imperial vessel Emperor Alexander III. At this plate three shots were fired from a 10-in. gun with a velocity of 1,739 ft. seconds. The plate was highly satisfactory, and the plate bore every evidence of fully meeting the requirements.

The Harlan & Hollingsworth Co., Wilmington, Del., launched the new steamship Pathfinder this week.

Chester possesses many advantages as a ship building site. The river is practically open for twelve months in the year and the work can always be carried on. Almost in the proposed new yard is the plant of the Tide-water Steel Co., which makes all kinds of steel castings and plates, and within easy reach is the large engine building works of the Wetherell Machine Co. and those of the Chester Steel Castings Co.

#### OUR TRADE WITH GERMANY.

Recent discussions regarding the commerce between the United States and Germany lend especial interest to some figures just presented by the treasury bureau of statistics, which show the growth of commerce between the two countries in the last thirty years, and in detail during the last ten years. These figures show that imports into the United States from Germany have increased from \$27,000,000 in 1870 to \$100,000,000 in 1901, and that exports from the United States to that country have increased from \$42,000,000 in 1870 to \$191,000,000 in 1901—an increase of nearly 300 per cent. in imports from Germany and of nearly 400 per cent. in exports to Germany. On the export side, the greatest growth has been during the last five years, in which time our exports to Germany have doubled, being in 1896 \$97,897,197, and in 1901 \$191,072,252. This growth is distributed among a large number of articles. Comparing our exports to Germany in 1895 with those of 1901, corn has increased from \$1,672,539 in 1895 to \$17,305,229 in 1901; wheat, from \$1,522,736 to \$7,871,573; lard, from \$8,018,516 to \$13,700,875; oil cake and oil cake meal, from \$2,339,885 to \$5,242,624; flour, from \$740,264 to \$2,011,259; agricultural implements, from \$556,914 to \$2,677,319; and copper, from \$1,604,390 in 1895 to \$7,785,496 in 1901. Machinery of all kinds, including steam engines, increased from \$1,595,135 in 1895 to \$8,109,095 in 1900, the figures for 1901 in this item being not yet available. On the import side, the articles which show the greatest growth during the last decade are coal tar colors and dyes, chemicals, laces and embroideries, earthen, stone and chinaware, and sugar. Coal tar colors and dyes have increased from \$1,272,275 in 1891 to \$3,822,162 in 1900; other chemicals, from \$1,868,988 to \$3,968,116; laces and embroideries, from \$945,186 to \$2,402,372; earthen, stone and chinaware, from \$1,475,057 to \$2,787,163; and sugar, from \$7,209,150 to \$12,346,734.

An examination of the statistics issued by the German government shows that articles from the United States formed in 1891 10.4 per cent. of her total imports for consumption, while in 1900 they formed 16.9 per cent. Of her exports, those to the United States in 1891 formed 10.7 per cent. of the total, and in 1900 9.3 per cent.



### TRIAL TRIP OF SHALLOW-DRAUGHT GUNBOAT TEAL.


MESSRS. YARROW & CO. HAVE SUCCEEDED IN OVERCOMING MANY PRACTICAL DIFFICULTIES IN THE LITTLE VESSEL.

The British admiralty last year contracted with Messrs. Yarrow & Co. of Poplar, England, for the construction of two shallow-draught gunboats very similar to the Sheikh and Sultan, which the same firm built four years since for the Egyptian government for service on the Nile. These vessels, it will be remembered, played an important part in the taking of Khartoum, and the subsequent expedition to Fashoda. At about the same period as the Sheikh and Sultan were ordered, the admiralty also contracted with Messrs. Yarrow & Co. for the construction of a flotilla, six in number, of similar vessels for the rivers in China and the interior of Africa. These six vessels were named as follows: Heron, Jackdaw, Snipe, Sandpiper, Nightingale and Robin, and they have been doing excellent service.

The problem placed before Messrs. Yarrow & Co. was to obtain a speed of 13 knots (which is equivalent to 15 statute miles an hour), burning wood only, carrying a load of 40 tons on a draught not exceeding 2 ft. 3 in., all the machinery and fighting spaces being protected by rifle-proof plating. Those who are familiar with naval construction will be aware that the conditions to be conformed to present many practical

to, the fan being kept slowly revolving for the sake of ventilation only. The hull is built entirely of galvanized steel. It is sub-divided into ten water tight compartments, each compartment being floatable and independent of the others. This system of construction was introduced by Messrs. Yarrow & Co. in the year 1883, when they built for his majesty the King of the Belgians the stern wheel steamer Le Stanley for exploring the Congo. After Le Stanley was built the advantage of this system of construction was recognized, and it was adopted in the case of the Mosquito and Herald, built for the British government for the Zambesi, and also in similar vessels for the French and Russian governments. The benefit of this floatable section system of construction is that it enables the vessel to be put together while afloat, thus avoiding the tedious process of riveting up and launching in distant parts, where skilled labor may not be obtainable. The main deck is of steel, covered with corticine. Above is an upper or battery deck, extending for about half the length of the vessel, on which are mounted quick-firing guns and Maxims. Above the battery deck is the awning deck, from which are swung the hammocks for the troops. The battery deck being completely housed in spacious quarters are thus formed for the Europeans. The sides of the vessel in way of the machinery, as well as the cabin accommodation and the bulwarks round the battery deck, are throughout of chrome steel by Cammell, and the plates are of sufficient thickness to be proof against rifle fire, point blank, at close quarters. A conning tower is placed forward on the battery deck and is also rifle proof.

The general fittings of these gunboats are very complete, including accommodation for the native crew, also a specially fitted sick bay. The officers are accommodated in cabin between the main and battery decks.



THE SHALLOW-DRAUGHT GUNBOAT TEAL ON HER TRIAL TRIP.

Built by Yarrow & Co., Poplar, England.

difficulties. These have been successfully overcome, and when Messrs. Yarrow have completed their contract they will have the honor of adding two more vessels of a special type to the British navy, the names of which are the Teal and Moorhen, and the dimensions are as follows: Length, 160 ft.; beam, 24 ft. 6 in.

A partial description of these vessels was given two weeks ago, but the Review is now enabled to give a more thorough one.

The system of propulsion selected is that of twin screws revolving in tunnels of a special design, so arranged that, although the propellers do not pass below the bottom of the hull, they are of a large and efficient diameter, and work in solid water. The result of the trials show that they have an exceedingly good propulsive efficiency. Doors are placed immediately over the propellers, so that they can be examined or removed without difficulty while the vessel is afloat, thus avoiding the necessity of going into dry dock or hauling the boat up a slip way, should it be required to gain access to the propellers.

As evidence of the accessibility of the propellers, it may be stated that it requires only twenty minutes to remove a propeller and replace it by another.

The first of these vessels, H. M. S. Teal, was recently launched, with steam up, and immediately proceeded down the Thames for a preliminary trial. Five days later the official trial took place. The admiralty were represented on this occasion by Mr. Cotsell and Mr. Adams of the ship department, and Mr. Spyer and Mr. Harding of the engineers' department. These results are exceedingly interesting, and they may be looked upon as unique in the annals of naval construction, a speed of over 15 statute miles an hour being obtained when burning wood fuel only and without the necessity of resorting to the forced draft appliances which were provided, and this result was combined with a draught of 2 ft. 2½ in., carrying a load of 40 tons, independent of the weight involved by the protection against rifle fire over a large area of the vessel.

After the six runs on the measured mile a three hours' trial was proceeded with, the mean revolutions being 282.6, equal to 13.033 knots, equal to 15 statute miles, as the mean speed for the three hours. During one hour wood fuel only was used and forced draft was not resorted

to. These are loop-holed for rifle fire. The forward cabin is divided into a ward room and commander's cabin, and fitted up for the accommodation of three officers, the after cabin being adapted for eighty petty officers. Passing through these cabins are ammunition hoists, so that there is a direct passage from the magazines below to the battery deck, under cover and protected from shot.

The machinery consists of two sets of compound surface condensing engines, running at an average of about 300 revolutions per minute. Steam is supplied by two of Yarrow's patent straight tube water tube boilers, the design of which is now so well known that it need not be described here. The boilers have been designed so that full speed can be obtained when burning wood fuel only. Forced draft is provided for by means of a steam fan in the stokehold, and, although this was not required to be in operation during the official trials for the purpose of forcing the fire, under some circumstances, no doubt, it will be found of great value when only wood fuel is to be obtained of a very inferior character, or green.

The vessel is steered by means of the usual steam and hand steering gear, which actuates four rudders, so as to ensure exceptional maneuvering qualities when navigating very tortuous rivers. Messrs. Yarrow & Co. have, of late years, made a very complete study of this special design of vessel, so as to secure the most efficient combination of speed with shallow draught, and have introduced numerous improvements since they first seriously took up this form of construction. Hitherto the greatest efficiency has only been obtainable at a given draught; but the builders have introduced and patented a system by which the maximum efficiency can be secured corresponding to any draught which the load carried may involve, rendering this system of propulsion, in consequence, not only applicable for river gunboats, where the load is practically constant, but also for shallow draught vessels for commercial purposes where the weight of cargo is continually varying.

During the run some tests were made of the steering capabilities of the Teal, which were shown beyond question to be something altogether remarkable. The way in which she maneuvered either to port or starboard immediately the helm and the four rudders were put over was astonishing.



### FOUNDER OF THE GOVERNMENT LIFE SAVING SERVICE.

Dr. William Augustus Newell, who died at his home in Allentown, N. J., last Thursday, was practically the founder of the life saving service of the United States, if any man may be said to be the founder of that which is really a growth. What life saving service there had been before he became interested in its development was of a private character. The Massachusetts humane society established a station at Cohasset in 1807 but did not receive government aid for many years thereafter. The establishment of the coast survey gave some impetus to the life saving service—that is, it caused the government to turn its attention in that direction. It was Dr. Newell who conceived the idea of shooting a life line from the shore to a stranded vessel. This was the initial step in the establishment of the government service and from it has grown the thoroughly organized system by which more than 100,000 human beings have been rescued from death and many millions of dollars of property saved. Dr. Newell, then a member of the national house of representatives, secured the first appropriation of \$10,000 in 1848, for the life saving service on the New Jersey coast. With this money life lines, surf boats, and the more crude appliances were provided, and the innovation, looked upon with incredulity by many members of congress who had voted for the appropriation, was ready for the first call to be made upon it to test its practicability. The call came on Christmas night of the following year, when 301 passengers and seamen were rescued from the stranded bark Ayrshire in the midst of a blinding snow storm. The people of the country read with amazement of this remarkable feat, while every member of congress bowed his head to Dr. Newell and his great idea.

From that day to this there has been no trouble in securing liberal appropriations for the life saving service. From the modest beginning on the Jersey coast, the system has grown until now there are 269 stations along the shore lines of the United States. Of this number 194 are situated on the Atlantic and gulf coasts, fifty-eight on the shores of the great lakes, sixteen on the Pacific coast, and one at the falls of the Ohio, Louisville, Ky.

Dr. Newell's account of the founding of the life saving service is as follows:

"The initial idea of a life saving service came to me in 1840, while I was practicing medicine at Mannahawkin, Ocean county, N. J. A terrific storm had swept the coast for a day and a night, but the following morning broke clear and still. I took a long walk along the beach and saw that the Austrian brig Count Perasto had been wrecked on Long Beach, near Barnegat inlet. The tide had gone out and the wrecked vessel was on dry land and thirteen dead bodies were lying along the beach. The idea there occurred to me, would it not have been possible, had a crew been on watch at this dangerous point, to throw a lifeline to the crew of the stranded ship by means of a bow and arrow or a blunderbuss? The experience of that morning created a deep impression upon my mind and I endeavored to evolve a plan whereby my idea could be put to an actual test.

"On Jan. 3, 1848, I introduced in the national house of representatives the following resolution:

"Resolved, That the committee on commerce be instructed to inquire whether any plan can be devised whereby the dangerous navigation along the coast of New Jersey may be furnished with additional safeguards to life and property, and that it report by bill or otherwise."

"The committee never reported; so when the light-house appropriation bill was before the house I offered the following as an amendment:

"An amendment appropriating \$10,000 for providing surf boats, rockets, cannonades, and other necessary apparatus for the better protection of life and property from shipwrecks along the coast of New Jersey, the sum to be expended under the supervision of such officer of the revenue marine corps as may be designated by the secretary of the treasury."

"The amendment was passed without a dissenting vote. Among the members of the house who voted for this amendment were John Quincy Adams, Abraham Lincoln, Andrew Johnson, Robert Toombs and Thaddeus Stevens. The measure was adopted unanimously by the senate, such members as Henry Clay, Daniel Webster, John C. Calhoun, Thomas H. Benton, Stephen A. Douglas and Jefferson Davis giving it their support, at the same time having little confidence in the practicability of the scheme. President Polk signed the bill cheerfully.

"The first practical result of the new venture was accomplished on the night of Christmas, 1849. The Scottish bark Ayrshire was wrecked at Absecon beach. Lines were thrown to her, surf boats were launched and the entire passenger list and crew, consisting of 301 persons, were brought safely to shore in the midst of a blinding snow storm. This remarkable feat cast aside all past doubts in the minds of the senators and representatives as to the practicability of the scheme, and thenceforth liberal appropriations were voted until we have the perfected system of the present day."

Efforts have been made by others to claim the credit of originating the life saving idea, but Dr. Newell's claims are beyond dispute. Appleton's Cyclopaedia, in the William A. Newell biography, says:

"He originated and procured the first appropriation by congress of \$10,000 for the life saving stations on the New Jersey coast, and was superintendent of life saving stations in New Jersey from 1861 to 1863."


Sumner I. Kimball, general superintendent of the life saving service and bureau, says in his report of 1876:

"The government first gave its attention to the method of aiding

stranded vessels by the establishment of stations along the coast provided with the means of effecting communication between such vessels and the shore in 1848, and to the Hon. William A. Newell of New Jersey, then a member of the house of representatives, belongs the honor of first advocating the merits of this plan in a speech in which he described the uses of the surf boats, mortar lines, rockets, etc., vividly portraying the horrible scenes of shipwrecks upon the calamitous shores of his state. This appeal, made on Aug. 3, was rewarded by an appropriation of \$10,000. More appropriations were made subsequently through the efforts of Dr. Newell until now there are 200 stations and crews, resulting in the rescue of 100,000 persons and saving many millions of property."

Mr. Kimball kindly furnished the Review with a copy of a report which he made to congress in 1898 setting forth Dr. Newell's offices in behalf of the life saving service of the United States. He adds that since the date of his report he has received information from the government of Austria to the effect that the brig Terasto (supposed to be the Austrian brig Count Perasto) was wrecked on the coast of New Jersey Aug. 13, 1839, but that no loss of life attended the disaster. This was in reply to a letter from him requesting particulars of the wreck of the Count Perasto. He infers that the Austrian government has no record of a vessel of that name.

### The Largest Vessel in the World.



THE SCREWS OF THE CELTIC OF THE WHITE STAR LINE.

Built by Harland & Wolff, Belfast, Ireland.

### EXPORTS TO PORTO RICO.

Exports of American products to Porto Rico in the fiscal year just ended were, according to the figures of the treasury bureau of statistics, more than three times as great as they averaged when Porto Rico was under the Spanish flag and more than 50 per cent. in excess of those prior to the enactment of the Porto Rican tariff law which went into effect May 1, 1900. The total domestic exports from the United States to Porto Rico in the fiscal year 1897, which entirely preceded the beginning of hostilities with Spain, were \$1,964,850. In the fiscal year 1900, ten months of which preceded the date at which the Porto Rican tariff went into effect, our domestic exports to Porto Rico were \$4,260,892. In the fiscal year ending June 30, 1901, all of which was under the Porto Rican act which levied 15 per cent. of the regular Dingley law rates on goods passing into that island from this country, the total domestic exports from the United States to Porto Rico were \$6,861,917. These figures include only exports of domestic merchandise and do not include foreign merchandise brought into the United States and re-exported to Porto Rico, which presumably amounted to about \$500,000, since the Porto Rican statement of imports from the United States for the fiscal year ending June 30, 1901, shows the grand total including domestic and foreign to be \$7,414,502.

Porto Rico imported in the fiscal year ending June 30, 1901, goods amounting to \$9,367,230 in value, and of this, \$7,414,502 came from the United States, the total from other countries being \$1,952,728. Of this \$1,952,728 imported from countries other than the United States, the value of \$808,441 was from Spain; \$374,837 from the United Kingdom; \$294,067 from Canada; \$166,723 from France, and \$152,201 from Germany.



## THE EVOLUTION OF THE SCREW STEAMER.

BY BENJAMIN TAYLOR, F. R. G. S.

Who invented the screw propeller? Lindsay, the author of the "History of Merchant Shipping," says it is impossible to ascribe the invention to any one man, as the subject had engaged the attention of so many men for upwards of a century. But it is possible, notwithstanding Lindsay, to get a little nearer than he did to the origin of this now common object of the ocean. The New Jersey has been sometimes described as the first screw propelled vessel in America. She was an iron vessel, built by Laird of Birkenhead in 1838, and originally called the Frank R. Stockton, after her owner, who sold her to the Delaware & Raritan Canal Co. But Stockton took the idea from Ericsson, to whom, indeed, he gave the commission to design the engines after he had watched the operations of

Ericsson's experimental boat, the Francis B. Ogden, on the Thames. To John Ericsson, Pettie Smith, and Bennet Woodcroft has been ascribed equal credit for actually putting the "screw" into working order. Let us look into the matter a little further,

however, without going into ancient history, as John McGregor did when he endeavored to find the origin of the screw propeller in China!

In one part of his "History" Lindsay says that, "In May, 1804, Mr. J. Stevens of the United States put to sea with a steam-boat propelled by a screw, turned first by a rotatory engine, and then by Watt's reciprocating engine; and as this small craft steamed from Hoboken to New York she has by some writers been considered the first sea-going screw of which there is any certain account." But further on he says, "The screw which Mr. Stevens used in his boat cannot have been of a practical character, or the Americans would not have allowed so valuable an invention to lie dormant for 35 years." That is to say, Stevens's voyage was made in 1804 but the New Jersey did not appear in American waters until 1840, and even then from the hands of English ship builders, with engines designed by a Swede.

Nevertheless, there is evidence that the screw propeller put in operation by Colonel John Stevens on the Hudson river between 1802 and 1806 was actually the first of the kind to navigate the waters of any country.

This Col. John Stevens was certainly a very remarkable man. He was born at New York in 1749, graduated at King's college, was admitted to the colonial bar in 1772, and was treasurer of the state of New Jersey during the war of independence. Afterwards he purchased the island of Hoboken and lived there until his death in 1838. In 1791 Stevens took out three patents for improvements in the steam engine, one of which had reference to a method for propelling a vessel by the reaction of water. In 1798 he was engaged along with the elder Brunel and some others in a series of experiments in steam propulsion on the Passaic river in New Jersey, and among the many things they tried was an elliptical paddle-wheel. But in 1794 a patent was granted to one William Lyttleton, in England, for a screw propeller worked by manual labor with an endless rope. This screw was tried on the Thames, and gave a speed of two miles an hour—a little fact which seems to have escaped even Lindsay's lynx eye.

Lindsay only briefly refers, in a couple of lines, to a patent taken out by Edward Shorter in 1800 for "a perpetual sculling machine having the action of a two-bladed propeller." But, as a matter of fact, Shorter had two schemes. One was a sort of duck-foot paddle, the pair working alternately; and the other was a two-bladed screw at the end of an inclined shaft from the deck of the vessel. With the latter he propelled a heavy transport at the rate of  $1\frac{1}{2}$  miles an hour—eight men working the screw at a capstan. But long before either Stevens or Shorter or Lyttleton, viz., in 1752, Bernouilli, the mathematician, elaborated a plan for propelling a boat by means of a screw worked by hand.

The idea of the screw propeller, then, did not originate with John Stevens, though quite possibly he may not have heard of either Bernouilli's or Lyttleton's inventions. But, as far as we can gather, Stevens seems to have been really the first who applied steam as the motive power. He began his experiments in 1801, and he had a screw steamer on the Hudson river in 1802—not in 1804 as mentioned by Lindsay. He tried a succession of non-condensing engines between 1801 and 1804 and it is interesting to note, he got a high pressure of steam out of multitubular boilers, for which he had taken out a patent. And he used not a two-bladed but a four-bladed screw.

In a letter to a New York Journal in 1812, Stevens thus wrote an account of his experiments:

"To avoid the mischievous effects necessarily resulting from the alternating stroke of the engine of the ordinary construction, I turned my attention to the construction of steam engines on the rotary principle. And the first steamboat put in motion on the waters of the Hudson was one constructed on this principle. \* \* For simplicity, lightness and compactness, the engine far exceeded any I have yet seen. A cylinder of brass, about 8 in. in diameter and 4 in. long, was placed horizontally on the bottom of the boat, and by the alternate pressure of the steam, on two sliding wings, an axis passing through its center was made to revolve. On one end of this axis, which passed through the stern of the boat, wings like those of the arms of a windmill, were fixed, adjusted to the


most advantageous angle for operating on the water. This constituted the whole of the machinery. Working with the elasticity of the steam merely, no condenser, no air pump, was necessary, and as there were no valves, no apparatus was required for opening and shutting them. This simple little steam engine was, in the summer of 1802, placed on board a flat-bottomed boat I had built for the purpose. This boat was 25 ft. long and about 5 or 6 ft. wide. She was occasionally kept going until the cold weather stopped us. When the engine was in the best order her velocity was about four miles an hour. I found it, however, impracticable on so contracted a scale to preserve due tightness in the packing of the wings in the cylinder for any length of time. This defect determined me to resort again to the reciprocating engine."

Here are chapter, verse and date in the inventor's own words, and never, so far as we know, called in question. In referring to his 1803 experiment, Stevens has written as follows:


"I constructed an engine although differing much from those described in the specifications of my patents, yet so modified as to embrace completely the principle stated therein. During the winter this small engine was set up in a shop I then occupied at the Manhattan works, in Duane, near Centre street, and continued occasionally in operation until spring, when it was placed on board the above-mentioned boat, and by means of bevel cog-wheels it worked the axis and wings above-mentioned, and gave the boat somewhat more velocity than the rotary engine. But after having gone some time, in crossing the river with my son on board, the boiler, which was constructed of small tubes inserted at each end into metal heads, gave way so as to be incapable of reparation." (Note here, also, the germ of the tubulous boiler.)

In the following year Stevens adopted Watt's "reciprocating rotative" engine, with a  $4\frac{1}{2}$ -in. cylinder and 9-in. stroke, working a two-bladed screw, with which he got a speed of about four miles an hour. It was probably this vessel and engine that Prof. Renwick of Columbia college saw, as related in an interesting letter which has been published in the Journal of the New York historical society. Prof. Renwick wrote in 1858:

"The first time that I ever heard of an attempt to use steam for propelling vessels was from a classmate of mine who resided during the summer months at Belleville, in New Jersey. He had, in the summer of 1803, seen an experiment on the Passaic river, which he stated to have been directed by John Stevens of Hoboken. According to his account the propulsion was attempted by forcing water by means of a pump from an aperture in the stern of the vessel(!) From some vague indications



THE FIRST AMERICAN STEAM ENGINE, 1801.



AN EARLY DESIGN OF A BRITISH SCREW STEAMER.

it would appear that the elder Brunel, afterwards so distinguished in Europe, was in the employment of Mr. Stevens on this occasion. In the month of May, 1804, in company with the same young gentlemen and another classmate, I went to walk in the battery. As we entered the gate from Broadway we saw what we, in those days, considered a crowd running towards the river. On inquiring the cause we were informed that 'Jack Stevens' was going over to Hoboken in a queer sort of boat. On reaching the bulkhead by which the battery was then bounded, we saw lying against it a vessel about the size of a Whitehall rowboat on which there was a small engine, but there was no visible means of propulsion. The vessel was speedily under way."

Fifty years later Prof. Renwick recognized, at an exhibition of the American Institute, the boat and engine which he had seen in 1804. They were exhibited by the sons of Col. Stevens. And Renwick himself was an authority on the history of the steam engine, for he contributed the American chapter to Tredgold's celebrated "Treatise."


Now we gather from these records that Stevens was not only the first to devise a screw propeller worked by steam, but that he was also the inventor of the twin-screw, for he found out the well known tendency of a single screw to turn the bow of the vessel. Forty years later, viz., in 1844, this old twin-screw engine, overhauled and repaired, was fitted on board a new boat and again tried on the Hudson river, when a speed of eight miles an hour was obtained. And this same engine, with



its boilers, is still, we believe, preserved in the Stevens Institute at Hoboken.

It is interesting to note that the young man whom Prof. Renwick saw in 1804 acting as coxswain in the queer little boat, was John Cox Stevens (son of the colonel), who in later years founded the New York yacht club, and steered the famous yacht America in her historic race off the Isle of Wight, when she won the international cup in 1851. He was sent over to England by his father to take out an English patent for the invention, and he called upon the famous James Watt with the plans. It is said that Watt objected to the thing, because he did not believe in the practical use of steam at a pressure more than 2 or 3 lbs above the atmosphere. As to this we read, some years ago, in Cassier's Magazine that "At the date of the introduction into use of the screw propeller, 1838, the pressure of steam carried on the boilers of condensing engines of the vessels that now navigate the bays and rivers of the Atlantic seaboard, averaged about 30 lbs. per square inch, while on the innumerable steamboats on the Mississippi and its tributaries the steam averaged 140 lbs. per square inch. At the same time, the pressure on English vessels was the same that Watt had established, viz.,  $2\frac{1}{2}$  to 3 lbs. The Great Western, in 1838, carried that pressure and the iron screw propeller Great Britain, in 1846, carried only 5 lbs. per square inch."

Col. Stevens continued his experiments with the screw propeller for several years before Fulton brought out his paddle-boat. And it is remarkable that all his ideas have now, after half a century, been applied to steamship navigation, viz., the four-bladed screw, the use of high-pressure steam, the multi-tubular boiler, the direct connection of the engine with the propeller shaft, and the twin-screw. But in Stevens's time there were neither efficient tools nor competent workmen in America to carry his ideas into effect. Fulton, it must be recalled, did not build the engine for his steamer Clermont in America, but had it



AN EARLY BEAM ENGINE.

made by James Watt in England and taken over complete. This was in 1806, and special permission had to be obtained for it from the king in council, because the exportation of machinery from England was then illegal—and indeed remained illegal down to 1820. Stevens cheerfully admitted that Fulton was the first to apply, with practical effect, "water-wheels" to the side of a steamboat, but he adhered to the opinion that, with proper machinery, the screw would always be found superior to the paddle for sea-going vessels.

It was just thirty years after Stevens discontinued his experiments that John Ericsson, the Swedish engineer, submitted to the admiralty a plan for screw propulsion. He constructed a model boat, some 2 ft. long, and by means of a small model engine, fed with steam from outside, showed the practicability of his scheme. Nevertheless, the admiralty, having previously come to the conclusion that the screw was impracticable, rejected his plan, and did not adopt it until after Ericsson had built upwards of forty screw steamers in America.

Ericsson's first test on a full scale was with the Francis B. Ogden, mentioned at the outset of this article. This was a wooden boat, built at Wapping on the Thames, into which he fitted an engine driving two screws, with which he obtained a speed of 10 miles an hour. Just about the time when Ericsson was taking out his patent, Thomas Pettit Smith also took out a patent for driving a vessel by means of a screw, or worm, revolving rapidly under water. He made trial of it in a small six-ton boat, and the experiment was so successful that a company was formed in 1839, called the Steamship Propeller Co., to purchase and work Smith's patent. The result was the Archimedes, a vessel of 237 tons built under the direction of Smith and specially for his screw propeller. Smith expected a speed of 12 or 13 miles an hour, but the Archimedes never developed more than about 9 miles an hour. She was eventually sold at a heavy loss.

Both Ericsson and Smith claimed the invention, but neither, as we have seen, originated the idea. Both took out patents in America, as well as in England, but in neither case were the patents sustained. The Robert F. Stockton was built, in 1838, for Ericsson's screw, but she was sent across the Atlantic under sail. The designs of the inventors were quite different. Smith was well backed and succeeded in getting his screw taken up in England, while Ericsson, not finding favor in that country,

went over to the United States. Both Ericsson and Smith eventually abandoned their original plans and adopted the short screw now in use. In Smith's patent the screw was a long single blade, after the model of the Archimedes screw; in Ericsson's patent there were two separate blades, one behind the other. Both were inferior designs to Stevens's, but Ericsson and Smith together revolutionized steam navigation, for from their complicated screws rapidly evolved the propeller now universally in use.

The first screw steamer to cross the Atlantic was the Great Britain (of Bristol) which took some six years to build. She was a vessel of some 3,618 tons, measuring 322 ft. in length, 50 ft. in extreme breadth, and 32 ft. in depth. She had six masts and one funnel, and with the aid of a screw propeller went from Liverpool to New York, in August, 1845, in fifteen days, making an average speed of nine knots. She made several voyages back and forward until September, 1846, when she ran ashore on the coast of Ireland, where she remained stranded for nearly a year. She was floated off in the autumn of 1847, taken to Liverpool for repairs, and then put into the Australian trade. After serving in that trade for some twenty years, her propeller and machinery were taken out, and the first transatlantic screw steamer was converted into a full-rigged sailer. The last stage in her eventful history was as a coal-hulk in the Pacific.

#### MONTHLY SUMMARY OF NAVAL CONSTRUCTION.

In the monthly summary of naval construction, issued by the bureau of construction and repair, the armored cruiser Colorado at Cramps is the only one of the recent order of eleven battleships and cruisers actually laid down. The protected cruiser Cleveland at the Bath Iron Works, Bath, Me., is 61 per cent. completed and will be launched on Sept. 22. Following is the summary:

Name.	Building at	Degree of completion, Per cent.	
		July 1.	Aug. 1.
BATTLESHIPS.			
Illinois	Newport News	96	98
Maine	Cramp & Sons	55	58
Missouri	Newport News	39	42
Ohio	Union Iron Works	43	43
Virginia	Newport News	0	0
Nebraska	Moran Bros. Co.	0	0
Georgia	Bath Iron Works	0	0
New Jersey	Fore River Co.	0	0
Rhode Island	Fore River Co.	0	0
ARMORED CRUISERS.			
Pennsylvania	Cramp & Sons	0	0
West Virginia	Newport News	0	0
California	Union Iron Works	0	0
Colorado	Cramp & Sons	2	3
Maryland	Newport News	0	0
South Dakota	Union Iron Works	0	0
SHEATHED PROTECTED CRUISERS.			
Denver	Neafie & Levy	49	51
Des Moines	Fore River Engine Co.	39	45
Chattanooga	Lewis Nixon	35	37
Galveston	Wm. R. Trigg Co.	31	33
Tacoma	Union Iron Works	20	20
Cleveland	Bath Iron Works	58	61
St. Louis	Neafie & Levy	0	0
Milwaukee	Union Iron Works	0	0
Charleston	Newport News	0	0
MONITORS.			
Arkansas	Newport News	60	61
Nevada	Bath Iron Works	89	90
Florida	Lewis Nixon	67	68
Wyoming	Union Iron Works	75	75
TORPEDO BOAT DESTROYERS.			
Bainbridge	Neafie & Levy	94	95
Barry	Neafie & Levy	88	90
Chauncey	Neafie & Levy	90	90
Dale	Wm. R. Trigg Co.	95	96
Decatur	Wm. R. Trigg Co.	96	97
Hopkins	Harlan & Hollingsworth	75	75
Hull	Harlan & Hollingsworth	74	74
Lawrence	Fore River Engine Co.	99	99
MacDonough	Fore River Engine Co.	98	98
Paul Jones	Union Iron Works	85	85
Perry	Union Iron Works	89	89
Preble	Union Iron Works	87	87
Stewart	Gas Engine & Power Co.	54	55
Truxton	Maryland Steel Co.	68	70
Whipple	Maryland Steel Co.	67	69
Worden	Maryland Steel Co.	67	69
TORPEDO BOATS.			
Stringham	Harlan & Hollingsworth	98	98
Goldsbrough	Wolff & Zwicker	99	95
Blakely	Geo. Lawley & Son	98	98
DeLong	Geo. Lawley & Son	98	98
Nicholson	Lewis Nixon	90	91
O'Brien	Lewis Nixon	94	96
Thornton	Wm. R. Trigg Co.	97	97
Tingey	Columbian Iron Works	68	68
Wilkes	Gas Engine & Power Co.	82	84
SUBMARINE TORPEDO BOATS.			
Plunger	Lewis Nixon	15	19
Adder	Lewis Nixon	70	75
Grampus	Union Iron Works	51	51
Moccasin	Lewis Nixon	65	70
Pike	Union Iron Works	50	50
Porpoise	Lewis Nixon	60	64
Shark	Lewis Nixon	58	63

Alvin R. Morrison, president of the Delaware Construction Co., of Wilmington, announces that the large dry dock which the company is building for the William Skinner & Sons of Baltimore, will be completed in about three weeks. This dry dock job is the largest contract ever undertaken by the Delaware Construction Co., and much time has been required to do the work. The construction company is now in the hands of receivers, but it is expected that the receivership will be terminated in the near future.

The recently launched battleship Maine was brought from Cramps' ship yard to League Island on Thursday last and put in dry dock. Her huge bulk completely filled the dock and the keel blocks had to be raised 15 in. higher than in ordinary cases to keep her clear of the dock's altars. The ship's bottom is at present receiving one coat of two coats of non-corrosive paint and one of anti-fouling paint. The Maine will be returned to the ship yard about Aug. 18.



# MARINE REVIEW

Devoted to the Merchant Marine, the Navy, Ship Building, and Kindred Interests.

Published every Thursday at No. 418-19 Perry-Payne building, Cleveland, Ohio, by  
THE MARINE REVIEW PUBLISHING CO.

SUBSCRIPTION—\$3.00 per year in advance; foreign, including postage, \$4.50, or 19 shillings.  
Single copies 10 cents each. Convenient binders sent, post paid, \$1.00.  
Advertising rates on application.

Entered at Cleveland Post Office as Second-class Mail Matter.

The present week has borne witness to a significant triumph of American manhood. The workman has proved himself to be greater than his union. When Mr. Shaffer issued his amazing call to the amalgamation last week the country was simply astounded at its provisions. This man, supposed to be the representative of American labor, called upon the members of the amalgamation to repudiate their contracts with the United States Steel Corporation. From the moment that call was issued until the day set for it to take effect the American workman was on trial before the bar of public opinion. To his credit let it be said that he declined to obey the call. It is true that there has been some deflection from the ranks but the majority of the American workmen have remained at work. The amalgamated association hoped to bring out one-half of the mills of the Steel Corporation and it succeeded in stopping only one-sixth of its great operating force. Even at that the major portion is unskilled labor which, of necessity, had to be thrown out of employment. The strike is clearly confined to the Pittsburg, Wheeling and Newcastle districts and the gas belt in Ohio and Indiana. The struggle is not likely to spread beyond these geographical limits. The great protest against the unwarranted action of the leader of the amalgamation came from the west. A considerable portion of the members of the amalgamation in Chicago, Milwaukee and Joliet did not accept Shaffer's view of the case. They simply stated that existing contracts forbade their striking. When Shaffer heard of this he said, "I cannot understand the action of our western men, but if it is true that they are at work I will not be satisfied until the men in the slave pens of the trust assert their manhood." Mr. Shaffer has very curious notions of manhood. Moreover his language in referring to the mills as slave pens is scarcely becoming. Most of the men working in them were very glad to get their positions and it has probably never occurred to any of them that they were slaves. They will not welcome the suggestion from Shaffer. These self same mills have been paying the highest wages known in the steel world, and they have, as a general thing, a contented and independent class of workmen.

What is the present situation? There is not a constituent company of the United States Steel Corporation which has not one or more plants in operation in face of the strike order and the largest and heaviest tonnage producing companies are running in full. What is the lesson to be derived from the strike? This is a point that is of as great importance to the workmen as it is to the employer. The country has seen a strike precipitated without just cause. It is because it is so grievously unjust that it is going to fail. The workmen of the country have seen the name of labor attached to the most dishonorable proposition that has ever been presented to a civilized community. With the union as a unit some have indorsed it; but it is inconceivable that with the individual as a unit it could possibly be indorsed by anyone. It is doubtful if Shaffer could find a single adherent. As far as Shaffer has been able to dictate the policy of the union he has said that contracts entered into by the union are binding only upon the employers. They may be revoked at will by the workmen. This is an entirely new view of contracts and that it is entirely at variance with the constitution of the United States, which holds as one of its most precious guarantees the sanctity of contract, does not disturb Mr. Shaffer in the least. It might well disturb the workman, however. Mr. Shaffer in seeking to do a considerable injury to the United States Steel Corporation has succeeded only in doing a very great mischief to the cause of organized labor. He has said in so many words that the amalgamation recognizes no obligation except the obligation to itself. We doubt very much whether the workmen care to subscribe to any such sentiment as that, or indeed to belong to an organization which includes it among its tenets. The lesson is, in the future, to look to the individual workman. After the present experience no employer can be blamed for looking with distrust upon a contract made by the union. He cannot help it. He will look to each man individually. With such a policy as this few contracts will be broken. Shaffer has written the death warrant of the amalgamation.

Senator Frye is planning a meeting of the friends of the shipping bill to be held in Boston during the first week of September. The purpose is to get the bill in preparation for presentation early after the opening of congress and to receive the suggestion of the members as to the best form in which to introduce it. Among the more important matters which will be considered at the Boston conference is a provision in favor of ves-

sels engaged for the greater part of the year in the coastwise trade and which wish to engage in the foreign trade during a portion of the year. The bill will be introduced in the senate by Mr. Frye but it is not yet determined who will introduce it in the house. It is barely possible that the bill may originate in the house for parliamentary reasons. With Pettigrew, Butler and Allen out of the senate, friends of the bill believe its prospects of passage at the next session are favorable.

## GRAIN ELEVATORS OF THE GREAT LAKES.

AFTER AN EXHAUSTIVE INSPECTION OF THEM, HARBOR ENGINEER JOHN KENNEDY RECOMMENDS FOR MONTREAL AN ELEVATOR SIMILAR TO THE GREAT NORTHERN AT DULUTH.

The harbor commissioners of Montreal recently made a tour of the great lakes to inspect the grain elevators and terminal facilities. Mr. John Kennedy, the chief engineer of the commission, who accompanied the members, has made the following instructive report upon fireproof grain elevators of the lakes:

The grain elevators examined were in the cities of Duluth, Minneapolis, Chicago, Cleveland and Buffalo, and they comprised examples of all the chief types of elevators of wholly fireproof materials, which are known to have been built, or are being built on this continent. For convenience of description and consideration the elevators examined may be divided as regards bin construction into four types: (1) Those having rectangular grain bins built of steel plates; (2) those having cylindrical bins, commonly called tank bins, built of steel plates; (3) those having cylindrical bins built of tiles strengthened with steel hoops, and (4) those having cylindrical bins built of concrete strengthened with steel hoops.

Of the first type, or those having rectangular steel bins, a notable example is the Great Northern elevator at Duluth. It is of 3,000,000 bushels capacity, and is the largest and amongst the first of its kind. The bins are 14 ft. 9 in. square by 85 ft. high, holding 14,500 bushels, except a few which are of two-thirds, half or quarter capacity. The bins are arranged in straight rows lengthwise and crosswise and they are formed of steel plates of such lengths as to reach from corner to corner, the corner junctions being formed with four angle bars and rivet fastenings. The plates are stiffened by angle bars riveted to each side and by flat tie bars reaching across the bins, placed edge up. For the smaller bins, the space of two standard bins is divided into three, one is divided into two, or one into four. The bins have steel plate hopper bottoms at suitable height for allowing cars to pass beneath, and they are carried on steel columns reaching through the ground floor to foundation piers beneath. The floor which covers the heads of the bins and the next above it are, for some unexplained reason, of wood plank on steel joists, but all other floors are of steel or other fireproof materials. There is no framing or walls surrounding the bins, but they are protected from the sun and weather by corrugated iron sheeting attached to them in such a way as to give a 6-inch air space all around between the sheeting and the outside plates of the bins. The framing of the building above the bins is of steel covered with iron sheeting and fireproof roofing. The elevator legs and heads, the garsers, weighing hoppers and spouting are all of steel. With the exception of the two wooden floors, the wooden casings and frames of the cleaning machines, the elevator belts, driving ropes and a few small wooden sills for machinery, everything worth noting, of both building and machinery, is of non-combustible material. The elevator is fitted for receiving from cars and delivering into large boats. For receiving it has two tracks extending through the building lengthwise, and holding nine cars each, and for delivering it has telescope spouts supported by cranes and convenient tackle. The machinery is all of the most improved description and largest capacity, and is driven by electricity. Construction was commenced about two years ago, but owing to delays in obtaining steel and difficulties incident to a novel character of construction, it is hardly yet completed. About a fourth of the bins and machinery have been in use, and are found to work well, and the remainder are very nearly ready for use.

At Minneapolis there are also examples of elevators having square steel bins, in which the square bins are essentially the same as those in the Great Northern elevator of Duluth, but the Minneapolis elevators, as a whole, differ from the Great Northern in having only part of their storage capacity in square bins, and the remainder in round bins. In the Pioneer steel elevator of Minneapolis, for instance, finished about a year ago, and of about 1,200,000 bushels capacity, there is a central working house, which contains the receiving and delivering machinery, which is fitted with square steel bins, but they are of only 200,000 bushels aggregate capacity, and the main storage capacity of the elevator is in ten circular steel bins of 100,000 bushels each, arranged in two annexes of five bins each. The square bins of the Pioneer are built and supported in substantially the same way as those of the Great Northern, but their outer sides stand open to the weather, without walls or sheeting of any kind. In the working house containing the square bins, the ground floor is of concrete and upper house floors, frames and sidings are of steel. Everything about the whole elevator and annex bins is of non-combustible material, except the belts and cleaning machines. Another Minneapolis elevator, of 1,800,000 bushels capacity, under construction, is to be of practically the same construction as the Pioneer, except that the tank annex is to be all at one end and everything but the belts will be non-combustible. Even the cleaning machinery will have steel casings and frames. The elevator is notable as being mainly owned by its builders, who are known as elevator builders of great skill and experience, and who may be considered as building that which their skill dictates as best suited to the requirements of the place, and most likely to be profitable as a venture.

Of the second type of steel elevators, or those having circular bins of steel plates, amongst the early examples are the electric elevator at Buffalo, and the Canadian Pacific railway elevator at Fort William, Ont. Later examples are the Great Northern of Buffalo, and the storage annex of the Pioneer steel elevator at Minneapolis; and the latest are the American Linseed Co.'s, and the Buffalo Elevating Co.'s elevators under construction in Buffalo, and the annex of another under construction in Minneapolis. In all of these, except the Great Northern and the Buffalo



Elevating Co.'s, under construction in Buffalo, the bins are simple cylindrical tanks built of steel plates, and placed in rows with their bottoms at ground level. The grain is taken in from grain boats or cars by machinery placed in a house at the end of the rows or groups of bins, and is sent to the bins by overhead conveyors which carry and drop it into any desired one. Beneath each row of bins is also a conveyor by which the grain is carried from any bin back to the working house, where it is elevated and shipped or restored as may be desired. The bins are roofed overhead, but the sides are not covered. In the Buffalo examples, the bins are of various sizes, but in those at Minneapolis they are all of about 50 ft. diameter and 100,000 bushels capacity each. In the Great Northern elevator of Buffalo, the circular bin system is quite differently treated. In it the bins are all supported on steel columns with their hopper bottoms at about the usual spouting height above the ground floor, and the elevator legs and working machinery, instead of being all at one end, is distributed throughout the house, and the grain is spouted from the bins to the boots, and from the heads to the bins as in ordinary elevators. There are thirty circular bins of about 39½ ft. diameter, and 75,000 bushels capacity each, and in their interspaces are twenty-seven circular bins of about 15½ ft. diameter and 12,000 bushels capacity. A number of the irregular shaped interspaces formed between the small and large cylinders, have been further utilized by connecting the cylinders by steel plates, thus making little bins of about 2,000 bushels capacity. The bins are housed around by steel framing and sheeting, and are surmounted by the usual upper stories and cupola for containing the elevator heads, spouting, weighing hoppers, etc. The elevator has a storage capacity of about 2,600,000 bushels, and is fitted for receiving from boats and for delivering to cars on tracks outside the house. In the elevator of the Buffalo Elevating Co. (practically the Lehigh Valley Railroad Co.), the round steel bin system is being skilfully used in still another way. It is yet in the early stages of construction, but it is intended to be a working and storage house for receiving from lake boats and delivering into canal boats and cars. The circular bins are supported on steel columns, with their bottoms at spouting height above the ground floor. They are 15½ ft. in diameter by about 70 ft. high, and placed a foot apart, which gives circular bins of about 10,500 bushels capacity and interspaces of about 5,000 bushels capacity, which are utilized as bins.

The third type of fireproof construction, or that in which the bins are of tiles, has thus far been used only for storage annexes, and the only examples seen are two in Minneapolis. In these the bins are circular, of 50 ft. diameter and 100,000 bushels capacity each. Their bottoms are at ground level, on concrete foundations, and they are filled and emptied by conveyors overhead and underneath. The walls of the bins are of specially molded glazed hollow tiles laid in two thicknesses, with steel hoops built in to resist the internal pressure of the grain. Only the inside of the bins is used for storage; the interspaces are not utilized.

Of the fourth, or concrete type, there is only one example, and that is an unfinished elevator at Duluth. The bins proper are being built of circular form, and in rows at about 4 ft. clear distance apart, with connecting walls to separate the interspaces, which are also intended to be utilized, are of about 30,000 bushels capacity each. The walls of the bins are of high class concrete, 12 in. thickness at the lower part and about 9 in. at top, and they are strengthened by steel hoops and diagonal wire lacing, built in. The bins are being roofed over, but they are to have no housing around them.

It is obvious, on considering the main characteristics of the elevators described, that the new materials which have been adopted in order to make them fireproof have in great measure governed the larger features of the elevators as well as the details of construction. When wood alone was used the rectangular plank bin was so clearly the best that no other was used, and the limitations of the material and mode of construction practically limited the general arrangement to groups of rectangular bins of 15,000 bushels or less capacity each. Bins of such material and sizes have the advantage of suitability for the storage of grain of all sorts and conditions, and lots of all usual sizes; but being of inflammable material, the risk of fire made it prudent to keep the aggregate capacity of the group, or single elevator building to something like a million bushels. On the other hand, steel, the first and most generally adopted material for wholly fireproof elevators is best suited to the construction of bins of large size, of say 100,000 bushels capacity, and of circular shape, and being fireproof they may be safely grouped to give any required aggregate capacity. In early examples of steel elevators the bins were therefore made circular, chiefly of large capacities, and with bottoms at ground level, but this arrangement is unsuited to the storage of grain in small lots, and it involves the use of grain handling machinery of very limited capacity, and gives limited freedom in changing heated grain from bin to bin. Its main advantages are economy of construction and freedom from fire risk. An improvement in the circular bin system which eliminates some of its most serious defects was that adopted in the Great Northern at Buffalo by raising the bottoms of the bins to spouting height above the ground, putting small round bins in the spaces between the large and making bins of the remaining interspaces, and by suitably increased working machinery of ordinary type. A still further and, for most conditions, the best development of the circular bin system, is that on the Buffalo Elevating Co.'s elevator, in which the bins are only about 11,000 bushels capacity, each with utilized interspaces of about half the capacity, and all at high level so as to be served by ordinary working machinery. While the circular bin system was being thus developed a more radical departure was made in the use of steel by discarding the circular bin altogether and reverting to square bins of moderate size, placed at high level, and served by ordinary machinery enclosed by steel housing, or in other words, in using steel in such a way as to make an enlarged and improved copy of the best features of wooden elevators, while avoiding their inflammability. A compromise type suited to certain requirements, and of moderate cost, is that of the Pioneer elevator in Minneapolis, in which there is a working house with square steel bins of convenient size, and an annex of large circular steel bins to make up the total required storage capacity.

The tile and concrete systems are obviously the outcome of efforts to obtain suitable materials other than steel plates for the construction of incombustible bins. Thus far the bins under both systems have been only of large size and circular form and seated at ground level, and they have therefore the same limitations as to use as have steel bins of the same size and form. As regards the action of the various fireproof ma-

terials upon the grain in contact with them and the sufficiency of the materials to bear the strains of service, experience is short, but so far as it goes indicates that none of them do any harm whatever to the grain nor are they harmed by grain in any condition. It was at one time feared that steel bins might sweat or heat the grain, but nothing of the kind has taken place. For the resisting of load strains steel bins can of course be made of any required strength, and tile bins as built and used have proved to be of ample strength. Some of the newly built concrete bins at Duluth failed on a test made by filling an interspace with grain, but the failure has not deterred the owners and builders from continuing the building of the other bins required to make up the full intended number.

In applying the information thus set forth to the case of the proposed Montreal harbor elevators, the following are the main questions which arise and the ways in which, in my judgment, they should be met. The questions are, for convenience, worked out for one elevator of 1,000,000 bushels capacity, but the reasoning is applicable to other capacities and more elevators.

1. As to whether the elevator building be built of wood or of fireproof materials. The question obviously touches both the owner and the user, and its solutions as regards both may be made on the following assumptions: A million bushel wooden elevator will cost, without wharf conveyors, say \$300,000, and its insurance rate may be taken at about 2½ per cent. One of fireproof materials will cost about \$400,000, and on it there need be no insurance. The interest on first cost will be, say, 3½ per cent. per annum, and alike for both kinds of elevators. An elevator like all other plant used in trade will soon become obsolete because of changing conditions, and must be practically rebuilt or replaced long before worn out. A renewal fund should therefore be set aside, which, at say 3½ per cent. yearly compound interest, will provide for total renewal in say twenty-five years. Such renewal fund will be equal to 2.9 per cent. per annum on the first cost. Maintenance and working expenses will about balance in the two kinds of buildings, and need not be taken into account. The average storage term of grain taken into the elevator for storage during navigation season, apart from that merely transhipped, may be taken at ten days; and the grain insurance rate for that term in a wooden elevator may be taken at 0.25 per cent. Probably no insurance need be carried on grain in fireproof elevator, but in case it should be required by banks making advances it would be about 0.05 per cent. For winter storage the term may be assumed at two months, for which the insurance rate would be about 0.75 per cent. in a wooden elevator, and 0.15 per cent. if demanded in a fireproof one.

The owner's yearly investment and insurance expenses will then be:

For a wooden elevator—	
Interest, 3½ per cent.; renewal fund, 2.9 per cent.; insurance, 2½ per cent.; total, 8.9 per cent. on \$300,000; first cost per annum .....	\$26,700
For a fireproof elevator—	
Interest, 3½ per cent.; renewal fund, 2.9 per cent.; (insurance, none); total, 6.4 per cent. on \$400,000; first cost.....	25,600
Difference per annum to owner in favor of fireproof elevator.....	\$ 1,100
The grain shippers' insurance charges will be:	
With a wooden elevator—	
For summer, ten day insurance.....	0.25 per cent.
For winter, sixty day insurance.....	0.75 per cent.
With a fireproof elevator—	
For summer, ten day insurance.....	0.05 per cent.
For winter, sixty day insurance.....	0.15 per cent.

The results of the estimates would, of course, be changed by change in the assumed data, but it is clear that a fireproof elevator could cost the commissioners no more per annum than would a wooden one, and that it would save to the shippers who store in it about four-fifths of their storage insurance. This conclusion is confirmed by the fact that almost all elevators built within the past two years are of fireproof material. I would therefore recommend that any elevator built by the commissioners for general use be made fireproof.

2. The chief requirements to which an elevator for the central part of the harbor should comply as regards its machinery and storage arrangements: It must, of course, be placed and equipped so as to take in grain from canal boats and cars, and to deliver to, say, four ships at any of ten berths, and also deliver to harbor lighters; and it should perform any or all operations separately or together. Grain shipments through Montreal are usually made up of small lots, whose identity must be preserved and the elevator bins should therefore be of small size, say about 12,000 bushels capacity each. These conditions would, on the whole, be best fulfilled by an elevator resembling the Great Northern of Duluth in its main features but greatly reduced in size and modified in structural details. The bins should be built of steel.

#### COMPASS PLATFORM TO BE INSULATED.

Rear Admiral Bradford, chief of the bureau of equipment, has received an interesting letter from Lieutenant-Commander F. M. Bostwick, navigator of the Oregon, in which he describes the effect on the standard compass of a "ground" in the bridge electric circuit. While the Oregon was steaming up the China coast on course N. E. by N., the navigator reports that it suddenly became necessary to change the course about a point to the eastward by bridge and steering compasses, to make the allotted course by standard. Upon investigation it was found that the trouble lay with the standard compass. A time azimuth taken showed the deviation of the standard compass to be 10° and 4-100 min. east, the tabulated deviation being 1° and 4-100 min. Upon inquiry it was found that the bridge circuit had just been turned on, and later a "ground" was discovered. Experiments showed conclusively that the fault was due to this "ground." In order that this trouble may be avoided in the future, the secretary of the navy has authorized the chief of the bureau of construction and repair to inform the commandants of the navy yards and the superintending naval constructors that hereafter the platforms for carrying the standard compass should, whenever practicable, be insulated from the structure of the ship by three-eighths of an inch of hard rubber fiber, and that the bolts securing platform stanchions to the structure should also be insulated by bushings and washers of the same material; also that all horizontal railings within 12 ft. of the compass should be made either of wood or Manila hemp rope.—Electrical World and Engineer.




**SPECIAL CARRIER FOR LOADING COAL ON VESSELS.**

C. O. Bartlett & Co. of Cleveland have lately installed at Fairport, Ohio, for the Pittsburg Coal Co. a special carrier for loading coal on vessels. The carrier handles with equal facility either hard or soft coal and has been the subject of considerable attention from coal shippers. The contrivance is of extremely simple construction and is operated as follows: The coal to be loaded on the boat is dumped from hopper bottom railroad cars into a large hopper underneath the car, and over the lower end of the carrier the coal is fed onto the carrier by means of large slides or openings opened and closed by power. The coal is then conveyed up this continuous carrier and delivered into a spout, which feeds the coal into the boat from the carrier. This spout is so arranged that it may be raised or lowered at will. The spout is worked by a special hoisting engine, and is raised or lowered as desired, taken up in a perpendicular position entirely out of the way of the boat as it passes along, and quickly lowered again. The spout is also made to telescope so that when the boat

It will be some months before the keel of the sheathed protected cruiser St. Louis is laid at this ship yard. Assistant Naval Constructor Robinson said that the keel plates for this vessel will go down on the blocks vacated by the cruiser Denver when the latter is launched. The Neafie & Levy Co. are unable as yet to assign a date for this event.

Constructor Hanscom and Mr. Robinson are very busy these days, dividing their time equally between Neafie & Levy's and Cramps' ship yard. They have begun the inspection of the first plates which have been delivered at the latter plant for the keel of the armored cruiser Pennsylvania, which is to go down alongside of her sister ship, the Colorado, and incidentally on the same spot where the Maine was built. In this connection it may be said that the builders have a little problem to solve in putting down the Pennsylvania. She is over 100 ft. longer than the Maine and will require many additional keel blocks. In the meantime the keel of the Colorado has been completed throughout its length and the latest naval estimate places the vessel at 3 per cent. completed. As she is an exact duplicate of the Pennsylvania, having them built next to each other is a very convenient arrangement, the same overhead traveling crane supplying both with material.

The Russian battleship Retvizan will sail from Cramps' ship yard on



Showing the carrier with the spout lifted up out of the way, so that the vessel to be loaded can be moved along either way.

Designed and built by C. O. Bartlett & Co., Cleveland.

is being filled, the spout itself may be kept constantly full of coal, thus keeping the breakage at a minimum. The whole machinery is operated with less than 50 H.P., and loads up to 1,000 tons of coal per hour. When it is taken into consideration that the whole machinery is operated with less than 50 H.P. and with very little labor, it cannot fail to appeal to those who have a large amount of coal to handle.

**SHIP BUILDING AT PHILADELPHIA AND VICINITY.**

Philadelphia, Pa., Aug. 14.—The torpedo boat destroyer Bainbridge, building at Neafie & Levy's ship yard, will be launched Tuesday, Aug. 27. After a series of vexatious delays President Mathias M. Seddenger was able to definitely fix the date, and the program will be strictly adhered to. The honor of christening the destroyer will devolve upon Miss Louise Adele Bainbridge-Hoff, daughter of Capt. William Bainbridge-Hoff of Washington. Miss Bainbridge-Hoff is a sister of Lieut. Arthur Bainbridge-Hoff, United States navy, and a great granddaughter of Com. Bainbridge.

The launch of the Bainbridge and that of her sister ships, the Barry and Chauncey, all of which are side by side on the stocks, has been delayed by changes decided upon after Rear Admiral Bowles assumed the duty of chief constructor of the navy. One of the boats, built elsewhere on the same design, found difficulty in attaining the speed required by her contract and investigation led to the belief that changes in the stern lines to allow a freer escape of the water would increase the speed. The alteration has been effected by a slight cutting away of the stern aft of the propellers and arching it somewhat above the propeller blades. The speed demanded by the contract for these boats is 29 knots. Naval Constructor J. H. Hanscom, the government inspector here, believes that a full knot will be gained under the changed conditions and his opinion is shared by the builders. When the destroyers go overboard they will be practically ready for their trial trips. The Bainbridge is 95 per cent. completed, the Chauncey 90 per cent. and the Barry 88 per cent. Their boilers have been tested several times under steam, and in these trials have proved satisfactory.

her builders' trial trip Saturday, Aug. 24. The latter will be run over the triangular course between Five Fathom Bank, Winter Quarter and North East End light-ships, outside the Delaware capes. The contract requirement is for a speed of 18 knots during 12 consecutive hours steaming. It is the intention of the builders to put the battleship through an equally stringent test with the one which she will undergo on her trial acceptance trial.

A rapid piece of work is being performed on the Clyde liner Comanche in Cramps' dry dock. This vessel reached the yard about three weeks ago to be lengthened 45 ft. and since that time the separation of the hull has been made and the intervening space is now in frame. It is expected that she will be in service within a month. The additional length will result in almost double cargo capacity. The work includes a thorough renovation of the interior of the steamship. In addition to the vessel construction which they have under way the New York Ship Building Co., at Kaighn's Point, Camden, N. J., is busily engaged in fitting the merchant steamship, formerly M. S. Dollar, now J. M. Guffey, as a tanker to run on the proposed oil carrying line between Sabine Pass, Texas, and Philadelphia. The M. S. Dollar is the pioneer vessel of the new ship building firm. It was originally contracted for by Robert S. Dollar of San Francisco, but was recently purchased by J. M. Guffey in the interests of the independent oil operators of Texas.

The new ferryboat Chancellor of the New York & College Point ferry line was successfully launched at the ship yard of the Townsend & Downey Ship Building & Repair Co., Shooter's island, N. Y., last week. The new boat is 175 ft. in length, 37 ft. breadth of beam, 60 ft. 6 in. over guards and 16 ft. depth of hold, and built of white wood throughout. She is equipped with single engines of the walking beam type.

Buffalo and return \$3.70, via the Nickel Plate road every Tuesday and Saturday. Three-day limit. Inquire of nearest ticket agent or E. A. Akers, C. P. & T. A., 189 Superior street, Cleveland, O. Tel. Main 218.  
144 Aug. 31.




### PROGRESS OF WORK AT NEWPORT NEWS, VA.

Newport News, Va., Aug. 14.—This week witnessed the completion of the new pumping system for emptying the two large dry docks at the ship yard. The Newport News Ship Building & Dry Dock Co., it seems, takes the initiative in many things pertaining to ship building. It was the first private yard to undertake the building of a large Simpson dry dock, it was the first to introduce the electric cantilever traveling crane in ship construction; it was the first to use an electric revolving crane in ship building, and it has always taken the lead in the use of the most modern tools and methods employed in this kind of work. Now it has the most remarkable pumping system in America, probably in the world, being the only one applied to two mammoth dry docks. Their capacity is greater than the capacity of any other dry dock pumps known to ship building. For some years, in fact since the yard was first laid out, a 600-ft. basin has been doing all of the docking for the ship yard, but several years ago Collis P. Huntington realized that another and a larger dock was needed to properly handle the new and repair work of the company, and he gave orders for the construction of a basin nearly 900 ft. in length,

high. There are two butterfly valves operated by electricity from the pump house. The new dry dock has been in operation some weeks and it is handled with remarkable ease and dispatch. At one time there have been in it as many as three steamers at one time, and ever since its opening it has been kept constantly at work, so great has been the amount of repair work secured by the yard. For several weeks the old dry dock has been occupied by the North German Lloyd liner *Main*, which is being rebuilt at a cost of nearly \$1,000,000. The old dock was operated for the first time under the new pumping system this week, with the floating of the *Main*, which will be ready to leave the ship yard about Oct. 1, practically a brand new vessel and with no sign of the damage it suffered in the Hoboken pier conflagration.

The next launching at the ship yard will occur Sept. 28 or Oct. 5, when the Pacific Mail leviathan *Siberia* will go overboard. It is probable that the Morgan liner *El Alba* will be launched at the same time. Preparations for the *Siberia* launching have commenced. The Old Dominion steamer *Hampton*, which was damaged in collision with the steamer *Jamestown*, resumed her runs between Old Point and Norfolk early in the week after being repaired here. The British steamship *Wragby*, which collided July 25 near Bermuda with the British ship *Foyle*, is now at the



Showing the spout lowered into the hold of the vessel. It also shows the engine on top of the spout, used in raising and lowering the spout at will. Designed and built by C. O. Bartlett & Co., Cleveland.

which is in use today and which is capable of receiving at one time two of the largest warships afloat. The largest merchant ship ever built can be docked in the new basin with room to spare, and it will be some time before a vessel will be floated which cannot find a berth in it.

The pump which emptied the 600-ft. dock in about an hour and a half is located to the south of the basin. With the completion of the new pumping system this house will be closed and kept for emergency. The new pump house is situated between the great new dry dock and the old basin, about 53 ft. from the former and 103 ft. from the latter. A 9-ft. circular tunnel connects it with the new dock and a 7-ft. circular tunnel connects it with the old one. Should the occasion arise, both docks could be emptied simultaneously. The combined highest capacity of the pumps is 410,000 gallons a minute, or 24,600,000 gallons an hour. There are two large pumps with a capacity of 200,000 gallons a minute each, and one small pump with a capacity of 10,000 gallons a minute. The small pump makes about 200 revolutions a minute, throwing out about a barrel with every revolution. It is operated nearly to its full capacity.

The large pumps are not run to their full capacity, but ordinarily they throw out about 125,000 gallons of water a minute. They have suction pipes 5 ft. in diameter, while the small pump has a 22-in. suction pipe. The large pumps are used to empty the basins until the water gets toward the bottom, when the smaller pump is put to work draining it off. With the pumps working at average capacity, the large dry dock can be emptied in about two hours; the 600-ft. dock in a little more than an hour. This is remarkably quick time and it cannot be approached by any other dry dock in the country, three and four hours being required to empty some docks not nearly so large as those here.

The old pump house, operating only one dock, required two engineers and several firemen. The new pump house, operating two docks and doing more than double the work, requires but two men, one engineer and one electrician. The new pumps are operated entirely by electricity, the machinery consisting of two 800 H.P. motors, for which power is furnished by three 800 H.P. dynamos. As the water is pumped from the dry docks it passes to a brick culvert 50 ft. long, 15 ft. wide and 5 ft.

ship yard for repairs. The *Wragby* was struck by the *Foyle* opposite the forward hatch. Her plates were stove in from the water line up, the decks started and other damage done to rail and top gear. The Clyde line steamer *Yemassee* is at the yard for repairs. The *Yemassee*, the schooner *Josie L. Burt* and the large barge *Ohio* were all put in the dry dock together. The Pacific Mail liner *Korea* and the steamer *Simon J. Murphy* have been taken out of the dock. A number of other vessels, mostly barges, are undergoing repairs. The ship yard has recommended to the navy department some changes in the plans for the protected cruiser *Charleston*, which, it has reason to believe, will operate to the advantage of this class of ships.

The trim little passenger steamer *Norfolk-on-the-Roads*, which ran day and night between Old Point Comfort and Sewall's Point for the Norfolk & Atlantic Terminal Co., was burned to the water's edge last Thursday at her dock at the latter place. The *Norfolk-on-the-Roads* was formerly the *Salacia* and was built at Bath, Me., for the Maine & Coastwise Steamship Co. For several years she had been plying between Cuba and northern ports. She was purchased in 1900 by the Norfolk & Atlantic Terminal Co., taken to Baltimore, where she was refitted and greatly improved and then brought to these waters. She was 120.9 ft. in length, 26.2 ft. in breadth, 10 ft. in draught and had a gross tonnage of 332.4 and net of 168.4. The company will replace her with a new steamer if it is found that the hull is beyond rebuilding.

The yacht *Independence*, owned by Thos. W. Lawson of Boston and built to defend the America's cup, has twice this summer been docked at the yard of the Thames Ship Building Co., New London, Conn.

A new chart, in colors, of Erie harbor and Presque Isle, has just been issued and may be had from the Marine Review. A new chart of Buffalo harbor and Niagara river to the falls is also in print.

Percy & Small, Bath, Me., will launch the four-masted schooner *Cordelia E. Hayes* in a few days.



### EXPERT'S COMMENT IN HYACINTH AND MINERVA TRIALS.

Reviewing the interesting series of trials of the Hyacinth with Belleville boilers and the Minerva with cylindrical boilers, an expert in the London Times says:

The trials have been made by request and under the supervision of the boiler committee appointed for the purpose of investigating the very important question concerning the wisdom of fitting water tube boilers on board our war vessels, and in this capacity their investigations are necessarily directed more particularly toward the Belleville boiler, owing to its having been adopted in our navy, for large war vessels, practically to the exclusion of other types. It should be borne in mind that several members of the house of commons have declared, in the most emphatic manner, their opinion that water tube boilers generally, for marine purposes, were both dangerous and excessively wasteful of fuel. It was in consequence of these declarations that the committee was appointed to investigate the truth of such statements and thereby alleviate the anxiety in the public mind. It was desirable to make comparative trials between the cylindrical and Belleville boilers, working, as far as possible, under precisely similar sea-going conditions. It was difficult to make such comparisons, owing to the fact that our navy does not possess two vessels of any considerable horse power, having precisely similar dimensions, lines, displacement, and propelling machinery, fitted with boilers of the two types in question. The best that could be done in the circumstances was to select two second-class cruisers of practically equal displacement and maximum indicated horse power, the one being fitted with Belleville boilers, the other with those of the cylindrical type commonly known as Scotch boilers.

The general dimensions of the two ships and of their machinery are as follows: The Hyacinth—Length, 350 ft.; breadth, 54 ft.; mean draught, 20 ft. 6 in.; displacement, 5,600 tons; maximum horse power, 10,000; twin screw engines of four cylinders; high pressure cylinders, 26 in. diameter; intermediate pressure cylinders, 42 in. diameter; low pressure cylinders (2), 48 in. diameter; stroke, 2 ft. 6 in.; revolutions at maximum power, 180 per minute. The Minerva—Length, 350 ft.; breadth, 53 ft. 6 in.; mean draught, 20 ft. 2 in.; displacement, 5,600 tons; maximum horse power, 9,600; twin screw engines of three cylinders; high pressure cylinders, 33 in. diameter; intermediate pressure cylinders, 49 in. diameter; low pressure cylinders, 74 in. diameter; stroke, 3 ft. 3 in.; revolutions at maximum power, 140 per minute.

It will be noted that the vessels and their propelling machinery are not precisely comparable; and consequently so far as speed of ship per I.H.P. or efficiency of the engines are concerned, no heed need be taken of the results of the trials. The trials have been carried out for the purpose of comparing, as far as practicable, the efficiency of the two types of boiler from two points of view—first, as producers of steam from a given weight of coal, in other words, coal consumption; secondly, their capacity for producing an ample and constant supply of steam for a long run at maximum speed, having no special regard to economy of fuel. Those who have so bitterly criticized the adoption of the Belleville boiler in our navy have laid special emphasis upon alleged excessive coal consumption, and in the second place they have expressed their conviction that it would be impossible to maintain a high speed for any considerable period with these boilers.

The trials having now been completed; a brief summary of the principal results will be interesting to show whether the confident assertions that the strength of our navy has been jeopardized by the introduction of these boilers have, or have not, any foundation.

First coal consumption trial, 24 hours' duration, 2,000 H.P.:

	Mean. I.H.P.	Actual evaporation of water per lb. of coal.
The Hyacinth .....	2,053	9.69
The Minerva .....	2,142	8.54
Result—13.4 per cent. in favor of Hyacinth's boilers.		

Second coal consumption trial, 24 hours' duration, 5,000 H.P.

	Mean. I.H.P.	Actual evaporation of water per lb. of coal.
The Hyacinth .....	4,992	9.41
The Minerva .....	5,155	8.87
Result—6 per cent. in favor of Hyacinth's boilers.		

Third coal consumption trial, 12 hours' duration for Hyacinth, and eight hours for Minerva, 8,000 H.P.:

	Mean. I.H.P.	Actual evaporation of water per lb. of coal.
The Hyacinth (12 hours).....	8,105	9.89
The Minerva (8 hours).....	8,114	8.19
Result—20.7 per cent. in favor of Hyacinth's boilers.		

Fourth coal consumption trial, eight hours' duration:

The Hyacinth was tried for eight hours at a maximum power of 10,000 H.P., but no trial was made of the Minerva at full power, as it was considered undesirable to force the cylindrical boilers to their original specified maximum power of 9,600. The mean I.H.P. for eight hours in the Hyacinth was 10,181 and the actual evaporation of water per pound of coal during that period was 8.8, showing that at the maximum power of over 10,000 the Hyacinth boilers were doing better duty per pound of coal than the Minerva cylindrical boilers did at 8,000 H.P., the latter having evaporated only 8.19 of water per pound of coal at the lower power.

After these trials certain modifications were made in the boilers of the Minerva, and upon trial, with half the boilers, burning coal at the rate equivalent to that consumed upon the 8,000 I.H.P. trial, the evaporation per pound of coal was found to be about 9 per cent. better, consequently, in comparing the results of the third coal consumption trial, it would perhaps be fair to place 9 per cent. to the credit of the Minerva.


The vessels were now prepared for the last of this series of trials, which consisted of a run from Plymouth to Gibraltar, each vessel to maintain, as nearly as possible, 7,000 H.P., and after touching at Gibraltar to proceed until the coal on board was exhausted. The return run from Gibraltar to Portsmouth was to be at maximum possible speed, without any regard to coal consumption. Both vessels started at the

appointed time and touched at Gibraltar, signalling all well, and proceeded to exhaust their coal supplies. After steaming 103½ hours at 7,000 H.P. the Hyacinth was obliged to put in to Gibraltar, owing to having lost a considerable quantity of water through leaky feeding connections. The Minerva returned, after steaming about 150 hours, having stopped for some two or three hours owing to derangement of the machinery. Taking into consideration the time under way and the H.P. developed, the coal consumption per pound of water evaporated appears to be slightly in favor of the Hyacinth, but for practical purposes the results may be taken as equal. It is only fair to note, however, that the loss of water, through defective feed connections, must have told considerably against the efficiency of the Hyacinth boilers.

Regarding the home trip the expert says that from a scientific standpoint the most instructive part of the race was when the Minerva steaming at 8,400 I.H.P. drew away from the Hyacinth steaming at 9,400 I.H.P. It showed that the Minerva possessed an advantage, either in the form of her propellers or in the superiority of her lines, for when the Hyacinth made a sprint of three hours at 10,000 I.H.P. she merely churned the water without appreciably increasing her speed.

### COMPACTNESS IN GENERATING SETS.

A distinctive feature of small and medium sized generating sets is the compactness which is secured in late designs. Herewith is illustrated one which possesses some distinctive features of novelty. The running gear of the engine is entirely enclosed, all parts are oiled from sight feed oiling devices on the exterior, and access to the interior is provided through a tight fitting door. The engine is of the compound vertical type and its general appearance is very similar to the double vertical engine of the same company, the B. F. Sturtevant Co. of Boston, Mass., by whom a line of these generating sets is now being built from their own designs. The engines range from a 4-7x4 up to a 8½-15x7. The cylinders are in a separate casting from the frame, to which they are bolted, thus rendering them easily removed for repair. Two valves are employed, one controlling admission of steam to each cylinder, and motion is transmitted through a rocker, provided at its outer end with an accurately fitted ball-and-socket joint, and at its inner end connected by link to the valve stem yoke. The



cylinders are thoroughly lagged to prevent condensation, and danger of damage from water in the cylinders is avoided by the use of special automatic relief valves.

The generator is of the standard four-pole Sturtevant type, with magnet frame of special magnet steel, with field cores cast on. To these the pole shoes are secured by cap screws. The armature is of the barrel wound toothed drum type. Ventilation is effected by the use of specially constructed air ducts between the laminae of the core. These convert the armature into a blower and create a strong draft through the windings. The winding for low voltage machines is of copper bars with easy bends. High voltage machines are wire wound with machine formed coils. The commutator consists of drop forged segments of pure copper, secured between cast iron flanges of spider construction, which allow free circulation of air.

All machines are fitted with carbon brushes mounted in holders of the sliding socket type. The field coils are double cotton covered and are rendered absolutely oil and water proof by saturation in a special compound and subsequent baking at high temperature. The armature is subjected to a similar treatment.


All machines are given a full load test for a sufficient time to bring every part to its maximum temperature, which never exceeds 40° Cent.

Mr. P. H. Cheney of the firm of P. H. Cheney & Sons, ship chandlers at Ashtabula, died at his home on Sunday afternoon. He was one of the best known marine men on the lakes and had had a long and useful career. For eighteen years he was light-house keeper at Ashtabula and for nearly twenty years past had been engaged in the ship chandlery trade at that port. He had a personal acquaintance with practically every captain on the lakes and was universally esteemed. His death was due to a number of complications from which he had suffered for a year past. He was 65 years old.



**AMERICAN BLOWER CO. AT PAN-AMERICAN.**

In block No. 26 of machinery hall, at the Pan-American exposition, is an exhibit of heaters, fans, engines, blowers, dry kilns, trucks and other kindred machinery, which is quite interesting and well worth the few minutes time necessary to inspect it by anyone who has use for such machinery. Almost every one is in-



terested in this particular line, as these devices enter into almost all lines of manufacture in some way or other. The booth this company has put up is one of the handsomest in the building. The general scheme is rendered in ivory white and deep green. This feature is some 20 ft. in height, being topped by a gable end resting on some very prominent

columns. Above same is a large painting nearly 60 ft. in height, designed to be somewhat emblematical of the American blower.


The company has another feature which attracts a great deal of attention, being a model of their widely known and very successful "moist air" dry kiln. This model has a glass side, enabling the spectator to see the exact operation of the kiln. They also have a large 140 in. full-housed steel plate fan running, being driven by an 8x8 marine type vertical engine, coupled direct to the fan shaft. From the discharge of this fan, which points upward, they have myriads of yellow and blue ribbons streaming up into the air. These colors, of course, are the college colors of the University of Michigan, and no Michigan college graduate goes by without noticing it, and it likewise always attracts a great deal of attention from the ladies. In the wall back of the exhibit they have fitted a 108 in. disc fan, which is about as large as one commonly sees in such a place. It is by no means the largest they build, however. They are also exhibiting a Moorehead automatic return steam trap in operation, which clearly shows how the trap drains condensation from heating surfaces and delivers it direct to the boiler. There is also a large pressure blower mounted on a Z iron base, on the other end of which is the vertical automatic high-speed engine for driving same. They are also showing a horizontal, automatic high-speed engine and a vertical low pressure engine, as well as their widely known A, B, C exhaust fans, the adjustable features of which have been so frequently enlarged upon that further mention is hardly necessary here.

The Greenfield Steam Engine Works, 5th and Cross streets, East Newark, N. J., reports phenomenal success with their engine output since the establishment of the company in 1874. Besides the manufacture of the "Greenfield" vertical, stationary, throttling and automatic and yacht engines, they manufacture horizontal and vertical, stationary and marine boilers; also many steam appliances and stationary and marine gas and gasoline engines. This company has furnished since the middle of June to the United States government eleven engines for new cruisers and have altogether on different cruisers 184, and in other branches of the government bureau of engraving and printing, hospital service, etc., from twenty-five to thirty more. The Standard Oil Co. is a large purchaser, having taken in all about 250 engines. In the gas works of the United States there are installed from 575 to 600, and the same number sold to other companies and individuals throughout the country. The engines, which are built for all purposes, range from 3 to 300 H.P. The motto of the company has come to be "Once a customer, always a customer." It would certainly pay intending purchasers to write for circulars and full information before ordering elsewhere.

The Falls Hollow Staybolt Co., Cuyahoga Falls, Ohio, have just issued a card of sizes of staybolts for use in locomotive, marine and stationary boilers. The card is accompanied with a little circular setting forth the advantages of the staybolts and both will be sent to anyone upon application.



Electrolytic action on Brass Tubing which was taken out and replaced by "Benedict-Nickel."  
—From a photograph.


**Condenser Tubes**

made from

**"Benedict-Nickel"**

resist **Corrosion** and the  
destructive effect of

**Electrolysis:**



"Benedict-Nickel" Tubing in perfect condition after 28 months' service.  
—From a photograph.

*"Benedict-Nickel" Condenser Tubes are perfectly homogeneous and highly non-corrosive. They are rolled from solid cylindrical billets which contain absolutely no zinc nor any other weakening metal.*

The illustration shows how "Benedict-Nickel" Condenser Tubes are made. The spiral formation given to the walls of the tubes increases their tensile strength 50% over brass, and makes them the toughest and strongest tubes manufactured.

Another advantage is that, owing to their extreme stiffness, they can be made of thinner gauge, and yet be stronger than the thicker brass or copper tubes of the same diameter. The economical feature will therefore be readily understood.

A treatise on "Electrolysis of Condenser Tubes" mailed upon request.

We are also among the largest manufacturers of Seamless Brass and Copper Tubing, and the **ONLY** manufacturers in the United States of this tubing rolled spirally from a solid billet. This is the process used in the manufacture of "Benedict-Nickel."

**BENEDICT & BURNHAM MFG. CO.,**

MILLS AND MAIN OFFICES, **WATERBURY, CONN.**

DEPOTS: **NEW YORK, 253 Broadway.**

**BOSTON, 172 High Street.**

V. W. W. N. Y.



## ON SCREW PROPELLERS.\*

Propellers have usually been designed up to the present time by means of practical rules deduced from trials and comparisons, or from empirical formulæ having no connection among themselves, depending chiefly on workshop tradition, and personal prejudices of the designer, varying in different countries, and showing generally very little knowledge of the working of screws in water. Imperfect as this method is, so long as screws of large diameter and slow rate of revolution were dealt with, giving moderate speeds, the approximate formulæ sufficed, and often gave remarkably efficient propellers, although sometimes resulting in surprises and failures. But now that higher speeds are sought, by increasing the rate of revolution of the engine, the screw conditions become more difficult, the old rules are no longer suitable, and others more scientific are required, based on the laws of fluid resistance, which will make it possible to calculate exactly all the elements to suit varying conditions of power, speed, and revolutions.

Some years ago the author presented to the Association Technique Maritime a paper on the general theory of propellers, based on the resistance of a submerged plane. Encouraged by its favorable reception, he endeavored to obtain further proof of its correctness, by comparing the results of the trials of a large number of screws with the results predicted by his theory, and found them in close agreement. He has found it possible to explain hitherto obscure peculiarities in their action, and to discover the rationale of the empirical rules in use. To recapitulate briefly the principles upon which the theory is based, the author has shown that an element of a narrow inclined plane moving through a fluid experiences a resistance which can be resolved into two components, one of which represents useless resistance, and the other useful thrust, which is perpendicular to the first. These two component forces are related to each other in a manner independent of the speed, and depending only on the angle made by the plane to the direction of motion. He has shown that the useful component is a maximum when the plane is inclined at an angle of a little less than  $3^\circ$ .

In order to get the best effect from the blade of a propeller, each element of it should have this angle of incidence. The surface fulfilling this condition is a helicoidal one of variable pitch. The author proceeds to show how to draw the variable pitch to produce the required result, and he calls a "normal screw" one in which this angle of incidence has been secured for every part of the blade, and in which the diameter of the boss bears a certain fixed ratio to the diameter of the screw. A screw of uniform pitch can be altered so as to give the desired constant angle of incidence, by twisting the blades in the boss to a greater pitch. The chosen angle of incidence, which is  $2^\circ 52'$ , corresponds to a mean pitch equal to 1.25 times the diameter. He proposes to use certain definite shapes of blade, the curved outlines of which can be mathematically expressed. Propellers designed according to this theory will have all their dimen-

\*Extract of a paper read before the Institution of Naval Architects by M. Drzewiecki.

sions, such as diameter, pitch, surface, diameter of boss, etc., expressible as a function of one of them. He proposes to state them in terms of the advance of the screw per revolution, and he thinks that great benefits would result if all propellers were designed upon some uniform theory, such as he sets forth.

All screw propellers which give satisfactory results may be said to approach more or less perfectly to a common ideal type, of which the elements are strictly determinable by the general laws of mechanics and fluid resistance, and these are mutually related in a manner explained by the author in a paper communicated to the International Congress of Naval Architects in Paris in 1900. The name of "normal screw" has been given to a perfect type of screw determined by exact calculation. It has been shown that all the geometric dimensions are proportional to one of the elements, the advance per revolution. It follows that, if all the elements of the "normal blade" be expressed in terms of the advance per revolution, a series of abstract numbers will be obtained, which will be the same for all "normal blades" without exception. Whatever may be the type of boat to which they belong, or the speed, number of revolutions, etc., the screws will differ only in size and in number of blades. These abstract numbers can be grouped in a single table in such a manner that it will only be necessary to take as unity any given advance per revolution, when it will be possible to determine at once all the dimensions of the "normal blade" suitable for this rate of advance. The author recommends that experiments should be made with a large number of "normal screws" varying slightly from each other, in order to ascertain with certainty the proportions suitable for obtaining the best results.

A table is given showing the proportions of the "normal blade." As this is designed to have a constant angle of incidence equal to  $2^\circ 52'$ , it follows that the pitch is different at different radii, being less in the center of the blade than at the root and at the extremity. The number of blades to be employed is a function of the midship section, the advance per revolution and the hull efficiency.

The proposed method of designing screws will much simplify the drawing process, since one screw will differ from another only in scale. In small vessels where twin screws cannot be used, the engine requires to run faster than would be possible with one normal screw, the author recommends multiple screws placed one behind the other on the shaft.

A British admiralty chart, Midland section of Georgian bay, will be sent, postpaid, to any address for \$1.25; regular price \$1.75. Size of sheet 3x4 ft. The Marine Review Pub. Co., Perry-Payne building, Cleveland. Chart of the whole bay on one sheet at the same price.

"The Construction of a Gasoline Motor Vehicle" is the title of an interesting and useful book which has just been issued by Emil Grossman & Bro. of New York. It is the story of a gasoline motor vehicle from the time of conception up to the hour of completion and is illustrated with working drawings.

# BELLEVILLE GENERATORS

Grand Prix 1889

Originated 1849

Hors Concours 1900

Latest Improvements 1896

Number of Nautical Miles made each year by Steamships of the Messageries Maritimes Co., Provided with Belleville Generators—Since their Adoption in the Service.

Year.	Australien	Polynésien	Armand Béhic	Ville de la Ciotat	Ernest Simons	Chili	Cordillère	Laos	Indus	Tonkin	Annam	Atlantique
1890.....	67,728	2,460										
1891.....	68,247	68,331	204									
1892.....	68,247	68,403	69,822	23,259								
1893.....	68,379	68,343	68,286	68,247								
1894.....	68,439	68,367	68,574	68,439	37,701							
1895.....	68,673	68,766	68,739	68,808	40,887	28,713						
1896.....	69,534	92,718	69,696	69,549	62,205	63,153	40,716					
1897.....	68,250	69,606	92,736	69,555	62,235	76,110	63,357	43,146				
1898.....	70,938	69,534	69,552	69,597	62,526	63,240	63,240	62,553	63,954	22,707		
1899.....	69,534	69,615	67,431	90,405	60,246	62,778	62,868	52,344	54,855	44,007	22,884	
1900.....	69,534	67,494	69,744	69,564	61,719	62,382	62,502	51,471	53,373	62,016	63,066	52,140
Total.....	757,503	713,637	644,784	597,423	387,519	356,376	292,683	209,514	172,182	128,730	85,950	52,140

ATELIERS ET CHANTIERS DE L'ERMITAGE, À ST. DENIS (SEINE), FRANCE.

WORKS AND YARDS OF L'ERMITAGE AT ST. DENIS (SEINE), FRANCE.

TELEGRAPHIC ADDRESS: BELLEVILLE, SAINT-DENIS-SUR-SEINE.



## WITH THE COAST SHIP BUILDERS

Following is a description of the new steamer which the Pusey & Jones Co., Wilmington, Del., are building for the Bordentown & Philadelphia Transportation Co., for service between Philadelphia and Bordentown, N. J. Dimensions: length on deck, 135 ft.; length between perpendiculars, 127 ft.; beam molded, 24 ft.; beam over guards, 28 ft.; depth, 9 ft. The speed will be 15 statute miles per hour in still water. The draught of water will be 6 ft. aft, 3 ft. forward, without cargo; with tank forward of sufficient size to trim the boat for a mean draught of 4½ ft. There will be three water tight bulkheads, one forward and one aft and one forward of boiler, constructed of 9 lb. plates and stiffened by steel angle bars 2½ in. x 2½ in. x 5 lbs. All compartments are to be fitted with sounding tubes. There will also be two bulkheads of 5 lb. plates, one between engine and boiler and one aft of engine, stiffened with 2 in. x 2 in. x ¼ in. angles, and fitted with doors. The forward compartment of collision bulkhead is to be used for trimming vessel, and to be filled and emptied by pump in engine room. The new steamer will be fitted with one fore and aft compound engine, connected to crank shaft at right angles, and fitted with a Schutte condenser. The cylinders of the engine will be 14 in. and 26 in. in diameter by 22 in. stroke, both cylinders having slide valves operated by link motion and fitted with steam reversing gear. The propeller wheel will be 7 ft. in diameter, with four blades. The boiler will be of the Scotch type, 11 ft. diameter by 10 ft. 6 in. long, of steel, built for working pressure of 125 lbs. per sq. in. It will have two corrugated furnaces, each 44 in. in diameter.

It was announced in the Review last week that the Gulf Coast Ship Building & Dry Dock Co. had selected Alabamaport as the site for its ship yard. The company is chartered under the laws of Alabama and is organized with a capital, including stocks and bonds, of \$4,000,000. It is understood that the plant will be capable of turning out any class of ship from a torpedo boat to a battleship. One of the gentlemen interested in organizing the company said: "The place selected is the best adapted for the purposes of a ship yard of any port south of Newport News, having a natural harbor with a 20 ft. channel, which we intend to dredge out to 32 ft. We will also build a basin and docks for use in connection with the Mobile & Ohio, and possibly the Louisville & Nashville, in receiving and discharging cargoes. The port of Alabama is also desirable as a location for a ship building and marine railway plant because it is in proximity to the coal, iron and lumber industries of the state. All material necessary can be procured at less cost than in the north and labor is relatively cheap. The company is assured of a large business from the outset. We will take over the Johnson ship building and machine shops at New Orleans, with their dry dock of 2,000 tons capacity. This plant will be enlarged and a floating dry dock built capable of taking in a 10,000 ton ship."

Lane & DeGroot, Brooklyn, N. Y., have signed a contract with southern parties for a cabin launch, length 50 ft., beam 13 ft., depth 6 ft. 6 in., to be finished in mahogany. The International Gas Engine Co. of No. 26 Broadway, are to furnish a 25 H.P. motor for this launch, to be completed in sixty days.

The Nantasket Steamboat Co. has given a contract for a new passenger steamer to Montgomery & Howard, Chelsea, Mass. The new

steamer is to be 198 ft. over all, 190 ft. keel, 34 ft. beam and 11 ft. 5 in. deep. Engines will be furnished by the W. & A. Fletcher Co., Hoboken, N. J.

Capt. John G. Crowley, Taunton, Mass., will have another seven-masted schooner built, somewhat similar to the one under contract at the Fore River Ship & Engine Building Co.'s yards at Quincy, Mass., to be 365 ft. long, 50 ft. beam and 34 ft. deep, with a cargo capacity of 7,000 tons.

It is reported that Messrs. T. Hogan & Sons, New York, have contracted with Messrs. J. L. Thompson & Sons, Sunderland, for the construction of two large steamers, and with Messrs. C. S. Swan & Hunter, Newcastle, for the construction of one large steamer.

The Parkersburg Dock Co., Parkersburg, W. Va., is building a tow-boat of the following dimensions for Capt. John S. Summers: 100 ft. long, 22 ft. beam and 4 ft. deep. The vessel will be equipped with engines having 700 H.P. and will cost about \$20,000.

As soon as the big schooner William P. Frye is out of the way Arthur Sewall & Co., Bath, Me., will begin work on a five-masted steel schooner of about 3,000 tons capacity.

Bids will soon be invited for the erection of four buildings, a power house, foundry, machine shop and an office building, for the new naval plant at Algiers, La.

Washburn Bros., Thomaston, Me., have stretched the keel for a new five-masted schooner, the length of which is to be 225 ft.

A number of very complete outfits of driving machinery and boat equipment, accompanied by plans and specifications for building the hull and installing the machinery, have been sent out by the Marine Iron Works, station A, Chicago. Several similar contracts now under way. This is a plan that they have demonstrated to be an exceptionally good one, particularly for those located at a distance where they may have suitable material and good men to do the work, provided they secured the necessary information with plans and details, all of which the Marine Iron Works furnish with their complete machinery outfits when so contracted for.

3

## "Seaboard Steel Castings."

MANUFACTURERS OF  
"THE ADMIRAL" ANCHOR.

THE LATEST AND BEST  
STOCKLESS ANCHOR.  
APPROVED BY LLOYD'S.

ANCHORS CAST AND TESTED ON  
ORDER, OR STOCK ORDERS  
PROMPTLY FILLED.

## A GUARANTEE OF QUALITY.

OPEN-HEARTH STEEL CASTINGS  
OF THE HIGHEST GRADE.  
FACILITIES FOR CASTINGS UP TO  
80 000 POUNDS WEIGHT.

MACHINE WORK AND PATTERNS  
FURNISHED WHEN REQUIRED.

RAIL OR WATER DELIVERIES.

CAPACITY, 1500 TONS PER MONTH

**Seaboard Steel Casting Co.,**  
CHESTER, PA.

## BURNISHINE.

THE MOST MARVELOUS METAL  
POLISH IN THE WORLD.



In Liquid and  
Paste Form.

Will Polish

Hot or Cold

Metal,

no matter which.

Produces a wonderfully brilliant  
lustre on brass, copper, nickel and  
all metals, no labor required.

Used on steamers all over the world.  
Free samples on application.

**J. C. PAUL & CO.**  
57 Dearborn St., CHICAGO, ILL.

It is up to you  
Mr. Engineer.

We have shown you time and again in  
the advertising pages of the leading en-  
gineering journals that we are the manu-  
facturers of

## High Grade Packings

for every purpose. They are reliable, dur-  
able, economical and guaranteed. All we  
ask is an opportunity to convince you of

## THESE SOLID FACTS.

Will you give us that opportunity?

Send for catalogue and samples to our nearest office.


## THE GARLOCK PACKING CO.



None GENUINE WITHOUT IT.  
New York. Philadelphia. St. Louis.  
Boston. Pittsburgh. Denver.  
Chicago. Cleveland. San Francisco.

MAIN OFFICES AND FACTORIES:  
PALMYRA, N. Y.; ROME, GA.

This illustration represents our



## PLATE PLANER

having capacity to plane the edges  
of plates any size or thickness.

The cutter head carries two tools, one cutting in each direction.  
Shifting of tools is automatic. Cutter head is driven by a large square  
thread screw, working in a bronze nut.

Girder is raised and lowered by power. Jack screws for holding  
plate furnished if required. Let us refer you to the users of these ma-  
chines for an expression as to their capacity for turning out work.

**THE CLEVELAND PUNCH AND SHEAR WORKS CO., CLEVELAND, O., U. S. A.**



*Here is a Book You Should Have.*

## Patterson's Illustrated Nautical Encyclopedia

**Y**OU have no book like it upon your shelves because there is no book like it in existence. It is the only work of its kind extant. It covers the whole field of naval architecture, marine engineering and navigation. It concentrates its whole energy upon the sea and its ships. Within its limited scope there is nothing lacking. To those who are interested in shipping, ship building and sailing it is the best dictionary ever written. Its definitions are clear and authentic, and there are 6,000 of them. Its illustrations are carefully drawn and engraved and there are 500 of them.

The book is bound in white duck and stamped with blue ink and is most fetching to the eye. Between its covers 500 pages are devoted to defining the meaning of words in nautical literature. If there is a word in that ought to be out, or a word out that ought to be in, we should know it. We don't think there is.

The book is of vital interest to nautical students, men of the merchant marine and navy, masters and engineers, admiralty lawyers and everyone concerned about the building and operation of a ship.

It is fresh from the press of the Marine Review and is for sale at \$3.00 per copy. Address

THE MARINE REVIEW PUBLISHING CO.,

PERRY-PAYNE BUILDING, CLEVELAND, OHIO.



## R. I. W. Damp Resisting Paint

WILL DAMP-PROOF YOUR FLOATING EQUIPMENT.  
A PROTECTOR AGAINST RUST AND DECAY.

**TOCH BROTHERS, Paint Makers,**

468, 470, 472 West Broadway, NEW YORK.

Established 1848.

WRITE FOR BOOKLET.

### If you want a MODERN ELECTRIC LIGHT PLANT—

Engines, Dynamos, Search Lights, Arc  
or Incandescent Lamps—for your boat,

ADDRESS

**BADT-GOLTZ ENGINEERING CO.,**  
1504 Monadnock Block, CHICAGO.

U. S. Engineer Office, Jones Building, Detroit, Mich., Aug. 8, 1901. Sealed proposals for dredging under continuing contracts, for improving Hay Lake Channel, St. Mary's River, Mich., will be received here until 12 noon (standard time), Aug. 31, 1901, and then publicly opened. Information furnished on application. G. J. Lydecker, Col., Engrs.  
Aug. 29.

### SECOND-HAND BEAM ENGINE.

WANTED—Second-hand engine of beam type and about 32 in. by 6 ft. Address box 400, the Marine Review Pub. Co., Cleveland, O. d

## BERTHS • BUNKS • BEDDING

Practical sanitary ideas in Metal Berths.

Made to fold up or drop down.

Made on hygienic principles that are already popular.

PERFECTION BERTHS are endorsed by the ARMY AND NAVY Authorities

and by leading Ship Builders. Full line Patent Metal Berths. Hardwood front Berths, any finish. Standee Berths, Extension Berths for cabin use. Forecastle and Steerage Berths of most approved styles. Portable Cabins. Can be removed without use of tools. All vermin-proof. Let us quote you prices on your wants in Berth and Bedding.

MADE ONLY BY

**LEIN, IRVINE & COMPANY,** 328 to 332 E. Twenty-third Street,  
NEW YORK CITY.

### Interest in Steam Barge For Sale.

Half interest in steambarge of 776 tons, A2 class and capable of carrying 950 tons of coal or 650 M ft. lumber. Compound engine and good boiler, the latter allowed 120 lbs. steam pressure. Address or apply to J. E. M., 23 Lodge avenue, Cleveland, O. d

### FOR SALE.

**BALANCED COMPOUND MARINE ENGINES** carried in stock for immediate delivery—20 to 200 horse power. Full line of patterns for larger sizes and quadruple expansion engines, insuring quick delivery. Highest economy and speed.

**NO VIBRATION.** Contracts taken for complete plants.

d **WELLS ENGINEERING CO., 136 Liberty St., NEW YORK, N. Y.**

### TUG FOR SALE.

Wood hull 61 ft. long, 14 ft. 8 in. beam. Iron house. Engine 16¼ by 18 in. Boiler pressure allowed, 140 lbs. Price \$2600. Inquire C. H. Strong & Son, No. 622 Cuyahoga building, Cleveland, O. d

# STANDARD SEAMLESS TUBE CO.

MANUFACTURERS OF

## Seamless Cold Drawn Steel Tubing

IN ALL SIZES FROM ⅛ TO 16" DIAMETER.

Stay Tubes,  
Water Grates,  
Compressed Air and  
High Steam Pressures.

## Boiler Tubes

FOR ALL CLASSES  
OF MARINE WORK.

Hollow Shafts,  
Bushings,  
Hydraulic Tubes,  
Etc., Etc.

# NATIONAL TUBE COMPANY,

SELLING AGENTS,

#### SALES OFFICES:

Havemeyer Building, New York.  
Conestoga Building, Pittsburg.  
Western Union Building, Chicago.

95 Milk St., Boston.  
267 So. Fourth St., Philadelphia.  
420 California St., San Francisco.

#### FOREIGN OFFICE:

Dock House, Billiter Street,  
London, E. C., Eng.



## Dearborn Vegetable Boiler Compounds.

SCIENTIFICALLY AND UNIFORMLY MADE. EVER RELIABLE.

Most Scientifically equipped, Complete, Handsome and expensively Furnished Laboratories, and the ONLY EXCLUSIVE LABORATORIES ON STEAM ECONOMY in the Country.

## MARINE FORMULA NO. 5, For the WATERS of the FIVE LAKES.

To prevent pitting, neutralize the oil, stop incrustation, and as a perfect preservative to the iron, boiler, and all its connections—especially prepared for the marine trade of the lakes.

If you are using a different water, prepay the express on a gallon jug of your feed water to the DEARBORN LABORATORIES at CHICAGO and receive a copy of analysis of same, with a written diagnosis of your case, and a letter giving you all the valuable information we can, and the actual cost of what it will require to clean your boilers and keep them clean. All of this will be done free of charge, and optional with you whether you order or not. When in Chicago call and inspect our Laboratories.

**Analyzers of Everything.**

**Makers of Boiler Compounds.**

**DEARBORN DRUG & CHEMICAL WORKS**


CHICAGO

W. M. H. EDGAR, President.

Manufacturing and Analytical Chemists.

OFFICES: 29, 30, 31, 32 and 33 Rialto Building. Telephone, Harrison, 1373.

WORKS: 23, 25, 27 and 29 La Salle Street. Telephone No. 1130 South.




## Liquid (Spirit) Compasses

of our make, in seven sizes, embody every known point of excellence possessed by those of other makers, and in addition have been improved in many important details.

We therefore positively assert that, in general construction and thoroughly scientific action of the card, we offer the best Liquid Compass ever made in this or any country. For sale by Ship Chandlers generally.

**John Bliss & Co., 128 Front Street, New York.**



**DREDGING, WRECKING,  
CIRCULATING  
AND BALLAST PUMPS.**

**Marine Boilers.**

**KINGSFORD FOUNDRY  
AND MACHINE WORKS,  
OSWEGO, N. Y.**

ALL MATERIAL MANUFACTURED  
FROM  
OUR OWN IRON

WE HAVE OUR OWN  
GALVANIZING PLANT

**NEW HALL CHAIN FORGE AND IRON CO.**  
OFFICES, HAVEMEYER BUILDING  
26 CORNHILL NEW YORK


"WARWICK" SHIP DRIVING IRON,  
SPECIAL HEAD MACHINE AND  
HAND MADE SHIP SPIKES, CLINCH  
RINGS, SCREW BOLTS, RODS,  
TURNBUCKLES, PLAIN AND  
BABBITTED CHOCKS AND CLEATS.

DAVITS, SHACKLES, SWIVELS  
AND OTHER FORGINGS. CLOSE  
LINK AND STUD LINK YACHT  
AND SHIP CABLES, ANCHORS,  
BLOCKS, BUNKER PLATES,  
CAPSTANS, WINDLASSES & PUMPS.

## KEEP YOUR BOILERS CLEAN BY USING Clean Water

The "BUFFALO" is Warranted to Remove all Sediment and Scale Forming Substance.

**THE BUFFALO  
FEED WATER  
HEATER  
AND PURIFIER.**



Anyone Can Operate It.

IT ADDS YEARS TO THE  
LIFE OF THE BOILER.

Used on principal steamers of Anchor Line, Lake Michigan & Lake Superior Transportation Co., American Steel & Wire Co., Bessemer Steamship Co., and others, aggregating 55,560 I. H. P.


Ask For Catalogue.

**ROBERT LEARMONTH, Patentee,**

100 WHITE BUILDING.

**BUFFALO, N. Y.**

## Ritchie Liquid Compass



THE STANDARD LIQUID COMPASS.  
USED EXCLUSIVELY BY THE UNITED  
STATES NAVY FOR OVER  
35 YEARS.

OVER 25,000 USED IN MERCHANT  
SERVICE.

Made in all sizes and styles, from 2 to 12 inches diameter of card. All compasses made by us have our name printed below the North point, or prominently upon the card. **NONE OTHER ARE GENUINE.** Latest form with four or six needles, the best instrument for iron ships. For sale by ship chandlers and nautical instrument dealers.

CATALOGUE FREE.

**E. S. RITCHIE & SONS,**

Manufacturers of Nautical and Physical Apparatus,

**BROOKLINE MASS. U. S. A.**



Absolute extinction of fires in holds or bunkers of ships  
no matter what the cargo.

Machine installed weighs 3800 lbs.

THE CLAYTON FIRE EXTINGUISHING AND DISINFECTING COMPANY,  
11 BROADWAY, NEW YORK.



## Pan-American Route

between CLEVELAND and BUFFALO.

STEAMERS CITY OF BUFFALO AND CITY OF ERIE.

Finest and fastest passenger steamers in the United States.

TIME CARD—DAILY—APRIL 15 TO DEC. 1.

Leave Cleveland 8 p. m. Arrive Buffalo 6.30 a. m.

Leave Buffalo 8 p. m. Arrive Cleveland 6.30 a. m.

ADDITIONAL SERVICE DURING JULY AND AUGUST.

Connections made at Buffalo with trains for all Eastern and Canadian points; at Cleveland for Detroit and all points West and Southwest.

SPECIAL LOW RATES CLEVELAND TO BUFFALO AND NIAGARA FALLS EVERY SATURDAY NIGHT, ALSO BUFFALO TO CLEVELAND.

W. F. HERMAN, General Passenger Agent, Cleveland, O.


## GEORGE STRATFORD OAKUM CO.,

MANUFACTURERS OF

Oakum, Plumbers' Spun and Marine Oakum and Spun Cotton.

OFFICE AND FACTORY:

CORNELISON AVENUE, JERSEY CITY, N. J.



ONE OF THESE BINDERS

that will hold 52  
NUMBERS  
of the

MARINE REVIEW,

Will be mailed to  
any address on  
receipt of \$1.

MARINE REVIEW...

Perry-Payne Bldg.,  
CLEVELAND, O.

# Pintsch Gas Lighted Buoys

Adopted by the English, German, French, Russian, Italian, and United States Light House Departments, for Channel and Harbor Lighting; over 1000 gas buoys and gas beacons in service.

## Burn Continuously


from 80 to 365 days and nights without attention,  
and can be seen a distance of six miles.

Brilliant and Steady Illumination.

Economical and Reliable in Operation.

Controlled by the SAFETY CAR HEATING AND LIGHTING CO.,

160 Broadway, New York City.



## MARINE ENGINES.

Quadruple and  
triple expansion,  
compound and  
simple.

15 to 3000 Horse  
Power.

"SEABURY'S" WATER TUBE BOILERS.  
STEAM AND SAIL YACHTS.  
THE ONLY NAPHTHA LAUNCH.

GAS ENGINE & POWER CO., AND  
CHARLES L. SEABURY & CO. Consolidated.

MORRIS HEIGHTS, NEW YORK CITY.

SEND 10c. STAMP FOR CATALOGUE.


## FOGG'S RESILIENT FELT MATTRESSES AND CUSHIONS

MANUFACTURED BY

M. W. FOGG,

20 Fulton St., NEW YORK.

Send for Illustrated Catalogue.



Perspective view of the 250 H. P. boiler built for steamboat Clara, having 6 feet face and 8 feet length; 37 1/2 square feet of grate area and 1900 square feet heating surface. Weight of boiler and water, 14,000 lbs.

WE CLAIM for the Boyer Sectional Water Tube Boilers, that they are of an entirely new design, are simplest in construction, are accessible to all parts, are rapid steamers with short circulation, have low center of gravity, have no joints in the fire, have no dead ends, occupy less space in width, length and height than any other, are easily fired, can be repaired or set up by any ordinary mechanic, do not require a brick casing, and are shipped whole or knocked down into packages for transportation by man or beast.

The Boyer Water Tube Boiler Co.,

90 Wall Street, NEW YORK.

MENTION THIS PAPER.)



## OHIO FUEL COMPANY.

WE FURNISH ONLY THE BEST GRADE OF  
PITTSBURGH **STEAM COAL.**  
and GOSHEN  
LIGHTER OF 300 TONS CAPACITY.

Dock Phone, Bell West 841.  
Office Phones: { Bell Main 526.  
                  { Cuyahoga C 240.

219 The Cuyahoga Building,  
CLEVELAND, O.

### Steamboat Fuel at Ashtabula. LARGE SUPPLIES OF BEST QUALITY

#### Lighter

Carrying  
Different  
Grades  
at all  
Times.



Fuel scow with elevators  
and discharging spouts.  
Storage of 650 tons. Dis-  
charges 150 tons an hour  
into steamers while un-  
loading cargo.

M. A. HANNA & CO., Miners and Shippers.  
Main Office, Perry-Payne Bldg., Cleveland

## THE Swain Wrecking Co.

The TUG FAVORITE  
STATIONED AT CHEBOYGAN, MICH.  
WITH COMPLETE WRECKING OUTFIT,  
IN CHARGE OF  
Capt. MARTIN SWAIN.

THE  
CANADIAN WRECKER SAGINAW  
STATIONED AT DETROIT, MICH.  
ENABLES US TO WRECK IN CANADIAN  
WATERS.

STEAM PUMPS AND SUB-MARINE  
WORK IN CHARGE OF  
JOHN S. QUINN.  
Address: 211 Commercial St.

A. A. & B. W. PARKER.  
Office: 15 WATER ST. WEST  
DETROIT, MICH.

STATIONED THE  
FAVORITE  
Capt. M. Swain  
Superior to all other wrecking  
tugs on the lakes.

4 STEAM PUMPS, 10 JACKS, 3 HAWERS.

1 COAL AND ORE PUMP  
3-12 INCH ROTARY.  
1-14 INCH WORTHINGTON.

DIVING RIGS  
AND  
DIVERS  
ABOARD  
AT  
ALL TIMES.

AUGUST.						
S	M	T	W	T	F	S
...	...	...	...	1	2	3
4	5	6	7	8	9	10
11	12	13	14	15	16	17
18	19	20	21	22	23	24
25	26	27	28	29	30	31

10-100 TON JACKS.  
1-12 INCH HAWSER  
1-10  
1-9

Telegraph  
Capt. M. SWAIN  
CHEBOYGAN, MICH.

A. A. & B. W. PARKER, SUCCESSORS TO  
DETROIT, MICH. PARKER & MILLEN,

## Pickands, Mather & Co.,



Western Reserve Building, CLEVELAND, O.

### FUEL LIGHTERS

AT BUFFALO,  
ERIE,  
ASHTABULA  
AND CLEVELAND.

AT DETROIT, MICH., A FUEL DOCK equipped  
with Shute capacity of 600 Tons.  
Best Quality PITTSBURGH COAL furnished at  
any time during Day or Night.

## To Admiralty Lawyers.

TO ALL LAWYERS, IN FACT, AND ALL  
OWNERS OF REFERENCE LIBRARIES.

We are offering a nautical encyclopedia, carefully revised, and up to date in all respects. Deals with 5,000 subjects and contains 500 descriptive engravings. Explains every term in the great mass of sea literature. It should interest every member of the naval, revenue, coast survey, transport and light-house services, for it is an invaluable reference work for them. It goes thoroughly into every feature of these services. It should interest also members of the merchant marine, yachtsmen, builders of steam and sailing vessels and underwriters.

Edited by HOWARD PATTERSON,  
Author of several similar works.

### JUST FROM THE PRESS.

Price only \$3.

THE MARINE REVIEW PUB. CO.,  
CLEVELAND, O.

## MODERN SEAMANSHIP.

By AUSTIN M. KNIGHT, Lieutenant-Commander, United States Navy.

### CONTENTS.

- Chapter I. The Hull and Fittings of a Ship.
- Chapter II. Rope—Knotting and Splicing.
- Chapter III. Spars and Standing Rigging.
- Chapter IV. Sails and Running Gear.
- Chapter V. Mechanical Appliances on Shipboard.
- Chapter VI. Blocks and Tackles.
- Chapter VII. Handling Heavy Weights.
- Chapter VIII. The Compass, Log, and Lead.
- Chapter IX. Boats.
- Chapter X. Handling Boats in a Surf.
- Chapter XI. Ground Tackle.
- Chapter XII. Carrying Out Anchors.
- Chapter XIII. The Steering of Steamers.
- Chapter XIV. The Rules of the Road.
- Chapter XV. Maneuvering to Avoid Collision.
- Chapter XVI. Piloting.
- Chapter XVII. Handling a Steamer Alongside a Dock.
- Chapter XVIII. Placing a Ship in Dry Dock.
- Chapter XIX. Weather, and the Laws of Storms.
- Chapter XX. Handling Steamers in Heavy Weather.
- Chapter XXI. Towing.
- Chapter XXII. Rescuing the Crew of a Wreck.
- Chapter XXIII. Man Overboard.
- Chapter XXIV. Stranding.
- Chapter XXV. Making and Taking in Sail.
- Chapter XXVI. Maneuvering Under Sail.
- Chapter XXVII. Getting Underway and Coming to Anchor Under Sail.

PRICE \$6.

THE MARINE REVIEW PUB. CO., CLEVELAND, O.

## The Erie & Western Transportation Co. ANCHOR LINE. 1901.

### Passenger Service—

Steamers.....India, China, Japan.  
Ports of call... Buffalo, Sault Ste. Marie, Hancock, Marquette, Cleveland,  
Detroit, Mackinac Island, Port Huron, Duluth, Houghton,  
Erie.

### Freight Service—

Steamers.....Alaska, Delaware, Codorus, Mahoning, Susquehanna,  
Schuykill, Lycoming, Conestoga, Clarion, Wissahickon,  
Conemaugh, Juniata, Lehigh.  
Ports of call... Buffalo, Erie, W. Superior, Cleveland, Marquette,  
Detroit, Houghton, Sault Ste. Marie, Hancock, Duluth,  
Houghton, Chicago, Milwaukee.

CHAS. E. MARKHAN, Gen. Pass. Agt., E. T. EVANS, Western Manager,  
Buffalo, N. Y. Buffalo, N. Y.

## THE DONNELLY SALVAGE AND WRECKING CO., Ltd

JOHN DONNELLY, Sr., Pres.  
JOHN DONNELLY, Jr., Vice-Pres.  
H. B. FOLGER, Treas.  
THOS. DONNELLY, Secy.

KINGSTON ONT.

Divers, Steam Pumps, Tugs, Etc  
SUPPLIED ON SHORTEST NOTICE.

## The W. L. SCOTT COMPANY, ERIE, PA.

WHOLESALE DEALER IN

SHAMOKIN  
ANTHRACITE  
WILKESBARRE

# COALS

YOUGHIOGHENY  
PITTSBURGH  
MANSFIELD

VESSEL FUELING A SPECIALTY By STEAM LIGHTER or Car Dump  
at all hours. Electric Light.

Main Office, Scott Block, Long Distance Telephone No. 440.  
Fueling Office, Canal Dock, Long Distance Telephone No. 320.



# CASTNER, CURRAN & BULLITT, SOLE AGENTS FOR POCAHONTAS SMOKELESS SEMI-BITUMINOUS COAL

THE BEST STEAM COAL IN THE WORLD.

Officially endorsed by Great Britain and United States. Standard Fuel of United States Navy.  
Used exclusively on Cunard, White Star and other Transatlantic Lines.

Main Office, 328 Chestnut Street - - PHILADELPHIA PA.

BRANCH OFFICES:

1 Broadway, New York.

Citizens Bank Building, Norfolk, Va.

Calle Reconquista 399, Buenos Ayres, Argentine Republic, South America.

Old Colony Building, Chicago, Ills.

70 Kilby Street, Boston, Mass.

Terry Building, Roanoke, Virginia.

Neave Building, Cincinnati, Ohio.

4 Fenchurch Avenue, London, England.

## PITTSBURG COAL CO.

Steamboat Fueling Facilities at various points on the Great Lakes:

Cleveland Harbor { 4 Car Dumpers. 3 Lighters.	Fairport Harbor { 1 Car Dumper. 1 Lighter.	Ashtabula Harbor { 1 Car Dumper. 1 Lighter.	Erie Harbor { 1 Car Dumper. Fuel Pockets.
Detroit River Branch { Docks and Pockets at Sandwich and Amherstburg.		Sault River Branches { Dock and Pockets at Detour. Dock and Pockets at Sault Ste. Marie. (The Port Royal Dock Co.)	

WE FURNISH ONLY THE BEST GRADE OF **PITTSBURG and YOUGHIOGHENY COAL.**

General Office, Lake Department, Perry-Payne Building, Cleveland, O.

STEAMBOAT FUEL AT CHICAGO.



**Youghioghenny and  
Lehigh Coal Co.**

J. T. CONNERY, Manager. ARCHIE J. HITCHCOCK, Dock Sup't.

**FUEL DOCKS:** { No. 1, Michigan Slip & Basin. 'Phone Main 1650.  
No. 2, N. Halsted St. Bridge. 'Phone Main 1649.  
No. 3, Foot South Water St. and Illinois Central  
Slip C. 'Phone Main 1679.

**FUEL LIGHTER:** Equipped with 125 2-ton Buckets for Fueling Anywhere in Harbor.

MAIN OFFICE: 1238-1242 Chicago Stock Exchange Building.

Long Distance Telephone, Main 1650.

110 LA SALLE STREET.

**The Rochester & Pittsburgh Coal & Iron Co.  
REYNOLDSVILLE COAL.**

STEAMBOAT FUEL DOCK—Blackwell Canal at Michigan St. Bridge. 1400 feet of dock frontage. Hulett Car Dumping Machine. Steam Fuel Scow of 550 tons capacity. Boats coaled day or night.

OFFICE: 684-88 Ellicott Square, BUFFALO, N. Y.  
TELEPHONE, Seneca 1154.

E. McQ. DUTHIE,  
Cargo and Fuel Agent.



## STANLEY B. SMITH & CO.

DETROIT, MICH.

SHIPPERS  
OF

# COAL

BY  
RAIL AND LAKE

OPERATING

**SMITH'S COAL DOCK, Detroit River.**

**A COMPLETE SET OF CHARTS OF THE GREAT LAKES**

ELEVEN IN ALL

SENT TO ANY ADDRESS, CARRIAGE PREPAID, FOR

===== \$5.45. =====

LAKE SUPERIOR.	DETROIT RIVER.
LAKE MICHIGAN.	ST. CLAIR RIVER.
LAKE HURON.	LAKE ST. CLAIR.
LAKE ERIE.	STRAITS OF MACKINAC.
ST. MARY'S RIVER IN THREE PARTS.	

THE MARINE REVIEW PUB. CO., 418-419 Perry-Payne Building, CLEVELAND, O.



## VESSEL AND INSURANCE AGENTS.

**C. W. ELPHICKE & CO.**

Vessel and Insurance Agents,  
Room 10, No. 6 Sherman St.,  
C. W. ELPHICKE, CALVIN CARR,  
H. B. EARHART, R. J. DUNHAM. **CHICAGO, ILL.**  
Long Distance Telephone, Harrison 1194.

**MITCHELL & CO.**

JOHN MITCHELL,  
JOHN F. WEDOW,  
ALFRED MITCHELL.  
Vessel and Insurance Agents,  
508, 509 & 510 Perry-Payne Bldg.,  
Office Telephone M 767. **CLEVELAND, O.**  
Residence, John Mitchell, Doan 341.  
John F. Wedow, Doan 141 J. Alfred Mitchell, Doan 218.

**F. H. OSBORN & CO.**

Marine Insurance Brokers,  
12 Sherman Street,  
Long Distance Telephone, **CHICAGO.**  
Harrison 1586.

**D. T. HELM & CO.**

Vessel Agents,  
TRANSPORTATION. Board of Trade,  
MARINE INSURANCE. **DULUTH, MINN.**

**W. C. RICHARDSON,**

Vessel and Marine Insurance Agent,  
420-421 Perry-Payne Building,  
Office Telephone 338. **CLEVELAND, O.**  
Residence Telephone 2938.

**D. SULLIVAN & CO.**

D. SULLIVAN,  
F. J. SULLIVAN.  
VESSEL AGENTS.  
MARINE INSURANCE.  
2 & 4 Sherman Street, **CHICAGO, ILL.**  
Tel. Harrison 2847.

**J. G. KEITH & CO.**

Vessel and Insurance Agents,  
138-139 Rialto Building,  
Long Distance Telephone, Harrison, 1339. **CHICAGO.**

**S. R. CHAMBERLAIN & CO.**

Vessel and Insurance Agents,  
No. 6 Sherman Street, **CHICAGO.**

**HALL & ROOT,**

JOHN B. HALL,  
HARRY B. ROOT.  
Vessel Agents,  
21-22 Exchange Building, 202 Main St.,  
Telephone Seneca 892. **BUFFALO, N. Y.**

**DRAKE & MAYTHAM,**

Vessel Agents,  
M. M. DRAKE, 202 Main Street,  
G. W. MAYTHAM.  
Telephone Seneca 1660. **BUFFALO, N. Y.**

**HUTCHINSON & CO.**

Vessel and Insurance Agents,  
Office Telephone, Main 2453.  
Residence C. L. Hutchinson, W. 697L.  
Residence W. H. McGean, E. 198J.  
313-315 Perry-Payne Bldg.,  
J. L. HUTCHINSON, W. H. M'GEAN, **CLEVELAND, O.**

**JOHN J. BOLAND,**

Vessel and Insurance Agent,  
25-26 Exchange Bldg., 202 Main St.,  
Telephone Seneca 115. **BUFFALO, N. Y.**

**WILSON TRANSIT CO.**

General Forwarders,  
Perry-Payne Bldg. **CLEVELAND, O.**

## VESSEL AND INSURANCE AGENTS.

**SAMUEL HOLMES,**

Steamship Offices, Morris Building,  
For Selling, Chartering and Building  
all classes Steam Vessels. 66-68 Broad St.,  
Steam Vessel Circulars. **NEW YORK.**  
Weekly Freight Circulars.

**BROWN & CO.**

J. J. H. BROWN,  
J. B. RODGERS,  
EDWARD SMITH.  
Vessel and Insurance Agents,  
202 Main Street,  
**BUFFALO, N. Y.**

## PROCTORS IN ADMIRALTY.

**RAY G. MACDONALD,**

Attorney at Law and Proctor in Admiralty,  
Suite 618 New York Life Building,  
Telephone Central 723. **CHICAGO, ILL.**

**STOWE & GRAYDON,**

Lawyers and Proctors in Admiralty,  
WILLIAM E. STOWE, 204 Dearborn Street,  
THOMAS J. GRAYDON. **CHICAGO.**  
Suite 806 Marquette Building.  
Telephone Central 1225.

**HOYT, DUSTIN & KELLEY,**

Lawyers and Proctors in Admiralty,  
Offices, 702 Western Reserve Building,  
**CLEVELAND, O.**

**White, Johnson, McCaslin & Cannon,**

ATTORNEYS AT LAW and  
PROCTORS IN ADMIRALTY,  
Williamson Building, **CLEVELAND, O.**

**GOULDER, HOLDING & MASTEN,**

LAW OFFICES,  
HARVEY D. GOULDER, J. H. HOLDING,  
FRANK S. MASTEN. Perry-Payne Building,  
**CLEVELAND, O.**

**ALBERT J. GILCHRIST,**

PROCTOR IN ADMIRALTY,  
604 Perry-Payne Building,  
**CLEVELAND, O.**

**ORESTES C. PINNEY,**

Lawyer and Proctor in Admiralty,  
Rooms 316 and 317 Perry-Payne Building,  
Telephone Main 2585. **CLEVELAND, O.**

**Compass Adjuster**

CAPT. J. M. FIELDS.  
Inventor of Fields' Course Finder,  
BETHEL HOTEL **CLEVELAND O.**

**"Elements of Navigation"** (Henderson)

Just the book for beginners—  
mates, wheelmen and watchmen.  
Recommended because it is  
short, simple and yet compre-  
hensive.

Price \$1.

THE MARINE REVIEW PUB. CO. CLEVELAND

## PROFESSIONAL.

**W. J. WOOD,** Naval Architect,  
Ship Surveyor.  
Consulting Engineer.

Prepares designs or working drawings and specifica-  
tions for all classes of vessels and superintends con-  
struction and repairs. Surveys damaged property and  
estimates cost of repairs.

Vessels designed—Twin S. S. Virginia, Steam Yacht  
Comanche, Twin S. S. North West and North Land,  
I. W. Nicholas, and many others, including Fire  
Boats, Tugs, Barges, etc.

COMPLETE PLANS FURNISHED FOR  
STEEL COMPOSITE OR WOODEN VESSELS  
Office on Goodrich Dock,  
foot of Michigan Avenue, **CHICAGO, ILL.**

**FRANK N. TANDY,**  
GENERAL MARINE AGENT,  
31 State Street, BOSTON, MASS.

SPECIAL ATTENTION GIVEN TO MARINE INVESTMENTS  
AND TO THE PROMOTING OF SHIP BUILDING.  
CORRESPONDENCE SOLICITED.

**Pittsburgh Testing Laboratory, Ltd.,**

INSPECTING AND METALLURGICAL  
ENGINEERS AND CHEMISTS,

1750 Monadnock, 325 Water Street,  
CHICAGO. PITTSBURGH.

906-7 Crozier Building, Philadelphia.  
New York City, 60 New Street.  
Richmond, Va., 1107½ Main Street.

Inspectors of Shipbuilding Materials and Machinery.  
Inspectors located at all mills, Physical and Chemical  
Laboratories. Tests of all kinds.

**ROBERT W. HUNT & CO.**

Bureau of Inspection, Tests and Consultation.  
1121 The Rookery, Chicago.  
Monong. Bank Bldg., Pittsburgh.  
71 Broadway, New York.  
Inspectors of Shipbuilding Material and Machinery. In-  
spectors of all Materials. Duty Tests of Engines  
and Boilers. Physical and Chemical Laboratories.

**HORACE SEE,**

CONSULTING ENGINEER  
AND NAVAL ARCHITECT,  
No. 1 Broadway, **NEW YORK**

**EDWARD GASKIN,**

Ship Building Expert.  
Plans and specifications for ships, surveys and  
estimates, superintendence, etc.  
ELLCOTT SQUARE, **BUFFALO, N. Y.**

**AMBROSE V. POWELL, M. Am. Soc. G. E.**

CIVIL ENGINEER,  
Designs and Constructs Dry Docks,  
Harbor Works, Docks and Plant for  
Handling Coal and Ore, Foundations.  
Office, 1008 Chamber of Commerce, **CHICAGO, ILL.**

## PATENTS.

**THURSTON & BATES,**

Counselors at Law in Patent Causes  
and Solicitors of Patents,  
1028 Society for Savings Bldg.,  
E. L. THURSTON, ALBERT H. BATES. **CLEVELAND, O.**

**HERBERT WRIGHT & CO.,**

1011-1015  
THE WILLIAMSON BUILDING,  
**CLEVELAND, O.**

TELEPHONE, MAIN 2754.

Every possible facility for conducting a  
brokerage business in

**STOCKS, BONDS, GRAIN, ETC.**



## Books on Naval Architecture, SHIP YARD PRACTICE, SEAMANSHIP, Etc.

AMERICAN PRACTICAL NAVIGATOR—Nathaniel Bowditch. \$2.25.  
 AZIMUTH TABLES for the Great Lakes—Hydrographic Office. 50 cents.  
 BOILER MAKERS AND IRON SHIP BUILDERS' COMPANION. Comprising a series of original and carefully calculated tables. James Foden. \$2.  
 BOWDITCH'S USEFUL TABLES. \$1.25.  
 DATA BOOK—Naval architects and engineer's data book. By T. H. Watson. A reliable and simple means of recording valuable data, etc., of vessels and engines. Size of book, 8 $\frac{3}{4}$  in. by 5 in., cloth. \$2.  
 ELEMENTARY NAVAL TACTICS—Com. Wm. Bainbridge-Hoff, U. S. N. \$2.  
 ELEMENTARY SEAMANSHIP—D. Wilson Barker. \$2.  
 ELEMENTS OF NAVIGATION—Henderson. \$1.  
 GEORGIAN BAY AND NORTH CHANNEL PILOT—Department of Marine and Fisheries, Canada.  
 GEORGIAN BAY AND NORTH CHANNEL SAILING DIRECTIONS—Hydrographic Office. 40 cents.  
 HINTS ON LEGAL DUTIES OF SHIPMASTERS—B. W. Ginsburg. \$1.75.  
 ILLUSTRATED NAUTICAL ENCYCLOPEDIA—Howard Patterson. In press. \$3.  
 ILLUSTRATIVE CLOUD FORMS FOR THE GUIDANCE OF OBSERVERS IN THE CLASSIFICATION OF CLOUDS—Hydrographic Office. \$1.00.  
 INTERNATIONAL SIGNAL CODE—Bureau of Navigation. \$2.50.  
 KNOW YOUR OWN SHIP—Thos. Walton. \$2.50.  
 LAKE MICHIGAN, GREEN BAY AND STRAITS OF MACKINAW SAILING DIRECTIONS—Hydrographic Office. 40 cents.  
 LAKE SUPERIOR AND ST. MARY'S RIVER SAILING DIRECTIONS—Hydrographic Office. 40 cents.  
 LATITUDE AND LONGITUDE: How to Find Them—W. J. Millar. \$1.  
 MANUAL OF ALGEBRA—R. C. Buck. For the use, more especially, of young sailors and officers in the merchant navy; numerous examples and exercises. \$1.50.  
 MARINER'S COMPASS IN AN IRON SHIP: How to keep it efficient and use it intelligently. J. W. Dixon. \$1.  
 MODEL ENGINES AND SMALL BOATS—N. M. Hopkins. New methods of engine and boiler making; ship design and construction; fifty illustrations. \$1.25.  
 MODERN SEAMANSHIP—Lieut. Com. Austin M. Knight, U. S. N. Adopted as the text book of the United States Naval Academy. \$6.

MODERN PRACTICE OF SHIP BUILDING IN IRON AND STEEL. Samuel J. P. Thearle. 2 volumes. Second edition, revised and enlarged. \$5.25.  
 NAVAL ARCHITECTURE: A treatise on laying off and building wood, iron and composite ships. Samuel J. P. Thearle. In two volumes. \$3.  
 NAVAL ARCHITECTURE: A manual on laying off iron and steel vessels—Thos. H. Watson. Valuable for naval architects as well as beginners in ship yards. \$5.  
 NAVAL ARCHITECTURE—Sir W. H. White. New Edition. 750 pages. \$9.  
 NAVAL ARCHITECTURE—J. J. Welch. New edition. Out soon.  
 NAVAL ARCHITECTS AND SHIPBUILDER'S POCKET BOOK—Clement Mackrow. Formulae, rules and tables, and marine engineers' and surveyors' Handy Book of Reference. Seventh edition. 700 pages; pocket-book form. \$5.  
 NAVAL POCKETBOOK—Clowe. \$2. Containing valuable information concerning all navies of the world.  
 NAVIGATION SIMPLIFIED—C. E. McArthur. Containing all problems required for U. S. Local Inspector's Examination of Masters and Mates of seagoing vessels. \$1.25.  
 NAVIGATION AND NAUTICAL ASTRONOMY—Prof. J. H. C. Coffin. \$3.50.  
 NAVIGATION: THEORETICAL AND PRACTICAL—D. Wilson Barker. Illustrated. \$1.50.  
 OCEAN METEOROLOGY: For vessels of the Merchant Navy—William Allingham. \$2.  
 THE PILOT: A guide, to United States Local Inspectors' examinations of Masters and Mates. R. M. Pugsley. \$1.  
 POCKET BOOK OF MARINE ENGINEERING, RULES AND TABLES—Seaton and Rounthwaite. For marine engineers, naval architects, superintendents and others engaged in construction of marine machinery. \$3.  
 PRACTICAL BOILER MAKER, IRON SHIP BUILDER AND MAST MAKER—R. Knight. \$2.  
 PRACTICAL INFORMATION ON THE DEVIATION OF THE COMPASS, for the use of Masters and Mates of Iron Ships—J. T. Towson. \$2.  
 PRACTICAL MARINE SURVEYING—Harry Phelps. \$2.50.  
 PRACTICAL SEAMANSHIP FOR USE IN THE MERCHANT SERVICE: Including all ordinary subjects; also Steam Seamanship, Wreck Lifting, Avoiding Collision, Wire Splicing, Displacement, and everything necessary to be known by seamen of the present day. Second edition, illustrated. John Todd and W. B. Whall. \$3.40.

PRACTICAL MECHANICS, Applied to the Requirements of the Sailor—Thos. Mackenzie. \$1.50.  
 PRACTICAL NAVAL ARCHITECTURE—S. J. P. Thearle. Two vols., \$3.  
 PROJECTION TABLES—Bureau of Navigation. \$1.50.  
 RESISTANCE AND PROPULSION OF SHIPS—Durand. \$5.  
 RESISTANCE AND PROPULSION OF SHIPS—By Taylor. \$3.75.  
 SAILING DIRECTIONS FOR THE GREAT LAKES AND CONNECTING WATERS. Second edition. Hydrographic Office. 30 cents.  
 SCOTT'S COAST PILOT FOR THE GREAT LAKES. \$1.50.  
 SCREW PROPELLERS AND MARINE PROPULSION—I. McKim Chase. \$2.50.  
 SELF-INSTRUCTION IN THE PRACTICE AND THEORY OF NAVIGATION—Earl of Dunraven. Two volumes. \$7.  
 SHIP BUILDING—Tables for constructing ship's lines. Second edition. Archibald Hogg. \$2.  
 SIMPLE ELEMENTS OF NAVIGATION—Young. New second edition, \$2; a few copies of the first edition at \$1.  
 STABILITY OF SHIPS—Sir E. J. Reed. \$3.40.  
 STEAM YACHTS AND LAUNCHES—By Kuhnhardt. \$3.  
 STEERING OF SHIPS AND YACHTS AND MANEUVERING THEM IN NARROW WATERS: having especial reference to the influence of the Screw Propeller on the steering of steamers. Sir C. Purcell Taylor. \$1.25.  
 ST. LAWRENCE RIVER SAILING DIRECTIONS. Second edition. Hydrographic Office. 70 cents.  
 SUBMARINE BOATS—By Hovgaard. \$2.  
 TABLES FOR FINDING THE DISTANCE OF AN OBJECT BY TWO BEARINGS—Hydrographic Office, U. S. N. 30 cents.  
 TEXT BOOK OF SEAMANSHIP—Com. S. B. Luce, U. S. N. Equipping and handling of vessels under sail or steam. \$10.  
 THEORETICAL NAVAL ARCHITECTURE: A treatise on the calculations involved in naval design. Samuel J. P. Thearle. In two volumes. \$3.50.  
 THEORETICAL NAVAL ARCHITECTURE—E. L. Atwood. Text book; 114 diagrams. \$2.50.  
 TRIGONOMETRY FOR THE YOUNG SAILOR—R. C. Buck. \$1.50.  
 "WRINKLES" IN PRACTICAL NAVIGATION. Ninth edition, revised. S. T. S. Lecky. \$3.40.

## Books on Marine Engineering, On the Operation of Engines and for Beginners in the Engine Room.

AIDS TO ENGINEERS' EXAMINATIONS, with Questions and Answers—N. Hawkins. \$2.  
 ALGEBRA SELF-TAUGHT—W. P. Higgs. Fourth edition. 60 cents.  
 AMERICAN MARINE ENGINEER—By Edwards. \$2.50.  
 ARITHMETIC OF THE STEAM ENGINE—E. S. Gould. \$1.  
 BOILER MAKERS AND IRON SHIPBUILDERS' COMPANION—James Foden. \$2.  
 BREAKDOWNS AT SEA AND HOW TO REPAIR THEM—A. R. Leask. 252 pages. \$2.  
 BREAKDOWNS—Thos. Reed. \$1.50.  
 CATECHISM OF THE MARINE STEAM ENGINE—Edwards. \$2.  
 DATA BOOK—Valve setting record book, for the use of marine engineers, by P. A. Low. 60 cents.  
 DATA BOOK—The engineer's and draughtsman's data book, for workshop and office use. So arranged that the data of a complete set of engines, boilers, auxiliary engines, pumps, etc., for a steamship can be recorded on four pages. Enough space for 20 sets of engines. Bound in full limp leather. \$1.25.  
 DATA BOOK—Marine engineer's record book—engines. By Bryan C. Bartley. Names of all parts, etc., are printed in one column on the left hand side of book when opened, and the remaining space is lined and column ruled for the recording of all necessary data. Complete thumb index which will facilitate ready reference. Contains enough space for 22 complete sets of engines. Size of book, 7 $\frac{3}{4}$  x 5 $\frac{1}{4}$  in., bound in full limp leather. \$2.00.  
 DRAWING AND DESIGNING FOR MARINE ENGINEERS—Chas. W. Roberts. \$3.  
 ELECTRIC LIGHTING FOR MARINE ENGINEERS, or how to light a ship by the electric light and how to keep the apparatus in order. S. F. Walker. \$2.  
 ELECTRIC SHIP LIGHTING—A hand book on the practical fitting and running of ship's electrical plant. J. W. Urquhart. \$3.  
 ELEMENTARY LESSONS IN STEAM MACHINERY—Langmaid and Galsford. For students and subordinates in marine engineering. \$2.  
 ENGINEER'S MANUAL—By Ainsley. \$5.  
 ENGINEERS' SKETCH BOOK—T. W. Barber, M. E. \$4.  
 ENGINE ROOM PRACTICE—John Leveridge. \$2.50.  
 ENGINES AND ENGINE RUNNING—Joshua Rose. For the use of those who desire to pass an examination to take charge of an engine or boiler; illustrated. \$2.50.  
 EXAMINATION QUESTIONS AND ANSWERS—Emory Edwards. 900 examination questions and answers for young engineers and firemen who desire to obtain marine licenses. \$1.50.  
 GAS AND OIL ENGINES—G. Richmond. A practical hand book on the care and management of gas engines, with instructions for running oil engines. \$1.  
 HAND BOOK OF ENGINEERING PRACTICE—Richard A. Smart. \$1.25.  
 HAWKINS' INDICATOR CATECHISM. \$1.  
 HIGH SPEED STEAM ENGINES—W. Norris and Ben H. Morgan—With 115 illustrations. \$2.50.

HOW TO RUN ENGINES AND BOILERS. Practical instruction for young engineers and steam users. E. P. Watson. New fifth edition. \$1.  
 KEY TO ENGINEERING, WHAT AN ENGINEER SHOULD KNOW ABOUT ELECTRICITY AND ENGINEER'S EPITOME—Three excellent little books for marine engineers. 50 cents each, or three for \$1.  
 KEY TO ENGINES AND ENGINE RUNNING—Joshua Rose. For use of those desiring to pass examination to take charge of an engine or boiler. \$2.50.  
 LESSONS AND PRACTICAL NOTES ON STEAM, THE STEAM ENGINE, PROPELLERS, ETC.—King. \$2.  
 LIBRARY OF STEAM ENGINEERING—John Fehrenbach, M. E. \$5.  
 LUBRICANTS, OILS AND GREASES. Redwood. \$1.50.  
 MACHINISTS' AND DRAFTSMEN'S HAND BOOK—Peder Lobben. A reference book for all interested in mechanical work. \$2.50.  
 MARINE BOILER MANAGEMENT AND CONSTRUCTION—C. E. Stromeyer. \$5.  
 MARINE BOILERS: A treatise on the Causes and Prevention of their Priming, with remarks on their general management. Reed. \$2.  
 MARINE BOILERS—L. E. Bertin. 250 illustrations, designs and tables. \$7.50.  
 MARINE ENGINEERS—Constantine. Just out. \$2.50.  
 MARINE ENGINES—R. Murray. \$1.80.  
 MARINE PROPELLERS—By Barnaby. \$4.25.  
 MARINE STEAM ENGINES—Sennett & Oram. \$6.  
 MARINE STEAM ENGINES—Main and Brown. \$5.  
 MECHANICS' AND ENGINEERS' POCKET BOOK, including Naval Architecture, Steam and the Steam Engine, Steam Vessels, etc. 64th edition, 1050 pages. Chas. H. Haswell. \$4.  
 MECHANICAL ENGINEERS' POCKET BOOK—Wm. Kent. Reference book of rules, tables, etc. \$5.  
 MECHANISM OF MEN-OF-WAR—R. C. Oldknow. A description of machinery to be found in modern fighting ships. Numerous illustrations. \$3.  
 MODERN EXAMINATIONS OF STEAM ENGINEERS—W. H. Wakeman. \$1.50.  
 MODERN AMERICAN MARINE ENGINES—By Edwards. \$5.  
 NAUTICAL ENCYCLOPEDIA, ILLUSTRATED—Howard Patterson. Complete from Standpoint of Marine Engineer and Naval Architect. \$3.  
 NAVAL ENGINEER AND THE COMMAND OF THE SEA—F. G. Burton. \$1.25.  
 NEW CATECHISM OF ELECTRICITY—N. Hawkins. \$2.  
 POCKET BOOK OF MARINE ENGINEERING, RULES AND TABLES—Seaton and Rounthwaite. For marine engineers, naval architects, superintendents and others engaged in construction of marine machinery. \$3.  
 POCKET-BOOK FOR BOILERMAKERS AND STEAM USERS—M. J. Sexton. \$2.  
 PRACTICAL ADVICE FOR MARINE ENGINEERS—C. W. Roberts. 64 illustrations. \$1.

PRACTICAL BOILER MAKER, IRON SHIP BUILDER AND MAST MAKER—R. Knight. \$2.  
 PROGRESS OF MARINE ENGINEERING—By Main. \$1.50.  
 QUESTIONS AND ANSWERS, 188 Elementary, from Reed's Engineers' Hand Book. A valuable help to the young engineer working up for his license. \$1.  
 QUESTIONS AND ANSWERS, sixth edition—Stephen Roper. \$2.  
 REED'S ENGINEERS' HAND BOOK—New edition; illustrated by 345 diagrams and 36 large plates. \$5.  
 REED'S KEY to Reed's Hand Book—Contains working of all questions given in examination papers. \$3.  
 RESISTANCE AND PROPULSION OF SHIPS—W. F. Durand, principal of school of marine construction, Cornell University. \$5.  
 REED'S GUIDE to the extra first-class engineers' examination. \$5.  
 ROPER'S ENGINEERS' HANDY BOOK for Steam Engineers and Electricians. Revised and enlarged. \$3.50.  
 SCREW PROPULSION—By Taylor. \$3.75.  
 SLIDE VALVE, SIMPLY EXPLAINED—W. J. Tennant. \$1.  
 SLIDE VALVES—C. W. MacCord, Jr. A book for practical men on the principles and methods of design. \$1.50.  
 SMALL ENGINES AND BOILERS—Egbert P. Watson. A manual of concise and specific directions for construction of small steam engines and boilers of modern types; illustrated. \$1.25.  
 STEAM AND THE MARINE STEAM ENGINE—Jno. Yeo. \$2.50.  
 STEAM BOILER ECONOMY—Wm. Kent. \$4.  
 STEAM BOILERS—Joshua Rose. Practical treatise on construction and examination. Seventy-three engravings. \$2.50.  
 STEAM BOILERS—Peabody & Miller. \$2.50.  
 STEAM ENGINES AND BOILERS—Frederick Colyer. \$5.  
 STEAMSHIPS AND THEIR MACHINERY—By Hal-dane. \$6.  
 TEXT BOOK ON MARINE ENGINEERING—Tompkins. \$3.00.  
 THEORETICAL AND PRACTICAL AMMONIA REFRIGERATION—I. I. Redwood. \$1.  
 THEORY OF STEAM ENGINE—Weisbach. \$5.  
 TRIPLE AND QUADRUPLE EXPANSION ENGINES AND BOILERS AND THEIR MANAGEMENT—A. Ritchie Leask. Third edition, revised. \$2.  
 VERBAL NOTES AND SKETCHES FOR MARINE ENGINEERS—J. W. Southern. \$1.  
 USEFUL HINTS TO SEAGOING ENGINEERS, AND HOW TO REPAIR AND AVOID BREAKDOWNS. Second edition, revised and enlarged. Reed. \$1.40.  
 WATER TUBE BOILERS—Fifth revised and enlarged edition of HOW TO RUN ENGINES AND BOILERS—E. P. Watson. Practical instruction for young engineers and steam users. \$1.

The Marine Review Publishing Co.,

Sent to any address, carriage prepaid, at prices named.

PERRY-PAYNE BUILDING, CLEVELAND.



## BUYERS' DIRECTORY OF THE MARINE TRADE.

For a more complete classification than that represented by advertisers in the Marine Review, see the BLUE BOOK OF AMERICAN SHIPPING, marine and naval directory of the United States, published by the Marine Review Pub. Co., 418-419 Perry-Payne Bldg., Cleveland.

See accompanying Index of Advertisers for full addresses of concerns in this directory.

### AIR COMPRESSORS, AIR HOISTS, ETC.

"Long Arm" System Co.....Cleveland.

### AIR PUMPS AND APPLIANCES.

Gleason-Peters Air Pump Co.....New York.  
Fore River Ship & Engine Co.....Quincy, Mass.

### ANCHORS.

Baldt Anchor Co.....Chester, Pa.  
International Anchor Co.....Cleveland.  
Seaboard Steel Casting Co.....Chester, Pa.

### ANTI-FRICTION METALS.

Cramp, Wm. & Sons.....Philadelphia.  
Phosphor Bronze Smelting Co., Ltd.....Philadelphia.

### ARTIFICIAL DRAFT FOR BOILERS.

American Blower Co.....Detroit.  
American Ship Building Co.....Cleveland.  
Bloomsburg & Co., H.....Newport News, Va.  
Boston Blower Co.....Hyde Park, Mass.  
Buffalo Forge Co.....Buffalo.  
Detroit Shipbuilding Co.....Detroit.  
Sturtevant, B. F. Co.....Boston.

### ATTORNEYS AND PROCTORS IN ADMIRALTY.

Gilchrist, Albert J.....Cleveland.  
Goulder, Holding & Masten.....Cleveland.  
Hoyt, Dustin & Kelley.....Cleveland.  
MacDonald, Ray G.....Chicago.  
Pinney, Orestes C.....Cleveland.  
Stowe & Graydon.....Chicago.  
White, Johnson, McCaslin & Cannon.....Cleveland.

### BAROMETERS, MARINE GLASSES, ETC.

Bliss, John & Co.....New York.  
Goetz, C. P.....New York.  
Ritchie, E. S. & Sons.....Brookline, Mass.

### BENDING AND STRAIGHTENING ROLLS.

Bement, Miles & Co.....Philadelphia.  
Cleveland Punch & Shear Works Co.....Cleveland.  
Niles Tool Works Co.....Hamilton, O.  
Wood & Co., R. D.....Philadelphia.

### BERTHS, BUNKS, BEDS.

Lein, Irvine & Co.....New York.

### BLOCKS, SHEAVES, ETC.

Boston & Lockport Block Co.....Boston, Mass.  
Cleveland Block Co.....Cleveland.

### BLOWERS.

American Blower Co.....Detroit.  
Boston Blower Co.....Hyde Park, Mass.  
Buffalo Forge Co.....Buffalo.  
Sturtevant, B. F. Co.....Boston.

### BOAT NAILS AND SPIKES.

American Steel & Wire Co.....Chicago.

### BOAT BUILDERS.

Drein, Thos. & Son.....Wilmington, Del.  
Gas Engine & Power Co. and Chas. L. Seabury & Co., Consolidated.....New York.  
Kahnweiler's Sons, David.....New York.  
Lane & DeGroot.....Brooklyn.  
Willard, Chas. P. & Co.....Chicago.

### BOILER MANUFACTURERS.

Almy Water Tube Boiler Co.....Providence, R. I.  
American Ship Building Co.....Cleveland.  
Atlantic Works.....East Boston, Mass.  
Babcock & Wilcox Co.....New York.  
Bath Iron Works, Ltd.....Bath, Me.  
Boyer Water Tube Boiler Co.....New York.  
Chicago Ship Building Co.....Chicago.  
Cramp, Wm. & Sons.....Philadelphia.  
Delaunay, Belleville & Co.....St. Denis, France.  
Detroit Shipbuilding Co.....Detroit.  
Farrar & Trefts.....Buffalo.  
Fletcher, W. & A. Co.....Hoboken, N. J.  
Fore River Ship & Engine Co.....Quincy, Mass.  
Gas Engine & Power Co.....Morris Heights, N. Y.  
Hardy, John B.....Tacoma, Wash.  
Harlan & Hollingsworth Co.....Wilmington, Del.  
Hodge, S. F. & Co.....Detroit.  
Jenks Ship Building Co.....Port Huron, Mich.  
Kingsford Foundry & Machine Works.....Oswego, N. Y.  
MacKinnon Mfg. Co.....Bay City, Mich.  
Maryland Steel Co.....Sparrow's Point, Md.  
Moran Bros. Co.....Seattle, Wash.  
Neafie & Levy Ship & Engine Building Co.....Philadelphia.  
Newport News Ship Building Co.....Newport News, Va.  
Nixon, Lewis.....Elizabeth, N. J.  
Pusey & Jones Co.....Wilmington, Del.  
Risdon Iron Works.....San Francisco.  
Roberts Safety Water Tube Boiler Co.....New York.  
Stirling, The Co.....Chicago.  
Taylor Boiler Co.....Detroit.  
Trigg, Wm. R. Co.....Richmond, Va.  
Union Iron Works.....San Francisco.  
Willard, Chas. P. & Co.....Chicago.

### BOILER COMPOUNDS.

Dearborn Drug & Chemical Works.....Chicago.

### BOILER FURNACES, FIRE FRONTS, ETC.

Continental Iron Works.....New York.

### BOILER RIVETS.

Bourne-Fuller Co.....Cleveland.  
Champion Rivet Co.....Cleveland.

### BOILER STAYBOLTS, IRON OR STEEL, HOLLOW OR SOLID.

Falls Hollow Staybolt Co.....Cuyahoga Falls, O.

### BOLT CUTTERS.

Bement, Miles & Co.....Philadelphia.  
Niles Tool Works Co.....Hamilton, O.

### BORING AND TURNING MILLS.

Bement, Miles & Co.....Philadelphia.  
Niles Tool Works Co.....Hamilton, O.

### BRASS AND BRONZE CASTINGS.

Cramp, Wm. & Sons.....Philadelphia.  
Fore River Ship & Engine Co.....Quincy, Mass.  
Illinois Smelting & Refining Works.....Chicago.  
Phosphor Bronze Smelting Co.....Philadelphia.

### BRIDGES, BUILDERS OF.

Scherzer Rolling Lift Bridge Co.....Chicago.

### BUCKETS, ORE AND COAL.

Brown Hoisting & Conveying Machine Co.....Cleveland.  
McMyler Mfg. Co.....Cleveland.

### CABIN AND CABINET FINISHING WOODS.

Martin-Barriss Co.....Cleveland.

### CAPSTANS.

American Ship Windlass Co.....Providence, R. I.  
Hyde Windlass Co.....Bath, Me.

### CHAINS.

Monongahela Iron & Steel Co.....Pittsburg.  
Newhall Chain Forge & Iron Co.....New York.  
Standard Chain Co.....Pittsburg.

### CHAIN HOISTS.

Boston & Lockport Block Co.....Boston, Mass.

### CHUCKING MACHINES.

Bement, Miles & Co.....Philadelphia.  
Niles Tool Works Co.....Hamilton, O.

### CHUCKS FOR LATHES, DRILLS AND PLANERS.

Skinner Chuck Co.....New Britain, Conn.

### CIRCULATOR, EQUILIBRIUM, with Steam Heating Attachment.

Bloomsburg & Co., H.....Newport News, Va.

### CLOCKS (Marine), CHRONOMETERS, BELLS.

Ashton Valve Co.....Boston.  
Bliss, John & Co.....New York.  
Ritchie, E. S. & Sons.....Brookline, Mass.

### COAL PRODUCERS AND SHIPPERS.

Castner, Curran & Bullitt.....Philadelphia.  
Hanna, M. A. & Co.....Cleveland.  
Ohio Fuel Co.....Cleveland.  
Pickands, Mather & Co.....Cleveland.  
Pittsburg Coal Co.....Cleveland.  
Rochester & Pittsburgh Coal & Iron Co.....Buffalo.  
Scott Co., The W. L.....Erie, Pa.

### COAL AND ORE HANDLING MACHINERY.

Brown Hoisting Machinery Co., Incorporated.....Cleveland.  
Lidgerwood Mfg. Co.....New York.  
Robins Conveying Belt Co.....New York.

### COMPASSES.

Bliss, John & Co.....New York.  
Ritchie, E. S. & Sons.....Brookline, Mass.

### COMPASS ADJUSTER.

Fields, J. M.....Cleveland.

### CORK JACKETS AND RINGS.

Armstrong Cork Co.....Pittsburgh, Pa.  
Kahnweiler's Sons, D.....New York.  
Lane & DeGroot.....Brooklyn.

### CRANES, CONVEYORS, HOISTS.

Brown Hoisting Machinery Co., Incorporated.....Cleveland.  
General Electric Co.....Schenectady, N. Y.  
Lidgerwood Mfg. Co.....New York.  
Niles Tool Works Co.....Hamilton, O.  
Robins Conveying Belt Co.....New York.  
Westinghouse Electric & Mfg. Co.....Pittsburg.  
Wood & Co., R. D.....Philadelphia.

### CRANK PINS.

Cleveland City Forge & Iron Co.....Cleveland.

### DIVING APPARATUS.

Hale Rubber Co., Alfred.....So. Boston, Mass.

### DRILL PRESSES—DRILLS OF ALL KINDS.

Bement, Miles & Co.....Philadelphia.  
Cleveland Punch & Shear Works Co.....Cleveland.  
Niles Tool Works Co.....Hamilton, O.  
Pond Machine Tool Co.....Plainfield, N. J.  
Pratt & Whitney Co.....Hartford, Conn.

### DRILLS, PNEUMATIC.

Standard Pneumatic Tool Co.....Chicago.

### DRYING APPARATUS.

American Blower Co.....Detroit.  
Boston Blower Co.....Hyde Park, Mass.  
Sturtevant, B. F. Co.....Boston.

### DRY DOCKS.

American Ship Building Co.....Cleveland.  
Bath Iron Works, Ltd.....Bath, Me.  
Buffalo Dry Dock Co.....Buffalo.  
Chicago Ship Building Co.....Chicago.  
Craig Ship Building Co.....Toledo, O.  
Cramp, Wm. & Sons.....Philadelphia.  
Detroit Shipbuilding Co.....Detroit.  
Harlan & Hollingsworth Co.....Wilmington, Del.  
Lockwood Mfg. Co.....East Boston, Mass.  
Maryland Steel Co.....Sparrow's Point, Md.  
Moran Bros. Co.....Seattle, Wash.

Newport News Ship Building Co.....Newport News, Va.  
Nixon, Lewis.....Elizabeth, N. J.  
Pusey & Jones Co.....Wilmington, Del.  
Shipowners Dry Dock Co.....Chicago.  
Union Iron Works.....San Francisco.

### ELECTRIC AUTOMATIC WHISTLE OPERATORS.

Signal & Control Co.....New York.

### ELECTRIC LIGHT AND POWER PLANTS.

Badt-Goltz Engineering Co.....Chicago.  
Buffalo Forge Co.....Buffalo.  
Electro-Dynamic Co.....Philadelphia.  
Elwell-Parker Electric Co.....Cleveland.  
General Electric Co.....Schenectady, N. Y.  
Seidler-Miner Electric Co.....Detroit.  
Sturtevant, B. F. Co.....Boston.  
Westinghouse Electric & Mfg. Co.....Pittsburg, Pa.

### ELECTRIC HOISTS AND CRANES.

Elwell-Parker Electric Co.....Cleveland.  
General Electric Co.....Schenectady, N. Y.  
Lidgerwood Mfg. Co.....New York.  
Westinghouse Electric & Mfg. Co.....Pittsburg, Pa.

### ELECTRIC STEERING GEAR, SPEED AND RUDDER INDICATORS, ETC.

Electro-Dynamic Co.....Philadelphia.

### ENGINE BUILDERS, MARINE.

American Ship Building Co.....Cleveland.  
Atlantic Works.....East Boston, Mass.  
Bath Iron Works, Ltd.....Bath, Me.  
Chicago Ship Building Co.....Chicago.  
Chase Machine Co.....Cleveland.  
Craig Ship Building Co.....Toledo, O.  
Cramp, Wm. & Sons.....Philadelphia.  
Detroit Shipbuilding Co.....Detroit.  
Farrar & Trefts.....Buffalo.  
Fletcher, W. & A. Co.....Hoboken, N. J.  
Fore River Ship & Engine Co.....Quincy, Mass.  
Gas Engine & Power Co. and Chas. L. Seabury & Co., Consolidated.....New York.  
Hardy, John B.....Tacoma, Wash.  
Harlan & Hollingsworth Co.....Wilmington, Del.  
Hodge, S. F. & Co.....Detroit.  
Jenks Ship Building Co.....Port Huron, Mich.  
Lake Shore Engine Works.....Marquette, Mich.  
Lockwood Mfg. Co.....East Boston, Mass.  
MacKinnon Mfg. Co.....Bay City, Mich.  
Maryland Steel Co.....Sparrow's Point, Md.  
Moran Bros. Co.....Seattle, Wash.  
Neafie & Levy Ship & Engine Bldg. Co.....Philadelphia.  
Newport News Ship Building Co.....Newport News, Va.  
Nixon, Lewis.....Elizabeth, N. J.  
Olds Motor Works.....Detroit.  
Pusey & Jones Co.....Wilmington, Del.  
Risdon Iron Works.....San Francisco.  
Roach's Ship Yard.....Chester, Pa.  
Sheriffs Mfg. Co.....Milwaukee.  
Trigg, Wm. R. Co.....Richmond, Va.  
Trout, H. G.....Buffalo.  
Union Iron Works.....San Francisco.  
Willard, Chas. P. & Co.....Chicago.

### ENGINE ROOM TELEGRAPH, CALL BELLS, ETC.

Cory, Chas. & Son.....New York.  
Electro-Dynamic Co.....Philadelphia.  
Seidler-Miner Electric Co.....Detroit.

### ENGINEERING SPECIALTIES AND SUPPLIES.

Crane Co.....Chicago.  
Reilly Repair & Supply Co., James.....New York.

### ENGINEERS, MARINE AND MECHANICAL.

Electro-Dynamic Co.....Philadelphia.  
Gaskin, Edward.....Buffalo.  
Hunt, Robt. W. & Co.....Chicago.  
Miller, Walter.....Cleveland.  
Pittsburgh Testing Laboratory, Ltd.....Pittsburg.  
Powell, Ambrose V.....Chicago.  
See, Horace.....New York.  
Wood, W. J.....Chicago.

### EVAPORATING AND DISTILLING APPARATUS.

Reilly Repair & Supply Co., James.....New York.

### FANS FOR VENTILATION, EXHAUST, ETC.

American Blower Co.....Detroit.  
Boston Blower Co.....Hyde Park, Mass.  
Buffalo Forge Co.....Buffalo.  
Sturtevant, B. F. Co.....Boston.

### FEED WATER PURIFIERS AND HEATERS.

Learmonth, Robert.....Buffalo.  
Reilly Repair & Supply Co., James.....New York.  
Reynolds, H. J.....Cleveland.

### FIRE EXTINGUISHING APPARATUS.

Clayton Fire Extinguishing & Disinfecting Co.....New York.

### FIXTURES FOR LAMPS, OIL AND ELECTRIC.

Page Bros. & Co.....Boston.  
Porter's Sons' Co., Wm.....New York.

### FOG SIGNALS.

Colt Co., J. B.....New York.  
Hamilton-Foster Fog Signal Co.....New York.

### FORGES.

Buffalo Forge Co.....Buffalo.  
Sturtevant, B. F. Co.....Boston.

### FORGINGS FOR CRANK, PROPELLER OR THRUST SHAFTS, ETC.

Cleveland City Forge & Iron Co.....Cleveland.  
Fore River Ship & Engine Co.....Quincy, Mass.



## BUYERS' DIRECTORY OF THE MARINE TRADE.—Continued.

## FURNACES FOR BOILERS.

Continental Iron Works.....New York.

## FUELING COMPANIES AND COAL DEALERS.

Castner, Curran & Bullitt (Pocahontas).....Philadelphia.  
 Hanna, M. A. & Co.....Cleveland.  
 Ohio Fuel Co.....Cleveland.  
 Pickands, Mather & Co.....Cleveland.  
 Pittsburgh Coal Co.....Cleveland.  
 Rochester & Pittsburgh Coal & Iron Co.....Buffalo.  
 Scott Co., The W. L.....Erie, Pa.  
 Smith, Stanley B. & Co.....Detroit.  
 Youghiogheny & Lehigh Coal Co.....Chicago.

## GAS BUOYS.

Safety Car Heating &amp; Lighting Co.....New York.

## GAS AND GASOLINE ENGINES.

Chase Machine Co.....Cleveland.  
 Lake Shore Engine Works.....Marquette, Mich.  
 Olds Motor Works.....Detroit.

## GAGES, STEAM AND VACUUM.

American Steam Gauge Co.....Boston.  
 Ashton Valve Co.....Boston.  
 Crosby Steam Gage & Valve Co.....Boston.

## GRAPHITE.

Dixon Crucible Co., Joseph.....Jersey City, N. J.

## GRAPHITE BUSHINGS AND BEARINGS.

Graphite Lubricating Co.....Bound Brook, N. J.

## HAMMERS, PNEUMATIC.

Standard Pneumatic Tool Co.....Chicago.

## HAMMERS, STEAM.

Bement, Miles & Co.....Philadelphia.  
 Chase Machine Co.....Cleveland.  
 Niles Tool Works Co.....Hamilton, O.

## HATCH GEARS.

"Long Arm" System Co.....Cleveland.

## HAWSERS, WIRE.

American Steel &amp; Wire Co.....Chicago.

## HEATING APPARATUS.

Sturtevant, B. F. Co.....Boston.

## HOISTS FOR CARGO, ETC.

American Ship Building Co.....Cleveland.  
 Brown Hoisting Machinery Co., Incorporated.....Cleveland.  
 Chase Machine Co.....Cleveland.  
 Elwell-Parker Electric Co.....Cleveland.  
 General Electric Co.....New York.  
 Hodge, S. F. & Co.....Detroit.  
 Hyde Windlass Co.....Bath, Me.  
 Lidgerwood Mfg. Co.....New York.  
 Marine Iron Co.....Bay City.  
 Westinghouse Electric & Mfg. Co.....Pittsburg.

## HOSE FOR PNEUMATIC TOOLS.

Sayen &amp; Schultz.....Philadelphia.

## HYDRAULIC MACHINERY.

Bement, Miles & Co.....Philadelphia.  
 Watson-Stillman Co., The.....New York.  
 Wood & Co., R. D.....Philadelphia.

## INDICATORS FOR STEAM ENGINES.

American Steam Gauge Co.....Boston.  
 Ashton Valve Co.....Boston.  
 Crosby Steam Gage & Valve Co.....Boston.

## IGNITERS FOR GAS ENGINES.

Holtzer-Cabot Electric Co.....Brookline, Mass.

## INJECTORS.

Crane Co.....Chicago.  
 Jenkins Bros.....New York.

## INSURANCE, MARINE.

Brown & Co.....Buffalo.  
 Chamberlain & Co., S. R.....Chicago.  
 Drake & Maytham.....Buffalo.  
 Elphicke, C. W. & Co.....Chicago.  
 Helm, D. T. & Co.....Duluth, Minn.  
 Hutchinson & Co.....Cleveland.  
 Keith, J. G. & Co.....Chicago.  
 La Salle & Co.....Duluth.  
 Mitchell & Co.....Cleveland.  
 Osborn, F. H. & Co.....Chicago.  
 Parker, A. A. & W. B.....Detroit.  
 Peck, Chas. E. & W. F.....New York and Chicago.  
 Richardson, W. C.....Cleveland.  
 Sullivan, D. & Co.....Chicago.  
 Tandy, Frank N.....Boston.

## IRON ORE AND PIG IRON.

Bourne-Fuller Co.....Cleveland.  
 Hanna, M. A. & Co.....Cleveland.  
 Pickands, Mather & Co.....Cleveland.

IRON OR STEEL STAYBOLTS, HOLLOW OR SOLID.  
 Falls Hollow Staybolt Co.....Cuyahoga Falls, O.

## LATHES OF ALL KINDS.

Niles Tool Works Co.....Hamilton, O.  
 Pratt & Whitney Co.....Hartford, Conn.

## LAUNCHES—NAPHTHA, ELECTRIC.

Gas Engine &amp; Power Co.....New York.

## LIFE PRESERVERS, LIFE BOATS, BUOYS, RAFTS, ETC.

Armstrong Cork Co.....Pittsburg.  
 Drein, Thos. & Son.....Wilmington, Del.  
 Kahnweiler's Sons, D.....New York.  
 Lane & DeGroot.....Brooklyn.

## LIGHTS, SIDE AND SIGNAL.

Page Bros. & Co.....Boston.  
 Porter's Sons' Co., Wm.....New York.

## LOGS.

Walker & Son, Thomas.....Birmingham, Eng.  
 Also Ship Chandlers.

## MACHINE TOOLS (WOOD WORKING).

Atlantic Works, Inc.....Philadelphia.

## MACHINE TOOLS.

Bement, Miles & Co.....Philadelphia.  
 Niles Tool Works Co.....Hamilton, O.  
 Pond Machine Tool Co.....Plainfield, N. J.  
 Pratt & Whitney Co.....Hartford, Conn.

## MALLET FOR CAULKERS, BOILER MAKERS, ETC.

N. Y. Mallet &amp; Handle Works.....New York.

## MARINE RAILWAYS, BUILDERS OF

Crandall &amp; Son, H. I.....East Boston, Mass.

## MATTRESSES, CUSHIONS, BEDDING.

Fogg, M. W.....New York.  
 Lein, Irvine & Co.....New York.

## MECHANICAL DRAFT FOR BOILERS.

American Blower Co.....Detroit.  
 American Ship Building Co.....Cleveland.  
 Boston Blower Co.....Hyde Park, Mass.  
 Bloomsburg & Co., H.....Newport News, Va.  
 Buffalo Forge Co.....Buffalo.  
 Detroit Shipbuilding Co.....Detroit.  
 Sturtevant, B. F. Co.....Boston.

## METALLIC PACKING.

Katzenstein, L. & Co.....New York.  
 U. S. Metallic Packing Co.....Philadelphia.

## METALS FOR BEARINGS.

Cramp, Wm. & Sons.....Philadelphia.  
 Phosphor Bronze Smelting Co., Ltd.....Philadelphia.

## METAL POLISH.

Bertram's Oil Polish Co.....Boston, Mass.  
 Paul & Co., J. C.....Chicago.

## MILLING MACHINES OF ALL KINDS.

Bement, Miles & Co.....Philadelphia.  
 Niles Tool Works Co.....Hamilton, O.

## NAUTICAL INSTRUMENTS.

Bliss, John & Co.....New York.  
 Ritchie, E. S. & Sons.....Brookline, Mass.

## NAVAL ARCHITECTS.

Gaskin, Edward.....Buffalo.  
 See, Horace.....New York.  
 Wood, W. J.....Chicago.

## OAKUM.

Stratford Oakum Co., Geo.....Jersey City, N. J.

## OILS AND LUBRICANTS.

Dixon Crucible Co., Joseph.....Jersey City, N. J.  
 Standard Oil Co.....Cleveland.

## PACKING.

Crane Co.....Chicago.  
 Garlock Packing Co.....Palmyra, N. Y.  
 Jenkins Bros.....New York.  
 Katzenstein, L. & Co.....New York.  
 Sayen & Schultz.....Philadelphia.  
 U. S. Metallic Packing Co.....Philadelphia.

## PAINTS.

Baker, Howard H. & Co.....Buffalo.  
 Toch Bros.....New York.  
 Upson-Walton Co.....Cleveland.

## PATENT ATTORNEYS.

Thurston &amp; Bates.....Cleveland.

## PATTERN SHOP MACHINERY.

Atlantic Works, Inc.....Philadelphia.

## PIPE THREADING AND CUTTING MACHINES.

Merrell Mfg. Co.....Toledo, O.

## PIPE, WROUGHT IRON.

Bourne-Fuller Co.....Cleveland.  
 Crane Co.....Chicago.

## PLANERS OF ALL KINDS.

Bement, Miles & Co.....Philadelphia.  
 Niles Tool Works Co.....Hamilton, O.

## PLANING MILL MACHINERY.

Atlantic Works, Inc.....Philadelphia.

## PLATE BENDING AND PLANING MACHINES.

Bement, Miles & Co.....Philadelphia.  
 Cleveland Punch & Shear Works Co.....Cleveland.  
 Niles Tool Works Co.....Hamilton, O.  
 Wood & Co., R. D.....Philadelphia.

## PLUMBING, MARINE.

Relly Repair & Supply Co., James.....New York.  
 Sands, Alfred B. & Son.....New York.

## PNEUMATIC TOOLS.

Standard Pneumatic Tool Co.....Chicago.

## POLISH FOR METALS.

Bertram's Oil Polish Co.....Boston.  
 Paul & Co., J. C.....Chicago.

## PRESSURE REGULATORS.

D'Este Co., Julian.....Boston.

## PROPELLER WHEELS.

American Ship Building Co.....Cleveland.  
 Atlantic Works.....East Boston, Mass.  
 Bath Iron Works, Ltd.....Bath, Me.  
 Cramp, Wm. & Sons.....Philadelphia.  
 Detroit Shipbuilding Co.....Detroit.  
 Farrar & Trefts.....Buffalo.  
 Fore River Ship & Engine Co.....Quincy, Mass.  
 Hardy, John B.....Tacoma, Wash.  
 Hyde Windlass Co.....Bath, Me.

Harlan & Hollingsworth Co.....Wilmington, Del.  
 Hodge, S. F. & Co.....Detroit.  
 Jenks Ship Building Co.....Port Huron, Mich.  
 Lockwood Mfg. Co.....East Boston, Mass.  
 MacKinnon Mfg. Co.....Bay City, Mich.  
 Maryland Steel Co.....Sparrow's Point, Md.  
 Moran Bros. Co.....Seattle, Wash.  
 Neafie & Levy Ship & Engine Bldg. Co.....Philadelphia.  
 Newport News Ship Building Co.....Newport News, Va.  
 Nixon, Lewis.....Elizabeth, N. J.  
 Phosphor Bronze Smelting Co., Ltd.....Philadelphia.  
 Pusey & Jones Co.....Wilmington, Del.  
 Risdon Iron Works.....San Francisco.  
 Sheriffs Mfg. Co.....Milwaukee.  
 Trigg, Wm. R. Co.....Richmond, Va.  
 Trout, H. G.....Buffalo.  
 Union Iron Works.....San Francisco.

## PROJECTORS, ELECTRIC.

Badt-Goltz Engineering Co.....Chicago.  
 Elwell-Parker Electric Co.....Cleveland.  
 General Electric Co.....Schenectady, N. Y.  
 Rushmore Dynamo Works.....Jersey City, N. J.  
 Seidler-Miner Electric Co.....Detroit.  
 Westinghouse Electric & Mfg. Co.....Pittsburg.

## PUMPS FOR VARIOUS PURPOSES.

Blake, Geo. F. Mfg. Co.....New York.  
 Kingsford Foundry & Machine Works.....Oswego, N. Y.  
 Wood, R. D. & Co.....Philadelphia.  
 Worthington, Henry R.....New York.

## PUNCHES, RIVETERS, SHEARS.

Bement, Miles & Co.....Philadelphia.  
 Cleveland Punch & Shear Works Co.....Cleveland.  
 Niles Tool Works Co.....Hamilton, O.  
 Wood, R. D. & Co.....Philadelphia.

## REGISTER FOR CLASSIFICATION OF VESSELS.

Great Lakes Register.....Cleveland.

## RELEASING HOOKS FOR DETACHING BOATS.

Standard Automatic Releasing Hook Co.....New York.

## RIVETS, STEEL, FOR SHIPS AND BOILERS.

Bourne-Fuller Co.....Cleveland.  
 Champion Rivet Co.....Cleveland.

## R. I. W. DAMP RESISTING PAINT.

Toch Bros.....New York.

## RIGGING ROPE (WIRE).

American Steel &amp; Wire Co.....Chicago.

## RUBBER GOODS.

Hale Rubber Co., Alfred.....So. Boston, Mass.

## RUBBER INSULATED WIRES.

Roebling's Sons, John A.....New York and Cleveland.  
 American Steel & Wire Co.....Chicago.

## SAFETY VALVES.

American Steam Gauge Co.....Boston.  
 Ashton Valve Co.....Boston.  
 Crosby Steam Gage & Valve Co.....Boston.

## SAIL MAKERS.

Baker, Howard H. & Co.....Buffalo.  
 Upson-Walton Co.....Cleveland.  
 Wilson & Silsby.....Boston.

## SALVAGE COMPANIES.

See wrecking companies.

## SEAM COMPOSITION AND ELASTIC SEAM PAINT.

Cole &amp; Kuhls.....Brooklyn.

## SEARCH LIGHTS.

Badt-Goltz Engineering Co.....Chicago.  
 Elwell-Parker Electric Co.....Cleveland.  
 General Electric Co.....Schenectady, N. Y.  
 Rushmore Dynamo Works.....Jersey City, N. J.  
 Seidler-Miner Electric Co.....Detroit.  
 Westinghouse Electric & Mfg. Co.....Pittsburg.

## SHAPERS.

Bement, Miles & Co.....Philadelphia.  
 Niles Tool Works Co.....Hamilton, O.  
 Pratt & Whitney Co.....Hartford, Conn.

## SHEARS.

See punches, riveters and shears.

## SHIP AND BOILER PLATES AND SHAPES.

Bourne-Fuller Co.....Cleveland.

## SHIP BUILDERS.

American Ship Building Co.....Cleveland.  
 Atlantic Works.....East Boston, Mass.  
 Bath Iron Works, Ltd.....Bath, Me.  
 Buffalo Dry Dock Co.....Buffalo.  
 Cramp, Wm. & Sons.....Philadelphia.  
 Craig Ship Building Co.....Toledo, O.  
 Chicago Ship Building Co.....Chicago.  
 Detroit Shipbuilding Co.....Detroit.  
 Fore River Ship & Engine Co.....Quincy, Mass.  
 Hardy, John B.....Tacoma, Wash.  
 Harlan & Hollingsworth Co.....Wilmington, Del.  
 Jenks Ship Building Co.....Port Huron, Mich.  
 Lockwood Mfg. Co.....East Boston, Mass.  
 Maryland Steel Co.....Sparrow's Point, Md.  
 Moran Bros. Co.....Seattle, Wash.  
 Neafie & Levy Ship & Engine Bldg. Co.....Philadelphia.  
 Newport News Ship Building Co.....Newport News, Va.  
 Nixon, Lewis.....Elizabeth, N. J.  
 Pusey & Jones Co.....Wilmington, Del.  
 Risdon Iron Works.....San Francisco.  
 Roach's Ship Yard.....Chester, Pa.  
 Trigg, Wm. R. Co.....Richmond, Va.  
 Union Iron Works.....San Francisco.  
 Willard, Chas. P. & Co.....Chicago.

## SHIP CHANDLERS.

Baker, Howard H. & Co.....Buffalo.  
 Moran Bros. Co.....Seattle, Wash.  
 Relly Repair & Supply Co., James.....New York.  
 Upson-Walton Co.....Cleveland.



## BUYERS' DIRECTORY OF THE MARINE TRADE.—Continued.

<b>SPARS—LARGE SIZES.</b>	
Moran Bros. Co.	Seattle, Wash.
<b>STAYBOLTS, IRON OR STEEL, HOLLOW OR SOLID.</b>	
Falls Hollow Staybolt Co.	Cuyahoga Falls, O.
<b>STEAM VESSEL FOR SALE.</b>	
Holmes, Samuel.	New York.
<b>STEAMSHIP LINES, PASS. AND FREIGHT.</b>	
Algoma Central Co.	Sault Ste. Marie, Ont.
American Line.	New York.
Cleveland & Buffalo Transit Co.	Cleveland.
Dominion Line.	Boston.
Erie & Western Trans. Co.	Buffalo.
International Nav. Co.	Philadelphia.
Red Star Line.	New York.
<b>STEEL CASTINGS.</b>	
Seaboard Steel Casting Co.	Chester, Pa.
<b>STEERING APPARATUS.</b>	
American Ship Building Co.	Cleveland.
Chase Machine Co.	Cleveland.
Detroit Shipbuilding Co.	Detroit.
Electro-Dynamic Co.	Philadelphia.
Hyde Windlass Co.	Bath, Me.
Jenks Ship Building Co.	Port Huron, Mich.
Queen City Engineering Co.	Buffalo.
Sheriffs Mfg. Co.	Milwaukee.
<b>STOCKS, BONDS, SECURITIES.</b>	
Wright, Herbert & Co.	Cleveland.
<b>STOCKLESS ANCHORS.</b>	
Baldt Anchor Co.	Chester, Pa.
International Anchor Co.	Cleveland.
<b>SUBMARINE DIVING APPARATUS.</b>	
Hale Rubber Co., Alfred.	So. Boston, Mass.
<b>SURVEYORS, MARINE.</b>	
Gaskin, Edward.	Buffalo.
See, Horace.	New York.
Wood, W. J.	Chicago.
<b>TELEGRAPH—DECK AND ENGINE ROOM.</b>	
Cory, Chas. & Son.	New York.
<b>TESTS OF MATERIAL.</b>	
Hunt, Robert W. & Co.	Chicago.
Pittsburgh Testing Laboratory, Ltd.	Pittsburg.
<b>THERMOMETERS FOR MECHANICAL PURPOSES.</b>	
Helios-Upton Co.	Peabody, Mass.

<b>TOOLS, METAL WORKING, FOR SHIP AND ENGINE WORKS.</b>	
Bement, Miles & Co.	Philadelphia.
Cleveland Punch & Shear Works Co.	Cleveland.
New Doty Mfg. Co.	Janesville, Wis.
Niles Tool Works Co.	Hamilton, O.
Pond Machine Tool Co.	Plainfield, N. J.
Pratt & Whitney Co.	Hartford, Conn.
Standard Pneumatic Tool Co.	Chicago.
Watson-Stillman Co.	New York.
Wood, R. D. & Co.	Philadelphia.
<b>TOOLS, WOOD WORKING.</b>	
Atlantic Works, Inc.	Philadelphia.
<b>TOPOPHONE—Prevents disasters in fogs.</b>	
Colt Co. J. B.	New York.
<b>TOWING MACHINES.</b>	
American Ship Windlass Co.	Providence, R. I.
Chase Machine Co.	Cleveland.
<b>TOWING COMPANIES.</b>	
Donnelly Salvage & Wrecking Co.	Kingston, Ont.
Midland Towing & Wrecking Co., Ltd.	Midland, Ont.
Swain Wrecking Co.	Detroit.
<b>TRAPS, STEAM.</b>	
D'Este Co., Julian.	Boston.
Haines Co., Wm. S.	Philadelphia.
<b>TRUCKS.</b>	
Boston & Lockport Block Co.	Boston.
<b>TUBING, SEAMLESS.</b>	
Benedict & Burnham Mfg. Co.	Waterbury, Conn.
Standard Seamless Tube Co.	Pittsburg.
<b>VALVES, STEAM SPECIALTIES, ETC.</b>	
American Steam Gauge Co.	Boston.
Ashton Valve Co.	Boston.
Crane Co.	Chicago.
Crosby Steam Gauge & Valve Co.	Boston.
D'Este Co., Julian.	Boston.
Jenkins Bros.	New York.
Wood & Co., R. D.	Philadelphia.
<b>VARNISH PAINT.</b>	
Mair, John & Son.	Philadelphia.
<b>VESSEL AND FREIGHT AGENTS.</b>	
Boland, John J.	Buffalo.
Brown & Co.	Buffalo.
Chamberlain & Co., S. R.	Chicago.
Drake & Maytham.	Buffalo.
Elphicke, C. W. & Co.	Chicago.


Hall & Root.	Buffalo.
Helm, D. T. & Co.	Duluth, Minn.
Holmes, Samuel.	New York.
Hutchinson & Co.	Cleveland.
Keith, J. G. & Co.	Chicago.
Kennedy Hunter & Co.	Antwerp.
Mitchell & Co.	Cleveland.
Richardson, W. C.	Cleveland.
Sullivan, D. & Co.	Chicago.
Tandy, Frank N.	Boston.
<b>VENTILATING APPARATUS FOR SHIPS.</b>	
American Blower Co.	Detroit.
Boston Blower Co.	Hyde Park, Mass.
Buffalo Forge Co.	Buffalo.
Sturtevant, B. F. Co.	Boston.
<b>WIRE ROPE AND WIRE ROPE FITTINGS.</b>	
American Steel & Wire Co.	Chicago.
Baker, H. H. & Co.	Buffalo.
Roebeling's Sons, John A.	New York and Cleveland.
Upson-Walton Co.	Cleveland.
<b>WHISTLES, STEAM.</b>	
American Steam Gauge Co.	Boston.
Ashton Valve Co.	Boston.
Crosby Steam Gauge & Valve Co.	Boston.
Signal & Control Co.	New York.
<b>WINDLASSES.</b>	
American Ship Windlass Co.	Providence, R. I.
American Ship Building Co.	Cleveland.
Hyde Windlass Co.	Bath, Me.
Jenks Ship Building Co.	Port Huron, Mich.
<b>WINCHES.</b>	
American Ship Windlass Co.	Providence, R. I.
Hyde Windlass Co.	Bath, Me.
<b>WOOD WORKING MACHINERY.</b>	
Atlantic Works, Inc.	Philadelphia.
<b>WRECKING AND SALVAGE COMPANIES.</b>	
Donnelly Salvage & Wrecking Co.	Kingston, Ont.
Midland Towing & Wrecking Co., Ltd.	Midland, Ont.
Swain Wrecking Co.	Detroit.
<b>YACHT SAILS, FITTINGS, HARDWARE, ETC.</b>	
Wilson & Silsby.	Boston.
<b>YACHT AND BOAT BUILDERS.</b>	
Dreйн, Thos. & Son.	Wilmington, Del.
Gas Engine & Power Co.	New York.
Lane & DeGroot.	Brooklyn.
Willard, Chas. P. & Co.	Chicago.
<b>YAWLS.</b>	
Dreйн, Thos. & Son.	Wilmington, Del.
Lane & DeGroot.	Brooklyn.

## ALPHABETICAL INDEX OF ADVERTISERS IN THE MARINE REVIEW.

The star (\*) indicates that the advertisement appears alternate weeks. For addresses see advertisements on pages noted.

Algona Central Steamship Line.	38	Detroit Shipbuilding Co.	1	Kahnweiler's Sons, David.	4	Reynolds, H. J.	9
Almy Water Tube Boiler Co.	11	Dixon Crucible Co., Joseph.	9	Katzenstein, L. & Co.	4	Richards, Mills & Co.	12
American Blower Co.	40	Dominion Line.	12	Keith, J. G. & Co.	34	Richardson, W. C.	34
American Line.	7	Donnelly Salvage & Wrecking Co.	32	Kennedy Hunter & Co.	3	Risdon Iron Works.	5
American Ship Building Co.	1	Drake & Maytham.	34	Kingsford Foundry & Machine Works.	30	*Ritchie & Sons, E. S.	30
American Ship Windlass Co.	2	Dreйн, Thos. & Son.	4	Lake Shore Engine Works.	1	Roach's Ship Yard.	5
American Steam Gauge Co.	1	Duluth, South Shore & Atlantic Ry.	39	Lane & DeGroot.	4	Roberts Water Tube Boiler Co.	11
American Steel & Wire Co.	1	Electro-Dynamic Co.	1	*Learmonth, Robert.	30	Robins Conveying Belt Co.	1
Armstrong Cork Co.	40	Elphicke, C. W. & Co.	34	Lein, Irvine & Co.	29	Rochester & Pittsburgh Coal & Iron Co.	33
Ashton Valve Co.	12	Elwell-Parker Electric Co.	2	Lidgerwood Mfg. Co.	10	*Roebeling's, John A. Sons Co.	40
Atlantic Works.	5	Erie & Western Trans. Co.	32	Lockwood Mfg. Co.	4	Rushmore Dynamo Works.	4
*Atlantic Works, Inc.	7	Falls Hollow Staybolt Co.	4	*"Long Arm" System Co.	3	Safety Car Heating & Lighting Co.	31
Babcock & Wilcox Co.	11	Farrar & Trefts.	5	L. S. & M. S. Ry.	39	Sands, Alfred B. & Son.	10
Badt-Goltz Engineering Co.	29	Fields, J. M.	34	MacDonald, Ray G.	34	Sayen & Schultz.	1
Baldt Anchor Co.	9	Fletcher, W. & A. Co.	4	MacKinnon Mfg. Co.	8	Scherzer Rolling Lift Bridge Co.	6
Baker, Howard H. & Co.	6	Fogg, M. W.	31	Mair, John & Son.	6	Scott Co., The W. L.	32
Bath Iron Works, Ltd.	1	Fore River Ship & Engine Co.	5	*Marine Iron Co.	7	Seaboard Steel Casting Co.	27
Bement, Miles & Co.	3	Garlock Packing Co.	27	Martin-Barriss Co.	8	See, Horace.	34
Benedict & Burnham Mfg. Co.	27	Gas Engine & Power Co. and Chas. L.	31	Maryland Steel Co.	5	Seidler-Miner Electric Co.	8
Bertram's Oil Polish Co.	1	Seabury & Co., Consolidated.	31	Merrell Mfg. Co.	5	Sheriffs Mfg. Co.	10
Big Four Railway.	39	Gaskin, Edward.	34	Midland Towing & Wrecking Co., Ltd.	40	Shipowners Dry Dock Co.	12
Blake, Geo. F., Mfg. Co.	9	General Electric Co.	12	Miller, Walter.	9	*Signal & Control Co.	7
*Bliss, John & Co.	30	Gilchrist, Albert J.	34	Mitchell & Co.	34	Skinner Chuck Co.	3
*Bloomsburg & Co., H.	31	*Gleason-Peters Air Pump Co.	29	Monongahela Iron & Steel Co.	3	Smith, Stanley B. & Co.	33
Boland, J. J.	34	Goerz, G. P.	9	*Moran Bros. Co.	39	Standard Chain Co.	10
Boston Blower Co.	4	Gouler, Holding & Masten.	34	Newhall Chain Forge & Iron Co.	5	*Standard Oil Co.	6
*Boston & Lockport Block Co.	40	Graphite Lubricating Co.	9	Newport News Ship Building & Dry	5	Standard Releasing Hook Co.	2
*Boyer Water Tube Boiler Co.	31	Great Lakes Register.	7	Dock Co.	5	*Standard Pneumatic Tool Co.	25
Bourne-Fuller Co.	12	Haines Co., Wm. S.	9	New York Mallet & Handle Works.	30	Standard Seamless Tube Co.	29
Brown & Co.	34	Hall & Root.	34	Niles Tool Works Co.	3	Stirling Co.	11
Brown Hoisting Machinery Co., Inc.	2	Hamilton-Foster Fog Signal Co.	2	Nixon, Lewis.	5	Stowe & Graydon.	34
Buffalo Dry Dock Co.	11	Hanna, M. A. & Co.	32	North River Iron Works.	4	Stratford Oakum Co., Geo.	31
Buffalo Forge Co.	12	Hardy, John B.	4	Osborne & Co., F. H.	34	Sturtevant, B. F. Co.	40
Castner, Curran & Bullitt.	33	Harlan & Hollingsworth Co., The.	5	Page Bros. & Co.	3	Sullivan & Co.	34
Chamberlain & Co., S. R.	34	Helios-Upton Co.	8	Parker, A. A. & B. W.	32	Swain Wrecking Co.	32
Champion Rivet Co.	8	Helm, D. T. & Co.	34	Paul & Co., J. C.	27	Tandy, Frank N.	34
Chase Machine Co.	8	Herriman, F. D.	7	Peck, Chas. E. & W. F.	7	Taylor Boiler Co.	11
Chicago Ship Building Co.	2	Hodge, S. F. & Co.	8	Phosphor Bronze Smelting Co., Ltd.	8	Thurston & Bates.	34
Clayton Fire Extinguishing & Disinfecting Co.	31	Holmes, Samuel.	34	Pickands, Mather & Co.	32	Toch Bros.	29
Cleveland & Buffalo Transit Co.	31	Holtzer-Cabot Electric Co.	2	Pinney, Orestes C.	34	Trigg Co., Wm. R.	4
Cleveland City Forge & Iron Co.	6	Hoyt, Dustin & Kelley.	34	Pittsburg Coal Co.	33	Trout, H. G.	9
Cleveland Punch & Shear Works Co.	27	Hunt, Robert W. & Co.	34	Pittsburg Testing Laboratory, Ltd.	34	Union Iron Works.	5
C. C. C. & St. L. R. R.	39	Hutchinson & Co.	34	Pond Machine Tool Co.	3	Upson-Walton Co.	40
Cole & Kuhls.	9	Hyde Windlass Co.	40	Porter's Sons' Co., Wm.	4	U. S. Metallic Packing Co.	40
Colt Co., J. B.	10	International Anchor Co.	9	Powell, Ambrose V.	34	Walker, Thomas & Son.	3
Continental Iron Works.	2	International Navigation Co.	7	Pratt & Whitney Co.	34	Watson-Stillman Co.	39
Cory, Chas. & Son.	10	Jenkins Brothers.	6-10	Pusey & Jones Co.	5	Westinghouse Electric & Mfg. Co.	6
*Craig Ship Building Co.	30	Jenks Ship Building Co.	39	Queen City Engineering Co.	10	Wheeling & Lake Erie R. R.	39
Cramp, Wm. & Sons, S. & E. B. Co.	1			Red Star Line.	7	White, Johnson, McCaslin & Cannon.	34
Crandall & Son, H. I.	7			*Reilly Repair & Supply Co., James.	10	Willard, Chas. P. & Co.	30
Crane Co.	2-6					Wilson, Thomas.	34
Crosby Steam Gauge & Valve Co.	12					Wilson & Silsby.	6
Dearborn Drug & Chemical Works.	30					Wood, W. J.	34
D'Este Co., Julian.	3					*Wood & Co., R. D.	30
Delauney, Belleville & Co.	26					Worthington, Henry R.	9
Delaware River Iron S. B. & E. Works.	5					Wright, Herbert & Co.	34
						Youghiogheny & Lehigh Coal Co.	33





## HYDRAULIC MACHINERY, TOOLS AND SUPPLIES

FOR MARINE AND SHIP YARD USE.

The **WATSON-STILLMAN CO.**

204 to 210 E. 43rd St., NEW YORK.



## ALGOMA CENTRAL & HUDSON BAY RAILWAY COMPANY STEAMSHIP LINE.

**Steamer OSSIFRAGE**  
Passenger and Freight,  
**TOLEDO to SAULT STE. MARIE**

Leaves Toledo every Friday, at 11.00 a. m. (central time) calling at Windsor, Sarnia, Goderich, Kincardine, Southampton, Little Current, arrive Sault Ste. Marie Sunday 12.00 noon (eastern time). Returning leave Sault Ste. Marie Tuesday at 8.00 a. m.

**Steamer MINNIE M.**  
Passenger and Freight,  
**SAULT STE. MARIE to MICHIPICOTEN.**

Tri-weekly service, calling at intermediate points by arrangement.

**W. B. ROSEVEAR, G. T. M., Sault Ste. Marie, Ontario.**

### WANTED FOR SALE, FOR CHARTER, Etc.

Space under this heading 25 cents a line, each insertion, for three insertions or less. Special rates for periods of more than three insertions.

—FOR SALE—Thirty-ft. cabin naphtha launch; ten horse power; in first-class condition. Richmond Phosphate Co., Richmond, Va. Aug. 29.

—WANTED—Second-hand beam engine about 32 in. by 6 ft. Address box 400, The Marine Review Pub. Co., Cleveland, O. d

—FOR SALE—Half interest in steambarge of 776 tons, A2 class and capable of carrying 950 tons of coal or 650 M ft. lumber. Compound engine and good boiler, the latter allowed 120 lbs. steam pressure. Address or apply to J. E. M., 23 Lodge avenue, Cleveland, O. d

—FOR SALE—Second-hand Wells balanced quadruple expansion engine. Size 8, 12, 16 and 24 by 18 in. Price, \$1,000. Fore River Ship & Engine Co., Quincy, Mass. d

—WANTED—Agents to call on all consumers of polishes, particularly yachts, steamers, etc. Bertram's Oil Polish Co., Boston, Mass. tf

—FOR SALE—Scott's Coast Pilot, 1901 edition. Great lakes and connecting waters. Fully revised. Price, \$1.50. The Marine Review Pub. Co., Cleveland. tf

—FOR SALE—Charts of all the world. Charts of the great lakes always in stock. United States Hydrographic Office charts, Coast Survey charts, Army Engineer charts. We bind charts and back them with tape, so that they will last for years. The Marine Review Pub. Co., Cleveland. tf

## LAKE SHORE & MICHIGAN SOUTHERN RAILWAY.

CLEVELAND CITY TICKET OFFICE 237 SUPERIOR ST

Eastward:		Ar. fr. West.	Dep. East.
No. 18, Southwestern Limited	.....	*2 15 am	*1 55 am
No. 22, Lake Shore Limited	.....	*5 50 am	*2 20 am
No. 26, Pan-American Express	.....	*7 40 am	*3 00 am
No. 28, New York & Boston Express	.....	*11 25 am	*8 00 am
No. 32, Fast Mail	.....	†1 35 pm	*11 30 am
No. 44, Accommodation, via Sandusky	.....	.....	*3 00 pm
No. 46, Southwestern Express	.....	.....	*5 45 pm
No. 6, Limited Fast Mail	.....	*7 35 pm	*7 40 pm
No. 10, Chicago, New York & Boston Special	.....	*10 30 pm	*10 35 pm
No. 16, New England Express	.....	†9 05 pm	†11 30 pm
No. 2, Day Express	.....	†7 55 am	†11 40 am
No. 126, Norwalk Accommodation	.....	.....	†4 30 pm
No. 40, Toledo & Buffalo Accom., via Norwalk	.....	.....	.....
No. 106, Conneaut Accommodation	.....	.....	.....
Westward:		Ar. fr. East.	Dep. West.
No. 11, Southwestern Limited	.....	*3 25 am	.....
No. 15, New York, Boston & Chicago Special	.....	*3 05 am	*3 10 am
No. 21, New York & Chicago Express	.....	*5 10 am	*5 20 am
No. 7, Day Express	.....	*7 35 am	*7 40 am
No. 19, The Lake Shore Limited	.....	*11 10 am	*11 15 am
No. 23, Western Express	.....	*12 25 pm	.....
No. 33, Southwestern Express	.....	.....	*12 30 pm
No. 133, Cleveland & Detroit Express	.....	.....	*13 00 pm
No. 47, Accommodation	.....	.....	*13 10 pm
No. 141, Sandusky Accommodation	.....	.....	*15 10 pm
No. 127, Norwalk Accommodation	.....	.....	*7 20 pm
No. 37, Pacific Express	.....	*7 00 pm	.....
No. 25, Southern Express	.....	*9 30 pm	.....
No. 3, Fast Mail Limited	.....	*10 50 pm	*10 55 pm
No. 115, Conneaut Accommodation	.....	†8 30 am	.....

## Half Rates to COLUMBUS, O. AND RETURN VIA "BIG FOUR ROUTE"

ON ACCOUNT OF

Ohio Agricultural and Industrial Exposition, Aug. 26 to Sept. 7, 1901.

Round trip tickets to Columbus, Ohio, will be on sale on Aug. 26th to Sept. 6th, 1901, inclusive, from all "Big Four" points in Ohio at rate of one fare for the round trip. (No fare less than 25 cents.) Tickets good for return the second day following date of sale. For those desiring longer return limit round trip tickets to Columbus good for return to and including Sept. 7th, 1901, will be on sale from above points on August 26th to Sept. 5th, inclusive, at rate of one and one-third fare for the round trip. For full information and particulars as to rates, tickets, limits, etc. call on agents "Big Four" Route, or address the undersigned.

WARREN J. LYNCH, Gen'l. Pass. & Tkt. Agt. CINCINNATI, O.  
W. P. DEPPE, A. G. P. & T. Agt. CINCINNATI, O.  
D. JAY COLLIER, C. P. & T. A. 116 Euclid Ave. CLEVELAND.



## DULUTH, SOUTH SHORE AND ATLANTIC RAILWAY.

The Only Line Reaching **MARQUETTE, MICH.**

"The Queen of Northern Summer Resorts."

Hotel Accommodations thoroughly first-class headed by the Hotel Superior, the finest Hostelry on the Great Lakes.

GEO. B. ROSS, Lessee, HOTEL SUPERIOR, MARQUETTE, MICH.; Proprietor LEXINGTON HOTEL, CHICAGO, ILL.; formerly Manager CHICAGO BEACH HOTEL.

—WRITE THE UNDERSIGNED FOR ILLUSTRATED PUBLICATIONS.—

E. C. OVIATT, Trav. Pass. Agent, 14 Ottawa St., GRAND RAPIDS, MICH.  
G. A. CLIFFORD, Trav. Pass. Agent, CINCINNATI, OHIO.  
A. E. EDMONDS, City Pass. Agent, DETROIT, MICH.  
F. W. SALSBERY, Commercial Agent, PITTSBURG, PA.  
J. F. LEE, Gen'l Agt. Pass. Dept., 228 So. Clark St., CHICAGO, ILL.  
GEO. W. HIBBARD, Gen'l Pass. Agent, MARQUETTE, MICH.

W. S. JENKS,  
President.

O. L. JENKS,  
Vice-Pres. and Treas.

A. M. CARPENTER,  
Sec. and Gen'l Mgr.

## The Jenks Ship Building Co.

Office and Machine Shops at Fourth St.

Yards: Foot of Lincoln Ave.

PORT HURON, MICH.

Steel and Wood Ship Builders.  
Marine Engines and Boilers.

STEAM WINDLASSES,


CAPSTANS AND

STEERING APPARATUS.

PROMPT ATTENTION GIVEN TO REPAIRS OF ALL KINDS  
ON SHIPS, ENGINES AND BOILERS.

OPERATES THE ONLY THROUGH  
**BUFFET PARLOR CAR LINE**  
Between Cleveland, Canton and Wheeling.  
J. N. MERWIN, E. B. COOLIDGE,  
A. G. P. A. G. P. A.  
CLEVELAND, O.






**STURTEVANT  
ENGINES**

BLOWERS FORGES  
ELECTRIC MOTORS  
GENERATING SETS  
ELECTRIC FANS  
STEAM HEATING  
VENTILATING AND  
DRYING APPARATUS  
MECHANICAL DRAFT

**B.F. STURTEVANT CO.**  
BOSTON, MASS.  
NEW YORK · PHILADELPHIA · CHICAGO · LONDON  
243

## The Upson-Walton Co.,


155-161 RIVER STREET, CLEVELAND, OHIO,



SLEEVE SHOWING CONSTRUCTION.  
BALL BEARING SHEAVES,  
THE LATEST IMPROVEMENT

## SELL THE Cleveland Block

TO BE FOUND ON  
NEARLY ALL THE MODERN  
LAKE VESSELS.



Our New Catalogue No. 118 will tell  
how to save money by employing

**Mechanical Draft**  
COPY MAILED ON REQUEST

**American  
Blower  
Company**  
DETROIT,  
MICH.

NEW YORK, CHICAGO,  
LONDON.

L. CLINE Adv. Dep.

## U. S. METALLIC PACKING CO.

429 N. 13th St. PHILADELPHIA PA.


120,000 PACKINGS IN USE.

12,000 APPLIED IN 1899.

Extensively Used on Ocean, Lake, and Stationary Engines.  
Cheap, Durable and Small Cost for Repairs.

Silver Medal Awarded Paris, 1900.

SEND FOR CATALOGUE.




## NEW STYLE CARGO HOISTING BLOCKS




with Wooden Cheeks, Malleable Iron Frame,  
Wrought Iron Straps, and fitted with new style  
metalline sheaves, which have lignum vitae  
cheeks.

Free  
Illustrated  
112-page  
Catalogue AX.  
on  
application.



Manufactured  
Only by . . . **BOSTON AND LOCKPORT BLOCK CO.,** Boston, Mass., and  
Lockport, N. Y.

## WINDLASSES AND CAPSTANS



The Hyde Steam and Power  
Windlasses and Capstans are the  
best in the market.

They have been selected for  
most of the vessels now building  
for the Navy Department, Rev-  
enue Marine, Light-house Board  
and United States Coast Survey.

They are being furnished for  
the majority of the highest class  
Steam Ships, Merchant Vessels  
and Yachts now building.

**HYDE WINDLASS CO., Bath, Me.**

**LIFE PRESERVERS—BUOYS.**

**Acme, Solid Cork, Granulated Cork.**

EACH PRESERVER stamped by United States Inspector guaranteeing proper  
buoyancy. Cork Filled Yacht Fenders. Cork Mooring Buoys. Material  
and Finish Guaranteed. Orders filled promptly.

**ARMSTRONG CORK COMPANY,**

Boston. New York. Philadelphia. Pittsburg. Chicago. St. Louis. Baltimore.

**Midland Towing & Wrecking Co., Ltd.**

MIDLAND, ONT., CANADA.

JAMES PLAYFAIR, Pres't and  
Gen. Mngr.  
D. L. WHITE, Vice-Pres.  
J. W. BENSON, Sec'y and Treas.

**FIRST-CLASS TUGS FOR WRECKING, RAFT TOWING, ETC.**

**STEAM PUMPS, DIVERS, JACKS, HAWSERS, LIGHTERS.**



EVERY PACKAGE OF BERTRAM'S POLISH, OIL AND PASTE (except 3 and 8-oz. Cans) CONTAINS ONE OF OUR "20TH CENTURY LUCK COINS." TRY A PACKAGE OF THE BEST POLISH IN THE WORLD AND SECURE YOUR CENTURY'S LUCK. ORDER FROM SHIP CHANDLERS AND ENGINEERS' SUPPLIERS.

**Bertram's Polish**

LUCK FOR 20th CENTURY IN MOST POPULAR POCKET PIECE EVER INVENTED.


BERTRAM'S OIL POLISH CO., BOSTON, MASS.

# MARINE REVIEW

VOL. XXIV.

CLEVELAND, O., AUGUST 15, 1901.

No. 7



## The Superior Marine Gasoline Engine

IS BUILT FOR HEAVY SERVICE.

Every sail boat and steamer should carry one in a tender. Small schooners save tug bills. One in a delivery boat pays for itself the first year. Built in single, double and triple cylinders. Send for catalogue and description of how it acted in a U. S. life-boat.

LAKE SHORE ENGINE WORKS, Marquette, Mich.

## The Wm. Cramp & Sons Ship and Engine Building Co. PHILADELPHIA.

SOLE MANUFACTURERS IN AMERICA OF

**Parsons Manganese Bronze  
AND Parsons White Brass.**

EDWARD W. HYDE, President. H. H. McCARTY, Treasurer.  
JOHN S. HYDE, Vice-Pres. and Gen'l Supt.

## BATH IRON WORKS, Ltd.

Ship Builders and Engineers,

BATH, MAINE.

W. L. BROWN, President.  
R. L. IRELAND, Vice-president.  
R. C. WETMORE, Sec'y and Treas.  
JAS. C. WALLACE, Gen'l Manager.

**DRY DOCKS IN CLEVELAND:**  
No. 1, foot Weddell St., 440 ft. x 50 ft. x 16 ft.  
No. 2, foot Weddell St., 300 ft. x 55 ft. x 13 ft.  
No. 3, Elm St., 340 ft. x 50 ft. x 13 ft.  
Dry Dock at Lorain: 560 ft. x 60 ft. x 17 ft.

## The American Ship Building Co.

OFFICE, 120 VIADUCT, CLEVELAND, O.

## STEEL SHIPS

MARINE AND STATIONARY ENGINES.  
BOILERS AND AUXILIARY MACHINERY.

PROMPT ATTENTION GIVEN TO SHIP  
REPAIRS OF ALL KINDS.

WORKS AT  
CLEVELAND AND LORAIN.

## THE ELECTRIC STEERING GEAR.

CIRCULARS AND PRICES ON APPLICATION.

## The Electro-Dynamic Co.,

212-226 Ionic Street, Philadelphia, Pa., U. S. A.

Cable Address: EDCO, A B C Code 4th Edition.

# WIRE HAWSERS RIGGING

GALVANIZED.  
STRONGEST.  
MOST SATISFACTORY.

AMERICAN STEEL & WIRE COMPANY, - THE ROOKERY, - CHICAGO, ILL.

ALEXANDER McVITTIE, President and Manager.  
WILLIAM C. McMILLAN, Vice-President.

CHARLES B. CALDER, General Superintendent.


M. E. FARR, Secretary and Treasurer.  
FRANK E. KIRBY, Consulting Engineer.

## DETROIT SHIPBUILDING COMPANY, SHIP AND ENGINE BUILDERS,

DETROIT, MICH.

Sole Owners for the Lakes and Atlantic Coast of the HOWDEN HOT DRAFT SYSTEM,  
as applied to Boilers, giving increased power and great economy.

Steel Ship Yard Located at Wyandotte, Mich.  
Wooden Ship Yards and Dry Docks, Foot of Orleans  
Street, and Foot of Clark Ave., DETROIT, MICH.



## AMERICAN STEAM GAUGE AND VALVE MFG. CO.

(Original Steam Gauge Company.)

NEW YORK. BOSTON. CHICAGO.  
1 AND 2 RANGOON ST., LONDON, ENG.

MANUFACTURERS OF

Gauges that Gauge,  
Indicators that Indicate,  
Pops that Pop.

Clocks, Revolution Counters, Whistles, and all  
kinds of Steamship Instruments.  
Original and only Genuine Thompson Indicator.

HIGHEST AWARD AT THE PARIS EXPOSITION.  
The Only American Indicator to Receive a Medal.

Board of Trade Drop Lever Two  
Pop Safety Valves.

## POSTAGE AND PRINTING WASTED.

Tons of it fail to reach the right people.

Not so when lists are selected from such reliable publications as the

## Blue Book of American Shipping.

1901 EDITION NOW IN PREPARATION.

A directory of everything pertaining to ships. Lists of Ship Owners,  
Ship Masters, Ship Builders, Naval Engineers, Marine Engineers.

Advertising rates and other information on application.

THE MARINE REVIEW PUB. CO., CLEVELAND, O.

**"COAL HANDLING"** OUR NEW ILLUSTRATED BOOK SENT ON APPLICATION.  
ROBINS CONVEYING BELT CO., 22 PARK ROW, NEW YORK.

HOSE, BELTING, VALVES, ETC.,  
FLAX AND GUM CORE PACKINGS  
FROM FACTORY TO CONSUMER.

**SAYEN & SCHULTZ,**  
Mechanical Rubber Works,  
PHILADELPHIA, PA.

"MELVILLE" PATENT SHEET GUM  
WITH WIRE GAUZE INSERTION WILL  
NOT BLOW OUT.

**RUBBER GOODS**



# THE BROWN HOISTING MACHINERY COMPANY, Incorporated.

Engineers, Designers and Manufacturers

—OF—  
**SPECIAL MACHINERY**  
FOR HANDLING COAL AND ORE

under the well known "BROWNHOIST" Patents.

Cantilever and Gantry Cranes

For Handling Structural Work,  
Marine Plates, Etc.

Locomotive Cranes for Ship Building Yards.

Main Office and Works, CLEVELAND, O., U. S. A.

Eastern Office,  
26 Courtlandt St., New York.

Pittsburg Office,  
Carnegie Building, Pittsburg, Pa.

European Office,  
39 Victoria St., London, S. W.

## GENERATORS **ELWELL-PARKER ELECTRIC CO.** MOTORS

OF AMERICA  
MANUFACTURERS  
GUARANTEES QUALITY  
CLEVELAND, OHIO.

STANDARD MARINE GENERATING SETS.

COMPLETE HOISTING AND POWER PLANTS.

**AMERICAN SHIP WINDLASS CO.,**

P. O. Box 53, PROVIDENCE, R. I.

Send for Catalogue.

Address FRANK S. MANTON, Agent.

**Ship Machinery.**

Sole Builders of the **ORIGINAL** and **ONLY AUTOMATIC**  
**STEAM TOWING MACHINE.**

WILLIAM L. BROWN,  
President.

B. W. WELLS,  
Vice-President.

O. R. SINCLAIR,  
Sec'y and Treas.

JOHN A. UBSDELL, JR.,  
Genl. Mngr.

## CHICAGO SHIP BUILDING COMPANY,

Long Distance Telephones.

Ship Yard and Dry Dock Office,  
"South Chicago 40."

Chicago Office, 1125 Rookery,  
"Harrison" 1207.

**STEEL SHIP BUILDERS AND  
DRY DOCK PROPRIETORS.**

Dry Dock and Yards: 101st St. and Calumet River, CHICAGO, ILL.



### Standard Automatic Releasing Device.

THE FALLS ARE SO ROVE THAT BOTH ENDS  
OF THE BOAT DETACH, IRRESPECTIVE OF  
WHICH END STRIKES THE WATER FIRST.

Will release a boat immediately in the  
roughest sea or under speed and can be  
hooked on without delay or injury to the  
hands of men hooking it on.

Standard Automatic Releasing Hook Co.,

NEW CHEESEBROUGH BUILDING,

17 State Street, New York, N. Y.



**A BIG FAT SPARK EVERY TIME**  
if you use our Magneto Igniter. Expense and annoy-  
ance of batteries avoided, and continuous, satisfactory  
operation of gas or gasoline engine assured. Special  
styles for automobiles and launches.

Send for our new booklet X for full particulars.  
It will interest you.

**THE HOLTZER-CABOT ELECTRIC CO., BOSTON, (Brookline) MASS.**  
New York Office, 115 Broadway. Chicago Office, 397 Dearborn St.

## CRANE FITTINGS

ESTABLISHED 1855

## MORISON SUSPENSION BOILER FURNACES

—FOR—

**LAND and MARINE BOILERS.**

UNIFORM THICKNESS—EASILY CLEANED  
UNEXCELLED FOR STRENGTH.

**Also Fox Corrugated Furnaces.**


Manufactured by

## THE CONTINENTAL IRON WORKS,

West and Calyer Sts NEW YORK

Near 10th and 23d Sts. Ferries.

Borough of Brooklyn.





## THE "LONG ARM" SYSTEM CO.

Cor. Lake and Wason Sts., CLEVELAND, O., U. S. A.

BUILDERS OF

PNEUMATIC  
AND  
ELECTRIC

**Safety Power Doors and  
Hatch Gears for Ships.**


SPECIAL AIR COMPRESSORS FOR MARINE WORK.

## THOMAS WALKER & SON, BIRMINGHAM, ENGLAND.

THE  
"NEPTUNE"  
SHIP-LOG  
WITH BALL BEARINGS  
FOR  
HIGH SPEEDS.


Particulars  
on Application.

SOLD BY ALL  
SHIP CHANDLERS.



As used in the British Navy.

## THE HAMILTON-FOSTER FOG SIGNAL



Directs a distinctive signal  
to each of the eight points of  
the compass, thereby convey-  
ing to the mariner its exact  
location.

This machine is for light-  
house stations only.  
Other models for ships and  
ferries.

WRITE FOR DESCRIPTIVE MATTER.

**HAMILTON-FOSTER FOG SIGNAL CO.,**

No. 11 BROADWAY, (Room 1167), NEW YORK, N. Y.


**BRITISH ADMIRALTY CHART OF GEORGIAN BAY** from Commander Boulton's survey, sent post-paid to any address at \$1.25. Regular price \$1.75. **WHOLE BAY ON ONE SHEET.** Size of sheet, 3 ft. x 3 ft.

THE MARINE REVIEW PUB. CO., PERRY-PAYNE BUILDING, CLEVELAND.

## KENNEDY HUNTER & CO., ANTWERP,

SHIP BROKERS, STEAMSHIP AND FORWARDING AGENTS.

AGENTS for BELGIAN, BRAZIL and RIVER PLATE MAIL LINE; MESSRS. LAMPORT & HOLT, of Liverpool; GENERAL STEAM NAVIGATION CO.'S LINE, ANTWERP to LONDON. Regular Lines of Steamers to SPAIN, PORTUGAL, ITALY, MEDITERRANEAN, BLACK SEA, and DANUBE Ports. Direct steamships to BOMBAY and KURRACHEE, CHINA and JAPAN. Direct Sailors to SAN FRANCISCO. Branches:—PARIS, CHARLEROI, BRUSSELS, and RUHRORT.



## Improved Pressure Regulator FOR STEAM.

In use on Steamships, for deck machinery, pumps, supplying steam to engines at lower than boiler pressure, for steam heating; or, in any place where it is desired to reduce from a higher to a lower pressure automatically.

SEND FOR CATALOGUE.

**JULIAN D'ESTE COMPANY,**  
24 Canal Street. BOSTON, MASS.

## BEMENT, MILES & CO.

MAKE A SPECIALTY OF

## Machine Tools

For Ship Building and Repair Yards.

NEW YORK:  
136-138 Liberty Street.

BOSTON:  
65 Oliver Street.

BUFFALO:  
Seneca and Wells Streets.

CHICAGO:  
Western Union Building.

PITTSBURG:  
Carnegie Building.

ST. LOUIS:  
615 N. Fourth Street.


ALSO A FULL LINE OF  
**HYDRAULIC MACHINERY.**



SINGLE FRAME STEAM HAMMER.

21st and Callowhill Streets,  
PHILADELPHIA, PA.


## STEAM HAMMERS.



STEAM RIVETER.

## SKINNER CHUCKS

For LATHES,  
DRILLS and  
PLANERS



A finely illustrated Catalogue, 6 x 9, sent to interested parties.

**THE SKINNER CHUCK CO.,** 340 CHURCH STREET.  
NEW BRITAIN, CONN.


## Monongahela Iron and Steel Co.

MANUFACTURERS OF

CHARCOAL **CARTER BRANDS** CHARCOAL  
BAR IRON IRON CHAINS  
ALL SIZES.

United States Government Specifications Guaranteed.  
**PITTSBURGH, PA.**






## Fan and Pressure Blowers,

EXHAUST FANS FOR ALL USES.

Hot Blast Heating Apparatus, Dry Kiln Outfits, Steam and Electric Fans, Forges, High and Low Pressure Engines.

SEND FOR CIRCULARS.

BOSTON BLOWER CO., Hyde Park, Mass.



## Ship Lamps

OIL AND ELECTRIC FIXTURES

FOR

Steamships, Yachts, &c.

GREAT VARIETY OF DESIGNS.

Prices and Cuts on Application.

**PAGE BROS. & CO.**

347 to 357 Cambridge St. Boston, Mass.



## SEARCH LIGHTS - - -

RUSHMORE PROJECTORS are in almost exclusive use in all classes of service, and are specified for finest Steamers and Yachts.

RUSHMORE DYNAMO WORKS,

TELEPHONE 559.


JERSEY CITY.

Reed's Engineers' Hand Book.

Reed's Guide to Examinations.

Key to Reed's Engineers' Hand Book.

MARINE REVIEW PUB. CO., Cleveland, O.



## MARINE LIGHTING EQUIPMENT.

**WM. PORTER'S SONS' CO.**

F. J. RUSSELL, Electrical Engineer.

271 Pearl St., NEW YORK.

## NEVERSINK CORK JACKET AND LIFE BELT.

Warranted 24 pounds. Buoyancy and full Weight of Cork, as required by U. S. Inspectors.

Consolidated Cork Life Preservers. Ring Buoys and Fenders.

SAFEST, CHEAPEST.

Approved and adopted by U. S. Board of Supervising Inspectors. Also adopted by the principal Ocean, Lake and River Steamer Lines as the only Reliable Life Preserver. Awarded four Medals by World's Columbian Exposition.

Metallic and Wooden Life Boats.



Metallic Life Rafts. Marine Drags.


Manufacturers of Woolsey's Patent Life Buoy—the lightest, cheapest and most compact Life Raft known.

**DAVID KAHNWEILER'S SONS**  
437 Pearl Street, NEW YORK CITY.

Send for Illustrated Catalogue.



## KATZENSTEIN'S Self-Acting METAL PACKING



For PISTON RODS, VALVE STEMS, etc., of every description, for Steam Engines, Pumps, etc., etc.

Adopted and in use by the principal Iron Works and Steamship Companies, within the last twelve years, in this and foreign countries.

FLEXIBLE TUBULAR METALLIC PACKING, for slip-joints on Steam Pipes, and for Hydraulic Pressure; also METAL GASKETS for all kinds of flanges and joints.

Double-Acting Balanced Water-Tight Bulkhead Doors for Steamers. Also Agents for the McColl Cumming Patent Liquid Rudder Brake. For full particulars and reference, address:

**L. KATZENSTEIN & CO.,**  
General Machinists, Brass Finishers, Engineers' Supplies,  
357 WEST ST. NEW YORK.

## THE LOCKWOOD MANUFACTURING CO. IRON WORKS AND DOCKS,

61 to 85 Sumner Street, EAST BOSTON, MASS.

BUILDERS OF

Steamships, Tow Boats and Marine Engines.

REPAIRING OF EVERY DESCRIPTION.

Builders of the Celebrated LOCKWOOD PROPELLER WHEELS.

**WM. R. TRIGG COMPANY,**  
SHIP BUILDERS, RICHMOND, VA.  
Government Contractors,

Building United States Torpedo Boats

SHUBRICK, STOCKTON and THORNTON,  
and Torpedo Boat Destroyers DALE and DECATUR.

SHIPBUILDING IN ALL ITS BRANCHES.


**W. & A. FLETCHER CO.**  
NORTH RIVER IRON WORKS.  
Marine Engines, Boilers, Etc.

Hudson, 12th and 14th Streets, Hoboken, N. J.

Take Ferry from foot of West 14th Street, N. Y.

**FALLS HOLLOW STAYBOLTS.**  
ANY SIZE, OUTSIDE OR INSIDE DIAMETER.  
AVERAGE LENGTH OF HOLLOW BARS  
SIX TO EIGHT FT.  
BOTH HOLLOW AND SOLID, MADE OF  
THE BEST QUALITY OF CHARCOAL IRON OR STEEL. CUYAHOGA FALLS O. U.S.A.

Guaranteed to pass U. S. Government or Railway Companies Specifications.



**THOS. DREIN & SON,**

BUILDERS OF

Metallic Life Boats and Rafts, Government and Pleasure Boats, Block and Granulated Cork Life Preservers. Outfits for Lake Steamers a Specialty.

TATNALL & RAILROAD STS  
WILMINGTON, DEL.



**LANE & DeGROOT,**  
METALLIC LIFE BOATS,

(Formerly Raymond's)

Metallic Life Rafts, Cork Life Preservers, Etc., approved by the U. S. Supervising Inspectors. Also Wood Boats of Every Description. Repairing of every kind promptly attended to.

Telephone Call 340-B, Greenpoint.

70 and 72 Kent St., BROOKLYN, NEW YORK.

## KEEP FILES


OF TRADE JOURNALS.

A handy and substantial binder, into which each issue may be securely and neatly placed with trifling effort, may be had at \$1.

THOUSANDS OF THEM IN USE.

THE MARINE REVIEW PUB. CO., Perry-Payne Building, Cleveland.



**ROACH'S SHIP YARD.**

DELAWARE RIVER  
—IRON—  
SHIP-BUILDING &  
ENGINE WORKS,  
CHESTER PA.

Builders of Steamships and Marine Machinery.  
SHIP-BUILDING IN ALL ITS BRANCHES.  
New York Office, Morgan Iron Works, Foot East Ninth St

**SHIP AND ENGINE BUILDERS.****Newport News Shipbuilding and Dry Dock Company.**

Equipped with a Simpon's Basin Dry Dock capable of docking a vessel 600 feet long drawing 25 feet of water, at any stage of the tide Repairs made promptly and at reasonable rates.

For estimates and further particulars, address

**C. B. ORCUTT, President,**  
No. 1 BROADWAY, NEW YORK.

WORKS AT NEWPORT NEWS, VA.  
(ON HAMPTON ROADS.)

**MARYLAND STEEL CO.,**

Marine Department.

**Ship Builders and Engineers**

SPARROW'S POINT, MD.

Baltimore Telephone No. 11.

A. G. WILSON, Manager.

Long Distance Telephone Service Between New York, Philadelphia, Boston and Sparrow's Point Offices.

New York Office: 71 Broadway.

Boston Office: 70 Kilby Street.

Philadelphia Office: 312-319 Girard Building.

**The Pusey & Jones Company,**

WILMINGTON, DELAWARE.

Builders of IRON AND STEEL STEAMERS, STEAM YACHTS,  
TOW BOATS, MARINE ENGINES, BOILERS, TANKS,  
AND OF HEAVY MACHINERY GENERALLY.

ALSO COPPERSMITH WORK.

SPECIAL FACILITIES for REPAIRS to both WOODEN and METAL BOATS.  
MARINE RAILWAY. NO WHARFAGE CHARGED

**Risdon Iron Works,**  
IRON AND STEEL SHIP BUILDERS,  
SAN FRANCISCO.

FORE RIVER SHIP AND ENGINE COMPANY, SUCCESSORS TO Fore River Engine Co.  
Steel Ship and Marine Engine Builders.

CONTRACTORS FOR  
U. S. Torpedo Boat Destroyers Lawrence and Macdonough.  
U. S. Protected Cruiser Des Moines  
U. S. Battleships New Jersey and Rhode Island.  
U. S. Steam Light-Vessel No. 72.

OFFICE AND WORKS: QUINCY, MASS., U. S. A.

**FARRAR & TREFTS,**

Propeller, Yacht and Tug Wheels.  
Marine and Stationary Engines & Boilers.  
Repairing Promptly Attended to.  
Drilling Boilers and Engines a Specialty.

64 to 66 Perry Street, BUFFALO, N. Y.

WORKS AND  
MAIN OFFICE, WILMINGTON, DEL.


**The Harlan & Hollingsworth Co.**

SHIP BUILDERS,  
DRY DOCKING, REPAIRING  
AND OUTFITTING.

(3-4 CENTURY EXPERIENCE.)

NEW YORK OFFICE, { EXCHANGE COURT BUILDING,  
52 BROADWAY, ROOM 702.

**UNION IRON WORKS**  
**SHIP BUILDERS,**  
**SAN FRANCISCO.**

**PIPE THREADING AND CUTTING MACHINES**

HAND OR POWER.

Types combining all that is LATEST and BEST.  
Established reputation for durability and rapidity of work.

GREAT RANGE OF WORK.  
QUICK CHANGE FROM SIZE TO SIZE OF PIPE.  
GEARS COMPLETELY HOUSED.

**MERRELL MFG. CO.**

SEND FOR  
CATALOGUE R.

Toledo, Ohio,  
U. S. A.

MATHIAS SEDDINGER, President.  
SOMMERS N. SMITH, Vice-Pres't and Gen'l Mgr.

ESTABLISHED 1838.

**THE NEAFIE & LEVY SHIP & ENGINE BUILDING COMPANY,**  
**PENN WORKS.**

IRON AND STEEL SHIP AND MARINE ENGINE BUILDERS.

SOLE MAKERS OF THE WELL KNOWN

PHILADELPHIA PROPELLER WHEEL.

Beach and Palmer Streets, PHILADELPHIA, PA., U. S. A.

**The Atlantic Works,** BUILDERS OF . . . STEAMSHIPS,  
STEAM YACHTS,  
TOW BOATS, ETC.  
EAST BOSTON, MASS.

Marine Engines, Boilers and Tanks,  
Heavy Machinery and Plate Iron Work.

**LEWIS NIXON, SHIP BUILDER**

Office and Works, ELIZABETH, N. J.

Builder of Stern-wheel, Paddle and Screw Steamers; also Torpedo  
Boats and Barges of all kinds in Steel.

A Specialty made of South American and Alaskan River Boats.



## CRANE VALVES

ESTABLISHED 1855

### Patterson's Nautical Encyclopedia.

Is in all respects a work up to date, correct as to every term known to the shipping world.

Divided as to departments of Naval Architecture, Marine Engineering, etc.

The latest and bound to be the most complete work of its kind. Best effort of Howard L. Patterson, New York, author of several standard books on marine subjects.

**JUST FROM THE PRESS. \$3 PER COPY.**

Order from THE MARINE REVIEW PUB. CO., CLEVELAND.

As complete in everything pertaining to naval architecture and marine engineering as it is in sea terms. No expense spared in illustrations. Special attention given to the modern steel ship. A work that may well be recommended to admiralty lawyers.

**WILSON & SILSBY,** Rowe's Wharf,  
**BOSTON, MASS.**  
MAKERS OF

### Sails for Yacht Independence.

— ALSO THE —  
**OUTFITS OF LARGE STEAM YACHTS.**



### JENKINS '96 PACKING.

Pronounced by steam users throughout the world the best joint packing manufactured. Expensive? Not at all, as it weighs 30% less than many other packings, consequently is much cheaper.

**JENKINS BROTHERS,**  
NEW YORK BOSTON PHILADELPHIA CHICAGO

**Howard H. Baker & Co.**

**SHIP CHANDLERS  
AND SAIL MAKERS,**

18 to 26 Terrace

**BUFFALO, N. Y.**

## ON THE GREAT LAKES, GOOD ENGINEERS SEASON OF 1901, ARE MAKING BETTER TIME WITH THE BEST OILS

PORTS AT WHICH

**MARINE VALVE,  
MINERAL SEAL,**

**600 W. CYLINDER OIL,**

**DARK LUBRICATING,  
ELDORADO ENGINE,  
AND ARCTIC CUP GREASES ARE ON SALE:**

**VACUUM No. 1 MARINE ENGINE OIL,  
RENOWN ENGINE,  
HEAD LIGHT, CRANK CASE,**

**VICTOR SIGNAL,  
LARD OILS,**

**Cleveland, O.,** Standard Oil Co., 127  
River Street.  
**The Upson Walton Co.**  
**Buffalo, N. Y.,** Standard Oil Co., 15  
Ohio Street.  
**Chicago, Ill.,** Standard Oil Co., 5 Wa-  
bash Avenue.  
**South Chicago, Ill.,** So. Chicago Ship  
Chandlery Co.  
**Milwaukee, Wis.,** Standard Oil Co.  
**Joys Bros. & Co.**  
**Sheriffs' Mfg. Co.**  
**Manitowoc, Wis.,** Standard Oil Co.

**Marinette, Wis.,** Standard Oil Co.  
**West Superior, Wis.,** Standard Oil  
Co.  
**Hancock, Mich.,** Standard Oil Co.  
**Detroit, Mich.,** Standard Oil Co.  
**H. D. Edwards & Co.**  
**Muskegon, Mich.,** Standard Oil Co.  
**West Bay City, Mich.,** Standard Oil  
Co.  
**Sault Ste. Marie, Mich.,** Standard  
Oil Co.  
**Conneaut Harbor, O.,** Lake Erie  
Supply Co.

**Marine City, Mich.,** Scott Bros. &  
De Lisle.  
**Fairport Harbor, O.,** The Marine  
Supply Co.  
**Ashtabula Harbor, O.,** McKinnon  
Iron Works.  
**Escanaba, Mich.,** Standard Oil Co.  
**Marquette, Mich.,** Standard Oil Co.  
**Tonawanda, N. Y.,** James O'Connor.  
**Saginaw, Mich.,** Standard Oil Co.  
**St. Ignace, Mich.,** Standard Oil Co.  
**Manistique, Mich.,** Standard Oil Co.

**Ludington, Mich.,** Standard Oil Co.  
**Duluth, Minn.,** Standard Oil Co.  
**Ashland, Wis.,** Standard Oil Co.  
**Racine, Wis.,** Standard Oil Co.  
**Erie, Pa.,** Atlantic Refining Co.  
**Sandusky, O.,** W. L. Lewis.  
**Green Bay, Wis.,** Standard Oil Co.  
**Lorain, O.,** N. C. Alton.  
**Huron, O.,** Henry Hull.  
**Port Huron, Mich.,** D. Robeson.  
**Toledo, O.,** The M. I. Wilcox Co.  
**Cheboygan, Mich.,** Standard Oil Co.

## Polyphase Induction Motors

FOR OPERATING PORTABLE TOOLS.


GENERAL SHIP YARD WORK.

The name Westinghouse  
is a guarantee.

**Westinghouse Electric**

& Mfg. Co., Pittsburg, Pa.

All Principal Cities in  
U. S. and Canada.



NORTH HALSTED ST. SCHERZER ROLLING LIFT BRIDGE, CHICAGO - OPEN.  
INVENTED BY WM. SCHERZER, C. E. PATENTED.

Information, preliminary sketches and estimates furnished to responsible parties, upon request, accompanied by the necessary data.

**THE SCHERZER ROLLING LIFT BRIDGE CO.,** 1616 Monadnock Block,  
CHICAGO, U. S. A.


**TWENTY-SEVEN  
OTHER LARGE  
SCHERZER  
Rolling Lift  
BRIDGES**

In successful use  
and under construc-  
tion at the present  
time.

**Varnish Paint** made with gum begins to deteriorate  
from the moment of its application.


**Our Varnish Paint Contains no Gum.**

**JOHN MAIR & SON,** 136 S. Delaware Ave.,  
PHILADELPHIA, PA.



IRON OR STEEL FORGINGS FINISHED COMPLETE, ROUGH MACHINED OR SMOOTH FORGED ONLY, OF ANY WEIGHT  
COUPLING LINKS AND PINS PRESSED WROUGHT IRON TURNBUCKLES. CAR IRON SPECIALTIES.





ADJUSTABLE BEVEL BAND SAW.

Will bevel both ways to 45 degrees.  
Power movement to change angles.  
Power feed in three directions.

ESTABLISHED 1869.

INCORPORATED 1896.

## ATLANTIC WORKS INCORPORATED,

Successors to Berry &amp; Orton Company.

2223-25-27 &amp; 29 Arch St., PHILADELPHIA, PA., U. S. A.

MANUFACTURERS OF

### MACHINERY FOR WORKING WOOD

FOR USE IN SHIP YARDS,  
CAR SHOPS, RAILROAD SHOPS.

SEND FOR CATALOGUE.

ESTIMATES FURNISHED.

Hollow Chisel Mortisers.

Car Sill Dressers.

## Thearle's Works

ON SHIP BUILDING.

STANDARDS IN  
ENGLAND AND SCOTLAND

KNOWN AND USED WHEREVER STEEL SHIPS ARE BUILT.

SEPARATE VOLUMES FOR PLATES.

"Ship Building in Iron and Steel." (Plates in separate volume.) \$5.25.

"Ship Building and Laying Off." (Plates in separate volume.) \$3.00.


"Theoretical Naval Architecture." (Plates in separate volume.) \$3.50.

"Practical Naval Architecture." (Two volumes.) \$3.00.

THE MARINE REVIEW PUB. CO., CLEVELAND.

## BEST FORM OF DRY DOCK.

Crandall's Modern Marine Railways.



SAFE. RAPID.  
BUILT OF STEEL OR WOOD  
ANY SIZE.

H. I. Crandall & Son Co.  
(INCORPORATED.)

Contracting  
Engineers,

EAST BOSTON,  
MASS., U. S. A.

## AMERICAN LINE

NEW YORK  
SOUTHAMPTON  
LONDON

CALLING AT CHERBOURG WESTBOUND.

Sailing From New York Every Wednesday at 10 A. M.

Steamers: { ST LOUIS, ST PAUL, NEW YORK,  
PHILADELPHIA, HAVERFORD.

Special Express Train from Southampton to London in one hour and forty minutes.  
Close connection at SOUTHAMPTON for Havre and Paris by  
special fast twin-screw Channel Steamers.

## RED STAR LINE

NEW YORK  
ANTWERP  
PARIS

Sailing Every Wednesday at 12 Noon.

Steamers: { \*VADERLAND, \*ZEELAND, KENSINGTON,  
SOUTHWARK, FRIESLAND.

\* New Twin-screw Steamers calling at Cherbourg eastbound.

One of the Shortest Routes to BELGIUM, HOLLAND, FRANCE, GERMANY,  
THE RHINE, SWITZERLAND and ITALY.

Send for  
"Facts for Travelers." International Navigation Company

Empire Building, 73 Broadway, New York.

305-307 Walnut St., Philadelphia. Cor. Dearborn & Washington Sts., Chicago.  
Ske Building, 89 State Street, Boston. Third and Pine Streets, St. Louis.  
306 F St., N.W., Washington, D. C. 10-12-14 Washington Ave., S., Minneapolis.  
30 Montgomery St., San Francisco.

PIERS: 14 &amp; 15 NORTH RIVER, FOOT OF FULTON ST., NEW YORK.

### Three Excellent Little Books FOR MARINE ENGINEERS.

"KEY TO ENGINEERING."

"WHAT AN ENGINEER SHOULD KNOW ABOUT ELECTRICITY."

"ENGINEER'S EPITOME."

Any one of these is worth a dollar. All three may be had for a dollar  
from the Marine Review Pub. Co., 418-419 Perry-Payne Building, Cleveland.

## NOW READY 200 PAGES

SEND 3 CENTS FOR OUR

## NEW CATALOGUE

OF BOOKS ON

### MARINE, ELECTRICAL, MECHANICAL ENGINEERING.

BE SURE TO WRITE CLEARLY YOUR FULL ADDRESS.

SPON & CHAMBERLAIN,  
12 Cortlandt Street, NEW YORK, U. S. A.

### ELECTRIC AUTOMATIC WHISTLE OPERATOR

will operate whistle from  
any distance with ease  
and certainty.

WHISTLE BLAST RECORDERS will prove invaluable in cases of collision or grounding  
through crowding or other causes. STEAM SHIP WHISTLES in all sizes to operate with  
steam or air. It will pay you to investigate our novel improvements. Catalogues mailed to  
captains, owners or engineers, upon application.

THE SIGNAL & CONTROL CO., 24-27 WEST STREET  
NEW YORK, U. S. A.

## Chas. E. & W. F. Peck,

58 William Street,  
NEW YORK CITY.C. T. BOWRING & CO., Ltd.  
5 & 6 Billiter Ave., London, E. C., Eng  
AND AT LLOYDS, LONDON.Royal Insurance Bldg.,  
CHICAGO, ILL.

## INSURANCE

ALL CLASSES OF MARINE INSURANCE  
BOTH CARGOES AND HULLS.

### GREAT LAKES REGISTER

INCORPORATED

COMBINED AND ISSUED IN CONNECTION WITH THE

### BUREAU VERITAS

INTERNATIONAL REGISTER OF SHIPPING.

GREAT LAKES REGISTER DESIRES TO ANNOUNCE THAT ITS RAT-  
INGS GO BEFORE THE LEADING UNDERWRITERS OF AMERICA  
ENGLAND AND FRANCE.

THE SERVICES OF ITS SURVEYORS MAY BE ENGAGED ON HULL AND CARGOES.

F. D. HERRIMAN, SURVEYOR GENERAL,  
320-322 PERRY-PAYNE BUILDING, CLEVELAND O



**THE CHAMPION RIVET CO.**Government Work  
a SpecialtyQuality:  
Highest Standard.  
Finish: Unexcelled.

CLEVELAND, O., U. S. A.

**VICTOR BOILER AND STRUCTURAL RIVETS.****SEIDLER-MINER ELECTRIC CO.**

DETROIT, MICH.

**Electric Lighting of Ships**



OUR SPECIALTY.

COMPLETE INSTALLATIONS OR RECONSTRUCTION,  
SAFE, SUBSTANTIAL AND EFFICIENT.


DEALERS IN

**Marine Electrical Supplies AND Special Fittings.**

Catalogue and Marine Rules on application.

**GASOLINE MARINE ENGINES**Suitable for all Boats from 3½ to 200 H.P.  
Over 100 in successful use.Also the well known and always  
reliable Wooters Gas or Gasoline  
Stationary Engines.**HOISTING ENGINES**Of all kinds and sizes, and  
for all purposes, especially  
for ship use.Docking and Hauling Engines  
and Wire Rope Windlasses.**AUTOMATIC TOWING MACHINES**Somewhat the cheapest, and  
altogether the best. Positively  
guaranteed.Automatic Fog Whistle Machines  
Steam Steering Engines.

FOR THESE AND OTHER WELL KNOWN SPECIALTIES ADDRESS ALL INQUIRIES TO.

**THE CHASE MACHINE CO. Engineers and Machinists, CLEVELAND, OHIO.****Helios-Upton Co.**

PEABODY, MASS.

Hot Water Thermometers  
and Thermometers for  
Mechanical Purposes.

Used by U. S. Navy in all New Ships.

Eighty of them furnished  
the Japanese Cruisers  
"Kasagi" and "Chitose."

SEND FOR BULLETIN No. 40 A.

**Shepard's Horse Power Scale.**

FOR DETERMINING

HORSE POWER,  
SIZE OF CYLINDERS,  
DENSITY, TEMPERATURE  
AND LATENT HEAT OF STEAM.

HAS SOLD IN GREAT NUMBERS AT \$1 EACH.

OFFERED  
AS A PREMIUM  
WITH ONE YEAR'S  
SUBSCRIPTION  
TO THE  
MARINE REVIEW  
AT \$3.**DELTA METAL**THE PHOSPHOR BRONZE SMELTING CO. LIMITED,  
2200 WASHINGTON AVE., PHILADELPHIA.  
"ELEPHANT BRAND PHOSPHOR-BRONZE"  
INGOTS, CASTINGS, WIRE RODS, SHEETS, ETC.  
— DELTA METAL —  
CASTINGS, STAMPINGS AND FORGINGS.  
ORIGINAL AND SOLE MAKERS IN THE U.S.**PROPELLERS.***The Martin-Barriss Co.*

IMPORTERS AND MANUFACTURERS OF

*Mahogany, White Mahogany,*  
AND ALL NATIVE CABINET WOODS.HIGH GRADES OF KILN DRIED WOODS FOR  
CABIN WORK AND INSIDE TRIM.*White Oak Timbers and Plank,*CONSTANTLY ON HAND AND SAWED TO ORDER  
ON SHORT NOTICE.

654 Seneca Street,

Cleveland, O.

**MacKinnon Manufacturing Co.**

Boiler Makers, Founders and Machinists.

Marine Boilers, Engines and Shipyard Machinery. Most  
powerful set of Hydraulic Slings on the Lakes. Best  
Towing and Speed Propeller Wheels made

SPECIALTY SMALL YACHT WHEELS.

Works and Office, 224-230 N. Water Street, BAY CITY, MICH.

**S. F. HODGE & CO.**MARINE ENGINES,  
PROPELLER WHEELS,  
DECK HOISTERS,  
MARINE REPAIRS.320 ATWATER STREET,  
DETROIT, MICH.



## DIXON'S GRAPHITE PIPE JOINT COMPOUND

Enables you to MAKE A TIGHTER JOINT than you can possibly make with red lead. You can do it easier, and parts can be separated at any time without breaking anything. Send for sample and circular.

JOSEPH DIXON CRUCIBLE COMPANY, JERSEY CITY, N. J.

STEERING GEAR BEARINGS,  
AMMUNITION HOIST BEARINGS,  
CAPSTAN BEARINGS,  
WINDLASS AND WINCH BEARINGS,

REQUIRING  
NO OILING  
OR  
GREASING

Also Anchor, Davit and Cargo Block Bushings,  
Bushings for Sheaves on Wrecking Derricks,  
Washers and Collars for Thrust Bearings.

THE GRAPHITE LUBRICATING CO.,  
BOUND BROOK, N. J., U. S. A.



**The Wonderful TRIEDER BINOCULAR**

Has 8 to 10 times the power of the old-style Field and Opera Glass.

**IMPORTANT**  
Owing to the completion of the facilities to mount our **Trieder Binoculars** at the New York factory the prices will henceforth be as follows, magnifying

3X	6X	9X	12X
\$38	\$46	\$54	\$62

DISCRIPTIVE CATALOGUE FREE FROM YOUR OPTICIAN, OR FROM  
C. P. GOERZ OPTICAL WORKS  
52 E. Union St., New York.

MAIN OFFICE: BERLIN, GERMANY  
BRANCH OFFICES:  
LONDON, ENGLAND  
PARIS, FRANCE  
NEW YORK, U.S.A.  
CHICAGO, ILL.  
PHILADELPHIA, PA.  
ST. LOUIS, MO.  
BOSTON, MASS.

As seen with the TRIEDER BINOCULAR.

Pure Feed Water.  
Clean Boilers.  
Lower Fuel Bills.


Reynolds  
Feed Water Heater  
and Purifier

Suited to both Marine  
and Stationary Boilers.

Prevents formation of  
scale, removes old  
scale, and reduces fuel  
bills.

In use on a number of steam  
vessels on the Great Lakes.

H. J. REYNOLDS,  
721 PERRY-PAYNE BLDG.,  
CLEVELAND, O.



Catalogues  
Mailed  
Upon  
Application

NEW PATENT  
STOCKLESS  
ANCHOR

MADE BY THE  
International Anchor Co.  
CLEVELAND, O.  
BINGHAMTON, N. Y.

## BALDT PATENT STOCKLESS ANCHOR

Made of the finest quality of open-hearth steel, and constructed on the ball and socket principle. Many points of superiority over ordinary stockless anchors.

BALDT ANCHOR COMPANY,  
CHESTER, PA.

WALTER MILLER PERRY-PAYNE BUILDING,  
CLEVELAND, O.

Representative for the Great Lakes  
We keep a large number of Anchors  
in stock.



## DIXON'S Lubricating Graphite

Is fully explained in an INTERESTING AND INSTRUCTIVE PAMPHLET which is FREE to all interested. It will pay all Engineers and Machinists to SEND FOR IT.

JOSEPH DIXON CRUCIBLE COMPANY, JERSEY CITY, N. J.



Established 1837.  
Incorporated 1900.

**Alfred Hale Rubber Co.**  
SUCCESSORS TO ALFRED HALE & CO

**DIVING APPARATUS**  
OUR SPECIALTY.

Repair Cloth.  
Rubber Cement.

OFFICE AND FACTORY:  
387 E. Eighth St.,  
SO. BOSTON, MASS.

## THE MARINE DEPARTMENT

of the Geo. F. Blake Mfg. Co. take pleasure in announcing that they were awarded the Grand Prix at the recent Exposition at Paris, for their special exhibit of Marine Pumps, Condensers, etc.

Send for new Catalogue of Marine Specialties.

THE GEO. F. BLAKE MFG. CO., 91 Liberty St., N. Y. City.

**HENRY R. WORTHINGTON, PUMPING  
MARINE AIR AND FEED PUMPS  
A SPECIALTY.**

BOSTON.  
CHICAGO.  
PHILADELPHIA.  
ST. LOUIS.  
BUTTE.

**WATER METERS.**

120 Liberty St., NEW YORK.

CLEVELAND.  
PITTSBURG.  
ATLANTA.  
SAN FRANCISCO  
NEW ORLEANS.



For Decks and all other Seams,  
Weather Checks,  
Floors, Skylights, Etc.

AND ELASTIC SEAM PAINT  
WHITE, BLACK AND COLORS,

IS BEING USED BY

U. S. ARMY TRANSPORTS, AMERICAN LINE, ATLAS LINE,  
OCEAN STEAMSHIP CO., OLD DOMINION STEAMSHIP CO.,  
FIRE BOAT NEW YORKER, PANAMA RAILROAD STEAMSHIP CO.,  
L. BOYER'S SON'S TRANSPORTATION CO.,  
NEW YORK & CUBA MAIL STEAMSHIP CO., (WARD LINE),  
MERRITT & CHAPMAN D. & W. CO. PENNSYLVANIA RAILROAD CO., Etc.

TO BE BOUGHT OF

Geo. B. Carpenter & Co., Chicago, Ill. Jennison Hardware Co., Bay City, Mich.  
H. Steffens, 337-339 Fell St., Baltimore. J. F. Donahue & Co., Sandusky, O.  
E. A. Burnside, Point Pleasant, W. Va. The Chas. F. Beebe Co., Portland, Ore.  
Cook & Co., Tacoma, Wash. Anthony S. Morse, 210 Commercial St., Boston.  
Elisha Webb & Sons, 108 S. Delaware, Philadelphia.  
Uhler & Co., Seventh & K Sts., Washington, D. C.

And all marine hardware stores in New York and Brooklyn.

Samples sent on receipt of 30 cents in stamps. An agent wanted in each seaport town.

**COLE & KUHL'S, Sole Manufacturers,**  
Office and Factory, foot of 24th St. [Mention this Paper.] **BROOKLYN, N. Y.**

**H. G. TROUT,  
KING IRON WORKS,  
BUFFALO, N. Y.**

MANUFACTURERS OF


**TRIPLE EXPANSION,  
FORE-AND-AFT**

AND  
**STEEPLE COMPOUND  
MARINE ENGINES,**


High and Low Pressure Engines  
Sectional Propellers,  
Tug and Yacht Wheels.

Cowles Aluminum and Manganese  
Bronze Propeller Wheels.

These Wheels are noted for their extra speed, towing power and proportionate saving of coal.  
Prices Quoted on Application.







## Evaporating and ... Distilling Apparatus

FOR MARINE PURPOSES.

The Most Efficient, Compact, Accessible  
and Lightest Made.

GENERAL ENGINEERING SPECIALTIES  
AND SUPPLIES.

James Reilly Repair & Supply Co.,  
229 and 230 West St., NEW YORK.

SIXTH REVISED EDITION.

## Scott's Coast Pilot for 1901.

Great Lakes and Connecting Waters,

AT \$1.50.

For sale by MARINE REVIEW PUB. CO.



## Queen City Patent Hydraulic Steerer.

The Best and Most  
Reliable.

Generates No Heat  
in Pilot House.

Has Large Hand  
Wheel.  
Can be Changed from  
Power to Hand  
Steering Instantly.  
A Favorite with Pilots.  
Send for References.

Queen City Engineering Co., Buffalo, N. Y.

## ALFRED B. SANDS & SON

MARINE PLUMBERS  
AND MANUFACTURERS OF  
Marine Plumbing Specialties.



Marine Water Closet for either above or  
below water line.

Folding Lavatories, Ventilators, Pumps,  
Tanks, &c., &c.

134 BECKMAN ST., NEW YORK.

## LIDGERWOOD IMPROVED HOISTING ENGINES.

OVER 17,500 IN USE.

## ELECTRIC HOISTS


Specially adapted for Docks, Warehouses  
and Steamships.....

Simple, Light and Compact.

SEND FOR  
CATALOGUE

LIDGERWOOD MFG. CO.,

96 Liberty Street, NEW YORK.



## SHERIFFS STEAM STEERER

MADE IN TWO SIZES.

Easy to adjust, and can be handled by  
any one.

This steerer can be arranged to work in  
pilot house or in after part of vessel.  
None sold without a quadrant.  
Will be sold on approval.

MANUFACTURED BY

SHERIFFS MFG CO.,

26-130 Barclay St. MILWAUKEE, WIS.



# THE TOPOPHONE

\$25.00



Prevents Marine  
Disasters in Fogs.

Write for circular to

J. B. COLT CO.,

Room 7, 21 Barclay St., N. Y.

# MARINE CHAIN

OF ALL KINDS.

*Ships Cables, Dredge Chains,  
Stud Link and Marine Railway Chains,  
Steam Shovel Chains, Boom Chains, Etc.*

CERTIFICATE OF TEST FURNISHED.

## STANDARD CHAIN CO.


PITTSBURGH, PA.

## Bureau of Shipping Information.

Such is the office of the Marine Review, Cleveland. We try to  
keep in touch with all that is going on among ship owners and ship  
builders and never tire of answering inquiry on this score from ad-  
vertising patrons. Write us.

THE MARINE REVIEW PUB. CO., CLEVELAND, O.

## Sellers' Restarting Injector



A strictly first  
class machine at  
moderate cost.

Perfectly auto-  
matic, has wide  
range of capaci-  
ties, and raises  
water promptly  
with hot or cold  
pipes.

Very simple,  
has few parts  
and is easily  
repaired.

All parts interchangeable, made of  
the best bronze, and the workman-  
ship is perfect. Send for special  
catalogue descriptive of this Injector.

JENKINS BROTHERS, Selling Agents  
NEW YORK, BOSTON, PHILA., CHICAGO

## CHAS. CORY & SON,

Manufacturers of the  
Mechanical and Electric  
Marine Telegraph,

Electrical  
Helm Indicators  
Electric Call  
Bells.

Engine Bells and  
Brass Work of  
all descriptions,  
Shrieking and  
Siren Whistles.

278 DIVISION ST.,  
NEW YORK CITY.





## THE BABCOCK & WILCOX Co.

HAVE EQUIPPED THE FOLLOWING  
LAKE VESSELS WITH THEIR  
FORGED STEEL WATER TUBE  
BOILERS:

ZENITH CITY,  
QUEEN CITY,  
EDNA G.,  
CRESCENT CITY,  
SUPERIOR CITY,  
EMPIRE CITY,

ALEX McDOUGALL,  
PRESQUE ISLE,  
MATAAFA,  
MAUNALOA,  
MALIETOA,  
JOHN W. GATES,

JAMES J. HILL,  
ISAAC L. ELLWOOD,  
WM. EDENBORN,  
W. S. GRATTAN,  
HARVARD,  
LAFAYETTE,

CORNELL,  
PRINCETON,  
RENSSELAER,  
PARAGUAY,  
ASUNCION.

BOILERS NOW UNDER CONSTRUCTION FOR

### The Babcock & Wilcox Co.,

85 LIBERTY ST.,

NEW YORK.

U. S. MONITOR WYOMING,  
U. S. CRUISER CINCINNATI,  
U. S. CRUISER RALEIGH,  
U. S. CRUISER TACOMA,  
U. S. CRUISER GALVESTON,  
U. S. CRUISER CHATTANOOGA,  
U. S. CRUISER DENVER,  
U. S. CRUISER DES MOINES,  
U. S. CRUISER CLEVELAND,  
AND SEVERAL LARGE VESSELS FOR THE PACIFIC COAST.

## THE BUFFALO DRY DOCK CO.

GANSON STREET AND BUFFALO RIVER.

Operating Four Docks, Sixty-ton Shear Legs, and in every way Equipped

WITH MODERN MACHINERY FOR

### Prompt and Economical Repairs

AND FOR THE BUILDING OF STEEL AND WOODEN SHIPS.

OFFICE, GANSON ST., TELEPHONE 515 SENECA.

Edward Smith, President, Tel. 279 Seneca.  
Edward Smith, Residence Tel. 209 Bryant.

Geo. B. Drake, Ass't to President, Residence Tel. 798 Bryant.

## THE ROBERTS BOILER CO.

HAS BUILT OVER 1000 BOILERS TO DATE

For Launches, Yachts, Passenger and Freight Steamers,  
Dredges, Tugs, Stern-wheelers, Canalers;  
Also for Navy Department, War Department, Treasury Department,  
Light-House Board and Revenue Cutter Service;  
Also for N. Y. Dock Department and U. S. Supervisor, Harbor of N. Y.

### SAFETY AND ECONOMY.

NEVER KILLED A MAN OR HAD A SERIOUS ACCIDENT. \$250,000 capital. Works covering 29,000 square feet of ground. Never had a boiler returned on account of dissatisfaction. Every boiler warranted. All material made specially for our use. All boilers tested at 500 pounds hydrostatic pressure and 250 pounds of steam before shipping. Workmanship strictly first-class. All joints screwed and reliable. No expanded joints. State your requirements and we will furnish specifications. Correspondence solicited.


### THE ROBERTS SAFETY WATER TUBE BOILER CO.,

Works, Red Bank, N. J. 39 and 41 Cortlandt St., NEW YORK CITY.

TELEPHONE: { NEW YORK OFFICE, 599 CORTLANDT.  
OFFICE OF WORKS, 49 RED BANK, N. J.

Cable Address,  
"BRUNIVA, NEWYORK."

## THE "TAYLOR" YACHT BOILER



Has held the record five seasons on the fastest yacht on the great lakes.

Guaranteed against  
Rupture of Tubes.

Will not Prime in the  
Roughest Sea.

MANUFACTURED BY

Taylor Water Tube Boiler Co.

Office, Corner Reopelle and  
Franklin Streets,

DETROIT, MICH., U. S. A.

ALL THE NAVIES OF THE LEADING GOVERNMENTS  
OF THE WORLD USE

## The Niclausse Water Tube Boiler,

ADOPTED BY THE NAVIES OF

UNITED STATES,	RUSSIA,	SPAIN,
ENGLAND,	ITALY,	Argentine Republic,
FRANCE,	GERMANY,	CHILI.

We have now in course of construction at our Works 60,000 H. P. Niclausse Boilers for the following war vessels:

U. S. Monitor CONNECTICUT,	{ Building at the Ship Yard of the Bat Iron Works, Bath, Me.
U. S. Battleship MAINE,	{ Building at Wm. Cramp & Sons Ship Yards, Philadelphia.
Russian Battleship RETVIZAN, Russian Cruiser VARIAG,	

## THE STIRLING COMPANY,

Write for Descriptive Matter.

General Offices Pullman Building, Chicago, Ill.

## ALMY'S PATENT

SECTIONAL

## Water Tube Boilers.


NOW USED IN

Thirty Passenger Boats and 100 Steam Yachts  
ranging from 50 to 250 feet in length,  
U. S. Torpedo Boat "Stiletto,"  
Numerous Small Launches and Stationary Boiler  
also giving most excellent results.


## ALMY WATER-TUBE BOILER CO.,

178-184 Allens Avenue,  
near Rhodes St.

PROVIDENCE, R. I.








## BUFFALO STEEL PLATE FANS

STEAM OR ELECTRIC.

FOR  
Forced Combustion  
or Ship Ventilation.

? CATALOGUE ?

BUFFALO  
FORGE COMPANY,  
BUFFALO, N. Y.



# The Shipowners Dry Dock Co.

## CHICAGO.

Repairs to  
Steel and Wooden Vessels.

Three Docks at Halsted  
Street and North Branch.

OFFICES 21 AND 23 SHERMAN STREET.

OFFICE TELEPHONE, HARRISON 1020.  
YARD TELEPHONE, NORTH 759.

W. W. WATTERSON, SUPT.



### ASHTON

CAM LEVER POP SAFETY VALVES  
AND NON-CORROSIVE STEAM GAGES

give highest efficiency and durability. Specify them  
and get the best.

THE ASHTON VALVE CO.,

BOSTON, NEW YORK  
AND CHICAGO, U. S. A.



## GENERAL ELECTRIC COMPANY'S Projectors.



HAND, PILOT-HOUSE OR  
ELECTRICAL CONTROL.

Operated from direct-current  
incandescent lamp circuits.

Write for Catalogue No. 1025.

GENERAL OFFICE, SCHENECTADY, N. Y.

SALES OFFICES IN ALL LARGE CITIES.

18-INCH PROJECTOR.  
PILOT HOUSE CONTROL.

### EUROPE

#### ARE YOU GOING?

If so, sail from BOSTON on one  
of the Fast Steamers of the

### DOMINION LINE

Crossing the Atlantic under 7 days.

S. S. Commonwealth, (new 13,000 tons, twin screw); S. S. New England, 11,600 tons, twin  
screw; S. S. Canada, 9,000 tons, twin screw. Sailing from B. & M. R. R. docks, Boston,  
Wednesdays, for Queenstown and Liverpool.

PORTLAND-LIVERPOOL SERVICE S. S. Dominion, S. S. Vancouver, S. S. Cambrian.  
Short sea passage. For passage, plans, and informa-  
tion regarding these services, apply to or address local agents or

RICHARDS, MILLS & CO., 77 to 81 State Street, BOSTON.

## THE BOURNE-FULLER CO.

CLEVELAND O.

BAR IRON.

PIC IRON.

ARCHES AND STRAPS FOR WOODEN VESSELS.


BOILER RIVETS. BOILER TUBES. BRACE IRON.  
IRON AND STEEL SHEETS. MACHINERY AND TOOL STEEL.

BESSEMER AND OPEN HEARTH STEEL.

SHIP PLATES, BOILER PLATES, SHIP RIVETS.  
BEAMS, CHANNELS, ANGLES, BARS, AND OTHER SHAPES.  
BILLETS, BLOOMS AND FORGINGS.

"BYERS" FULL WEIGHT WROUGHT IRON PIPE.

## CROSBY STEAM GAGE AND VALVE CO.



CROSBY POP SAFETY VALVES, Locomotive,  
Marine and Stationary.  
CROSBY WATER RELIEF VALVES, for Pumps,  
Hydrants, etc.  
CROSBY IMPROVED STEAM PRESSURE GAGES  
CROSBY STEAM ENGINE INDICATORS, with  
Sargent's Electrical Attachment for taking any  
number of Diagrams simultaneously.

The Original SINGLE BELL CHIME WHISTLES.  
BRANDEN PUMP VALVES; rubber with wire-coil  
insertion.  
BOSWORTH FEED-WATER REGULATOR, PAT-  
ENT GAGE TESTER, and many other special-  
ties in Steam Lines.

Main Office and Works: Boston, Mass.

Stores; Boston, New York, Chicago, and London Eng.

WE WILL REPAIR YOUR STEAM FITTINGS PROMPTLY.